

02-8802-07-SI  
REV. NO. 1

**FINAL DRAFT  
SITE INSPECTION REPORT  
JOHN HASSALL  
WESTBURY, NEW YORK**

**PREPARED UNDER**

**TECHNICAL DIRECTIVE DOCUMENT NOS. 02-8802-07, 02-8901-25  
CONTRACT NO. 68-01-7346**

**FOR THE**

**ENVIRONMENTAL SERVICES DIVISION  
U.S. ENVIRONMENTAL PROTECTION AGENCY**

**FEBRUARY 17, 1989**

**NUS CORPORATION  
SUPERFUND DIVISION**

**SUBMITTED BY**

  
\_\_\_\_\_  
**JOSEPH MAYO  
PROJECT MANAGER**

**REVIEWED/APPROVED BY**

  
\_\_\_\_\_  
**EDWARD L. LEONARD  
SITE MANAGER**

  
\_\_\_\_\_  
**RONALD M. NAMAN  
FID OFFICE MANAGER**

333193



**SITE NAME:** John Hassall  
**ADDRESS:** Cantiague Rock Road  
Westbury, New York 11590

**EPA ID NO:** NYD002045417  
**LATITUDE:** 40° 46' 30" N  
**LONGITUDE:** 73° 33' 10" W

## **1.0 SITE SUMMARY**

John Hassall is located in the village of Westbury, Nassau County, New York. The facility is an active specialty nail and fastener manufacturer, operating at the present site since 1953. There are five buildings and a recharge basin on approximately 7.5 acres. The buildings include the main production building, the spec-com building, the treatment building, the warehouse, and a shed. Most of the warehouse is leased to Canon Inc.; only a small portion of the southern end is used for storage by John Hassall. The site is situated between the Long Island Expressway and the Northern State Parkway, in a small industrial/commercial area.

The site is on the western edge of Oyster Bay Township; North Hempstead Township is 0.5 mile to the west, and Hempstead Township is 1.4 miles to the south. This is a densely populated suburban area with approximately 12,721 people within 1 mile, 45,886 people within 2 miles, and 109,534 people within 3 miles of the site.

There are two areas of concern. The first is the recharge basin, which was utilized to discharge untreated and treated industrial wastewater to the surficial aquifer, from approximately 1959 to 1982. This wastewater contained metals, cyanides, solvents, and oil and grease. The other is the area around the underground holding tanks, where an oil and grease spill occurred in December 1987.

The following enforcement/regulatory actions have been taken against John Hassall:

- Prehearing Conference on May 15, 1980 with the New York State Department of Environmental Conservation (NYSDEC) and Nassau County Health Department. John Hassall will voluntarily comply with the compliance schedule for upgrading and modifying its wastewater treatment system.
- Consent Agreement and Consent Order (II RCRA- 83-0249) issued January 22, 1984 by the U.S. EPA. John Hassall must submit documentation to establish financial assurance for closure, and where appropriate, postclosure monitoring. In addition, John Hassall must establish financial responsibility for bodily injury and property damage to third parties caused by sudden accidental occurrences arising from the operation of the facility. A \$2,000.00 civil penalty was imposed.
- Reclassification of hazardous waste facility issued August 26, 1985 by the NYSDEC. John Hassall was reclassified from an interim status hazardous waste treatment, storage, or disposal facility to a generator only status.

On March 9, 1988, Region 2 FIT conducted a site inspection. One soil sample was collected from the spill area, and seven sediment samples were collected from the recharge basin. Analytical results indicate the presences of volatiles, semivolatiles, pesticides, polychlorinated biphenyls (PCBs), metals, and cyanide.

Ref. Nos. 1, 2, 3, 4, 5, 8, 10, 12, 24, 25, 27

## **2.0 SITE INSPECTION NARRATIVE**

### **2.1 EXISTING ANALYTICAL DATA**

Since 1975, John Hassall has monitored its own treated wastewater, through a New York State approved laboratory. From 1975 to 1982, the treated wastewater was monitored prior to recharge basin discharge, as required by its SPDES Permit (NY0026287). During this period, the treated wastewater routinely violated SPDES discharge limitations for total chromium, copper, nickel, iron, and oil and grease. Since 1982, the treated wastewater has been monitored per batch, to meet Nassau County Sewer Ordinance, prior to being discharged into the Nassau County Sewer System. At present, John Hassall is required to analyze for aluminum, hexavalent chromium, total chromium, chloride, copper, iron, silver, sulfide, fluoride, chemical oxygen demand, NH<sub>3</sub>-nitrogen, total dissolved solids, oil and grease, and pH.

In August 1988, the Nassau County Health Department (NCHD) collected soil samples from the area of the December 1987 spill. The analyses did not detect volatiles; however, several unidentifiable compounds were detected.

Ref. Nos. 3, 6, 7, 11, 26

### **2.2 WASTE SOURCE DESCRIPTION**

A recharge basin is located in the southwest corner of the site. This 51,000-cubic-foot basin (approximately 60 by 85 by 10 feet) received industrial wastewater for groundwater discharge, from about 1959 to 1982. The wastewater consisted of process solutions and rinse water from the deburring, burnishing, and cleaning operations. These solutions and waters contained metals, cyanide, solvents, and oil and grease. In 1974 cyanide use was discontinued, and a treatment system was installed to pretreat wastewater prior to groundwater discharge. Presently, the recharge basin is unused for wastewater discharge, but it may still be used for storm water runoff from on-site storm drains and roof gutters.

In December 1987 a spill occurred from an underground holding tank, associated with the wastewater treatment system. Approximately 50 to 100 gallons of oil and grease contaminated the soil in the immediate vicinity, and possibly flowed into the northeast corner of the recharge basin. The soil in the immediate vicinity was removed, and replaced with fresh fill. Presently, John Hassall is conducting an investigation into the condition of the underground tanks, under the guidance of the NCHD. Leak testing was performed, but the results were inconclusive. However, the tanks are assumed to be in unsound condition. Approximately four of the tanks are currently out of service. Further testing will be conducted to determine the condition of all tanks, and if required, an extent of contamination study will be conducted.

Ref. Nos. 8, 9, 10, 12, 13, 24, 26



### 2.3 GROUNDWATER ROUTE

Groundwater samples were not collected during the site inspection conducted on March 9, 1988; therefore, an observed release cannot be evaluated. However, the potential exists that groundwater contamination has occurred. For over 20 years John Hassall discharged both untreated and treated wastewater to the groundwater via an on-site recharge basin. In addition, the underground holding tanks are assumed to be in unsound condition.

Three sole source aquifers underlie the site: the Lloyd aquifer, the Magothy aquifer, and the upper glacial aquifer. The Magothy aquifer and the upper glacial aquifer are hydraulically connected and form the aquifer of concern. The Magothy aquifer consists of beds and lenses of light gray, fine to coarse sand with some interstitial clay. The upper glacial aquifer consists mainly of stratified beds of fine to coarse sand and of sand and gravel, but also contains thin beds of silt and clay interbedded with coarse-grained material. The deposits of the upper glacial aquifer are highly permeable ( $> 10^{-3}$  cm/sec) and form the unsaturated zone. Depth to groundwater is approximately 68 feet; groundwater flows in a south/southeasterly direction.

Potable water in the area is supplied by municipal wells drawing from the aquifer of concern. At least five water districts are located within 3 miles of the site, utilizing 42 wells and serving approximately 152,200 people. The closest well is located approximately 900 feet northeast of the site, and is owned by the Jericho Water District. The water districts within 3 miles of the site are as follows:

- The Town of Hempstead, Department of Water serves approximately 12,000 people, utilizing two wells within 3 miles of the site. The wells are located in the Magothy aquifer, and are 535 feet and 598 feet deep.
- The Hicksville Water District serves approximately 50,000 people, utilizing 19 wells within 3 miles of the site. The wells are located in the Magothy aquifer, and range in depth from 419 feet to 637 feet.
- The Village of Old Westbury, Department of Public Works serves approximately 3,200 people, utilizing three wells within 3 miles of the site. The wells are located in the Magothy aquifer, and range in depth from 478 feet to 610 feet.
- The Westbury Water District serves approximately 24,000 people, utilizing 10 wells within 3 miles of the site. The wells are located in the Magothy aquifer, and range in depth from 260 feet to 600 feet.

- The Jericho Water District serves approximately 63,000 people, utilizing eight wells within 3 miles of the site. The wells are located in the Magothy aquifer, and range in depth from 453 feet to 615 feet.

The net mean annual precipitation for this area is approximately 14.5 inches.

Ref. Nos. 14, 15, 16, 17, 18, 19, 20, 22, 23, 25, 26, 27

## **2.4 SURFACE WATER ROUTE**

The site is relatively flat and is located in a small industrial/commercial area. Site elevation is approximately 157 feet above mean sea level. The surrounding topography gradually slopes from northeast to southwest. There are several perennial ponds located approximately 1 to 2 miles northwest of the site. However, there is no surface water migration route between the site and these bodies of water. Surface water runoff drains from the site via storm drains, and enters a recharge basin where it infiltrates to the surficial aquifer.

Ref. Nos. 8, 21

## **2.5 AIR ROUTE**

No readings above background were detected in the ambient air on the OVA or HNu prior to disturbance of the waste source during the site inspection on March 9, 1988. However, readings up to 17 ppm and 15 ppm were noted in the sediment and soil, while samples NYEF-S7 and NYEF-S8, respectively, were collected.

It is not known if there are historic landmarks within view of the site.

Ref. No. 8

## **2.6 ACTUAL HAZARDOUS CONDITIONS**

Analytical results of sediment and soil samples collected during the site inspection conducted on March 9, 1988, indicated the presence of contaminants which are directly attributable to the facility. Section 4.0 provides a discussion of the site inspection sampling results.

The potential exists that groundwater contamination has occurred. John Hassall discharged industrial wastewater to the groundwater via an on-site recharge basin. This wastewater contained metals, cyanide, solvents, and oil and grease. From approximately 1959 to 1975, untreated wastewater was discharged to the groundwater. From 1975 to 1982, treated wastewater was discharged to the groundwater. This treated wastewater routinely violated SPDES discharge limitations for total chromium, copper, iron, nickel, and oil and grease. In addition, the underground holding tanks are assumed to be in unsound condition.

No other actual hazardous conditions pertaining to human or environmental contamination have been documented. Specifically:

- Contamination has not been documented either in organisms in a food chain leading to humans or in organisms directly consumed by humans.
- There have been no documented observed incidents of direct physical contact with hazardous substances at the facility involving a human being (not including occupational exposure) or a domestic animal.
- There have been no documented incidents of damage to flora or to fauna that can be attributed to the hazardous material at the facility.
- There is no documented contamination of a sewer or storm drain.
- A fire marshall has not certified that the site poses a significant threat of fire or explosion.


Ref. Nos. 9, 10, 11, 24, 25, 26

### **3.0 MAPS AND PHOTOS**

#### **JOHN HASSALL WESTBURY, NEW YORK**

#### **CONTENTS**

Figure 1:	Site Location Map
Figure 2:	Site Map
Figure 3:	Sample Location Map
Exhibit A:	Photograph Log




(QUAD) HICKSVILLE, N.Y.

**SITE LOCATION MAP**  
**JOHN HASSALL, WESTBURY, N.Y.**


SCALE: 1" = 2000'

**FIGURE 1**





**SITE MAP**  
**JOHN HASSALL, WESTBURY, N.Y.**  
(NOT TO SCALE)



NOTE: ALL SAMPLE NUMBERS ARE PRECEDED BY NYEF.

**SAMPLE LOCATION MAP**  
**JOHN HASSALL, WESTBURY, N.Y.**

( NOT TO SCALE )

**FIGURE 3**



EXHIBIT A  
PHOTOGRAPH LOG  
JOHN HASSALL  
WESTBURY, NEW YORK  
MARCH 9, 1988



JOHN HASSALL  
WESTBURY, NEW YORK  
MARCH 9, 1988  
PHOTOGRAPH INDEX

<u>Photo Number</u>	<u>Description</u>	<u>Time</u>
1P-12	Company sign on main manufacturing building	1037
1P-1	P. Solinski obtaining sediment sample NYEF-S1.	0838
1P-2	P. Solinski obtaining sediment sample NYEF-S2.	0854
1P-3	P. Solinski obtaining sediment sample NYEF-S3.	0858
1P-4	S. Lenczyk obtaining sediment sample NYEF-S4.	0908
1P-5	P. Solinski obtaining sediment sample NYEF-S5.	0920
1P-6	P. Solinski obtaining sediment sample NYEF-S6.	0932
1P-8	P. Solinski obtaining sediment sample NYEF-S7.	1027
1P-7	P. Solinski obtaining soil sample NYEF-S8.	1015
1P-9	Looking west at recharge basin	1034
1P-10	Looking north at recharge basin.	1035
	All photographs taken by E.L. Leonard.	

JOHN HASSALL, WESTBURY, NEW YORK




JP-12

March 9, 1988

1037

Company sign on main manufacturing building.

JOHN HASSALL, WESTBURY, NEW YORK



1P-1

March 9, 1988 0838  
P. Solinski obtaining sediment sample NYEF-S1.




1P-2

March 9, 1988 0854  
P. Solinski obtaining sediment sample NYEF-S2.



JOHN HASSALL, WESTBURY, NEW YORK



1P-3

March 9, 1988 0858  
P. Solinski obtaining sediment sample NYEF-S3.



1P-4

March 9, 1988 0908  
S. Lenczyk obtaining sediment sample NYEF-S4.

JOHN HASSALL, WESTBURY, NEW YORK



1P-5

March 9, 1988

0920

P. Solinski obtaining sediment sample NYEF-S5.



1P-6

March 9, 1988

0932

P. Solinski obtaining sediment sample NYEF-S6.



JOHN HASSALL, WESTBURY, NEW YORK



1P-8

March 9, 1988 1027  
P. Solinski obtaining sediment sample NYEF-S7.



1P-7

March 9, 1988 1015  
P. Solinski obtaining soil sample NYEF-S8.



JOHN HASSALL, WESTBURY, NEW YORK



1P-9

March 9, 1988  
Looking west at recharge basin.

1034



1P-10

March 9, 1988  
Looking north at recharge basin.

1035

#### 4.0 SITE INSPECTION SAMPLING RESULTS

On March 9, 1988, Region 2 FIT conducted a site inspection. One soil sample was collected from the spill area, and seven sediment samples were collected from the recharge basin. All samples were analyzed for Target Compound List (TCL) substances. Sample locations are presented in Figure 3, Section 3.0.

Organic analytical results of soil sample NYEF-S8 indicate that no volatiles, semivolatiles, or PCBs are present above the contract-required quantitation limits (CRQLs). However, pesticides are present at estimated values, and include 4,4'-DDE, 4,4'-DDD, and 4,4'-DDT at concentrations of 550, 450, and 1,500 ug/kg, respectively. Organic analytical results of the sediment samples indicate the presence of volatiles, semivolatiles, pesticides, and PCBs. Volatiles are present above the CRQLs in samples NYEF-S3, NYEF-S5, and NYEF-S6, and include trichloroethene and toluene at concentrations up to 15 and 21 ug/kg, respectively. Semivolatiles were detected in all sediment samples; however, only in samples NYEF-S1, NYEF-S2, NYEF-S3, and NYEF-S7 were they detected above the CRQLs. Benzoic acid was detected in sample NYEF-S2 at a concentration of 6,000 ug/kg. Eleven polycyclic aromatic hydrocarbons were detected in these samples at a range of 440-2,800 ug/kg. Pesticides were detected in all the sediment samples, and include 4,4'-DDE, 4,4'-DDT, and chlordane at concentrations up to 29, 120, and 260 ug/kg, respectively. PCBs were detected in three sediment samples: Aroclor-1254 in NYEF-S5 at a concentration of 210 ug/kg, and Aroclor-1260 in NYEF-S2 and NYEF-S3 at concentrations of 1,100 and 1,300 ug/kg, respectively.

Inorganic results indicate above-background levels of several metals and cyanide in sediment samples NYEF-S1, NYEF-S2, NYEF-S3, NYEF-S4, and NYEF-S7. The compounds detected include aluminum, chromium, copper, lead, nickel, zinc, and cyanide at concentrations up to 16,700, 151 (estimated value), 250, 145, 206, 167 and 0.63 mg/kg, respectively. Aluminum was the only inorganic compound detected above background levels in soil sample NYEF-S8 at a concentration of 14,800 mg/kg.



## **5.0 CONCLUSIONS AND RECOMMENDATIONS**

After review of all information gathered during the site inspection, John Hassall is recommended for further action as a high priority. The only route of concern is the groundwater migration route. The site overlies three sole source aquifers, which are the only source of potable water for the area. Municipal wells within 3 miles of the site serve approximately 152,200 people, with the closest well about 900 feet northeast. As background information indicates and analytical data support, contaminants are present on site, and a strong potential exists that groundwater contamination has occurred.

## 6.0 REFERENCES

1. General Sciences Corporation, Graphical Exposure Modeling Systems (GEMS). Landover, Maryland, 1986.
2. NCHD memorandum from J. Schechter (NCHD) to L. Sama (NYSDEC), Subject: Prehearing Conference. May 15, 1980.
3. Telecon Note: Conversation between J. Schechter (NCHD) and E. Leonard (NUS Corporation), April 26, 1988.
4. U.S. Environmental Protection Agency, Region 2, Consent Agreement and Consent Order (Docket No. II RCRA-83-0249) issued against John Hassall, Inc. January 22, 1984.
5. Letter from J.L. Middlekoop (NYSDEC) to V. Palese (John Hassall, Inc.). August 26, 1985.
6. NYSDEC, February 3, 1975, New York State Department of Environmental Conservation State Pollutant Discharge Elimination System Discharge Permit, Permit No. NY0076287 for John Hassall, Inc.
7. Letter from M.F. Foster (County of Nassau, Department of Public Works) to R.S. Iyer (Holzmacher, McLendon & Murrell). August 15, 1983.
8. Field Notebook No. 0189, John Hassall, TDD No. 02-8802-07, Site Inspection, NUS Corporation Region 2 FIT, Edison, New Jersey. March 9, 1988.
9. Telecon Note: Conversation between J. Schechter (NCHD) and R. Feinberg (NUS Corporation). February 19, 1988.
10. Palese, V. Report on the Hazardous and Nonhazardous Industrial Waste Generated, Treated, and/or Stored by John Hassall, Inc. Date unknown.
11. Holzmacher, McLendon and Murrell. Monthly SPDES Industrial Discharge Monitoring Reports for John Hassall, Inc. 1975 to 1982.
12. Telecon Note: Conversation between V. Palese (John Hassall, Inc.) and E. Leonard (NUS Corporation). March 17, 1988.
13. Telecon Note: Conversation between J. Schechter (NCHD) and E. Leonard (NUS Corporation). March 17, 1988.
14. Telecon Note: Conversation between J. McCrosson (Hicksville Water District) and R. Feinberg (NUS Corp.). February 18, 1988.
15. Federal Register, Vo. 43, No. 120, p. 26611. June 21, 1978.
16. Kilburn, C. and R.K. Krulikas. Hydrogeology and Groundwater Quality of the Northern Part of the Town of Oyster Bay, Nassau County, New York in 1980. Water-Resources Investigations Report 85-4051. U.S. Geological Survey and Nassau County Department of Public Works. 1987.
17. Letter from H.V. Morgan (Town of Hempstead, Department of Water) to E. Leonard (NUS Corporation). April 6, 1988.

## 6.0 REFERENCES(Cont'd)

18. Letter from J.J. McCrosson (Hicksville Water District) to E. Leonard (NUS Corporation). March 22, 1988.
19. Letter from A.J. Lindon (Village of Old Westbury, Department of Public Works) to E. Leonard (NUS Corporation). April 4, 1988.
20. Letter from I.J. Vacchio (Westbury Water District) to E. Leonard (NUS Corporation). March 21, 1988.
21. Telecon Note: Conversation between Staff Engineer (Nassau County, Department of Public Works) and E. Leonard (NUS Corporation). April 22, 1988.
22. Letter from W. Evers (Jericho Water District) to E. Leonard (NUS Corporation). May 9, 1988.
23. Uncontrolled hazardous waste site ranking system, A user's manual, 40 CFR, Part 300, Appendix A, 1986.
24. Letter from unknown (John Hassall, Inc.) to E.A. Regna (U.S. EPA, Region 2). February 10, 1984.
25. U.S. EPA Contract Laboratory Program, Hittman-Ebasco Assoc. Inc. and CSMRI Analytical Inc., Case No. 9116, Laboratory Analysis from NUS Corp. Region 2 FIT Site Inspection, conducted on March 9, 1988.
26. Telecon Note: Conversation between J. Schechter (Nassau County Health Department) and E. Leonard (NUS Corp.). February 1, 1989.
27. Three-Mile Vicinity Map, based on U.S. Geological Survey Map, 15-minute Quadrangles for Amityville, NY, 1969 (Photorevised 1979), Freeport, NY, 1969 (Photorevised 1979), Hicksville, NY, 1967 (Photorevised 1979), Huntington, NY, 1967 (Photorevised 1979).

**REFERENCE NO. 1**

02-8802-07

NYEF

E11

JOHN HASSALL, INC.

Lat: 40°46'30"N

Long: 73°33'10"W

Data List of Dataset: NYEF

Number of Records = 6

REC #	POP	HOUSE	DISTANCE	SECTOR
1	0	0	0.400000	1
2	2187	664	0.810000	1
3	10534	2984	1.60000	1
4	33165	10514	3.20000	1
5	63648	19481	4.80000	1
6	72437	20451	6.40000	1

DISTANCE MILES	TOTAL POPULATION	TOTAL HOUSES
1	12 721	3648
2	45 886	14162
3	109 534	33643
4	181 971	54094

02-8802-07

REFERENCE NO. 2

ENVIRONMENTAL  
HEALTH  
Continuation Sheet  
Nassau County Health Department

Owner or  
Agent :  
Address:

Inspector

DATE

C O M M E N T S

TO: L. SANA

FROM: J. SCHECHTER

SUBJECT: Pre Hearing Conference

John Hassall Inc.

Cantiague Rock Rd.

Westbury, N.Y.

On 5/15/80 at 2:00PM a pre-hearing conference was held at NYSDEC regional office in Stony Brook concerning the continuing violations of John Hassall Inc. Westbury, N.Y. Those attending included:

Joan Scherb, regional attorney, NYSDEC

Gerald Robin, senior sanitary engineer

Karl Horlitz, plant manager, John Hassall

John Molloy, H2M consulting ENGR. for John Hassall

Joseph Schechter, Senior Sanitarian, N.C.D.H.

Since the last pre-hearing conference held on 10/18/78, H2M has attempted to meet permit limitations by improving the treatment system - including manufacturing process changes, chemical usage + optimization of the treatment system. In addition, discharge of pre-treated wastes to the Nassau County sewer has also been investigated. However, discharge of wastewater continues to violate groundwater discharge standards.

DATE

COMMENTS

for total chromium, iron, nickel & oil & grease,  
although evidence of improvement can be noted  
in self monitoring reports & Nassau County samples.

In order to meet effluent standards & reduce the  
amount of sludge & filter cake presently produced,  
HAM intends to design an evaporative system & go  
to a no discharge condition by June 1981.  
Presently, on site there are:

250 drums - filter cake

66 " - industrial wash sludge (oil sludge)

63 " - mixed metal sludge

A compliance schedule was established as follows:

By 8/4/80 - Submit engineering report for means of  
meeting groundwater discharge standards -  
(will include discussion of present treatment  
system)

By 11/4/80 - Submit final plans & specs

By 11/10/80 - order equipment

By 3/20/81 - Begin construction

By 6/20/81 - Attain operational level

By 6/30/81 - Submit final report indicating discontinuation  
of discharge



ENVIRONMENTAL  
HEALTH  
Continuation Sheet  
Nassau County Health Department

Owner or  
Agent :  
Address:

Inspector

DATE

COMMENTS

The consent order was typed after the meeting and handed to Mr. Horlitz to deliver to a corporate officer for signature.

In addition, it was agreed, that since the current permit expired 2/5/80 and an application has not been submitted, to resolve legal problems, Mr. Molloy will send ~~an application~~ to a letter of explanation to George Hansen including a copy of the compliance schedule to be included in the renewal permit. The letter will request an application package.

No civil penalty was imposed.

J. J. Cheek

REFERENCE NO. 3

## NUS CORPORATION AND SUBSIDIARIES

TELECON NOTE

CONTROL NO:

DATE:

4/26/88

TIME:

1120 HRS

DISTRIBUTION:

JOHN HASSALL

02-8802-07

BETWEEN:

JOE SCHEFFER

OF:

NCHD

PHONE:

(516) 535-2286

AND:

E. LEONARD (NUS)

DISCUSSION:

RE: BACKGROUND

- 1) CONSENT ORDER ISSUED IN MAY 1980, BUT NOT SIGNED. HASSALL AGREED TO FOLLOW COMPLIANCE SCHEDULE ESTABLISH DURING PREHEARING CONF. 5/15/80. ON 7/1/81 NCHD FORCED HASSALL TO STOP DISCHARGING TO RECHARGE BASIN + COLLECT WASTE WATER. WASTE WATER SHIPPED CHEMICAL WASTE MANAGEMENT FROM JULY TO SEPT FOR DISPOSAL, UNTILL ALLOWED TO DISCHARGE TO NASSAU CO. SEWER SYSTEM IN SEPT 1981.

ACTION ITEMS:

- 2) SPDES PERMIT DELETED IN 1981.

- 3) HASSALLS ANALYTICAL LAB WAS SUPPOSE TO BE AN APPROVED ANALYTICAL LAB BY NY FOR DRINKING WATER ANALYSIS N 2 YRS AGO LABS WERE APPROVED FOR WASTE WATER ANALYSIS.

NUS CORPORATION AND SUBSIDIARIES

TELECON NOTE

CONTROL NO:

DATE:

4/26/88

TIME:

1140HRS

DISTRIBUTION:

JOHN MASSALL  
02-8802.07

BETWEEN:

J. SCHETTER

OF:

NCHD

PHONE:

(516) 535 2286

AND:

E. (EDWARD) (NUS)

DISCUSSION:

RE: BACKGROUND

4) DEC 1987 SPILL. NCHD HAS VISUALLY  
INSPECTED THE SPILL AT MASSALL.  
IN NEXT 2 WEEK THEY WILL SAMPLE.  
MR. SCHETTER WILL SEND REPORT &  
RESULTS WHEN COMPLETED.

Edward 4/26/88

ACTION ITEMS:

REFERENCE NO. 4

UNITED STATES ENVIRONMENTAL PROTECTION AGENCY  
REGION II

In the Matter of  
JOHN HASSALL, INC.  
NYD002045417

Westbury, New York 11590

Respondent.

Proceeding Under Section 3008 of the  
Solid Waste Disposal Act, as amended.

CONSENT AGREEMENT  
AND  
CONSENT ORDER

Docket No. II RCRA-83-0249

PRELIMINARY STATEMENT

This administrative proceeding was instituted pursuant to Section 3008 of the Solid Waste Disposal Act, as amended, 42 U.S.C. §6901 et seq. (the Act).

[Note: Among the statutes amending the Act is the Resource Conservation and Recovery Act, 90 Stat. 2795, P.L. 94-580 (1976).]

The Director of the Air and Waste Management Division of the U.S. Environmental Protection Agency (EPA), Region II, Complainant in this proceeding, issued a Complaint, Compliance Order, and Notice of Opportunity for Hearing to Respondent, JOHN HASSALL, INC. Said document charged Respondent with certain violations of Section 3004 of the Act, 42 U.S.C. §6924, and the regulations promulgated thereunder, as follows:

1. Respondent owns and operates a facility located at:

Cantiague Rock Road

Westbury, New York 11590

2. By notification dated August 12, 1980, Respondent informed EPA that it conducts activities at the facility involving "hazardous waste," as that term is defined in Section 1004(5) of the Act, 42 U.S.C. §6903(5) and in 40 CFR §261.3.

By application dated November 19, 1980, Respondent requested a permit to conduct its hazardous waste activities.

3. EPA regulations for hazardous waste treatment, storage, and disposal facilities are found at 40 CFR Part 265 (published in 45 Fed. Reg. 33063 et seq., May 19, 1980 and as later amended), promulgated pursuant to Subtitle C of the Act, 42 U.S.C. §6921 et seq.

4. 40 CFR Part 265 sets interim status standards for hazardous waste treatment, storage, and disposal facilities. These standards apply until final administrative disposition of permit applications with respect to these facilities has been made. No such final disposition has been made with respect to your facility, and thus the standards of Part 265 apply thereto.

5. 40 CFR §265.143 (amended on April 7, 1982) requires that by the effective date of the regulation, (July 6, 1982) an owner or operator of a hazardous waste facility must establish financial assurance for closure of the facility, as well as, where appropriate, post-closure monitoring. As of September 1, 1983, information available to EPA indicates that Respondent's facility had not submitted the documents necessary to comply with this requirement. Respondent was therefore in violation of 40 CFR §265.143.

6. 40 CFR §265.147 (amended on April 17, 1982) requires that by the effective date of the regulation (July 17, 1982) an owner or operator of a hazardous waste facility must establish financial responsibility for bodily injury and property damage to third parties caused by sudden accidental occurrences arising from the operation of the facility. As of September 1, 1983, information available to EPA indicates that Respondent's facility had not submitted the documents necessary to comply with this requirement. Respondent was therefore in violation of 40 CFR §265.147.

CONSENT AGREEMENT

Based upon the foregoing, and pursuant to Section 3008 of the Act, and Section 22.18 of the Consolidated Rules of Practices Governing the Administrative Assessment of Civil Penalties and the Revocation or Suspension of Permits, 40 CFR §22.18, it is hereby agreed that Respondent shall hereinafter comply with all relevant regulations at 40 CFR Parts 261 through 265 and the following terms:

1. Respondent shall, within thirty (30) days of the effective date of this Compliance Order, submit to EPA documents sufficient to establish financial assurance for closure and, where appropriate, post-closure monitoring, as required by 40 CFR §265.143.
2. Respondent shall, within thirty (30) days of the effective date of this Compliance Order, submit to EPA documents sufficient to establish financial responsibility for bodily injury and property damage to third parties caused by sudden accidental occurrences arising from the operation of the facility, as required by 40 CFR §265.147.

Within sixty (60) days of receipt of a signed and executed copy of this Consent Agreement and Final Order, Respondent shall pay by cashier's or certified check a civil penalty for the violations cited herein in the amount of \$2,000.00, payable to the Treasurer, United States of America. Such payment shall be remitted to the Regional Hearing Clerk, EPA, Region II, 26 Federal Plaza, New York, New York, 10278. Failure to remit such payment in full will result in the referral of this matter to the United States Attorney for collection. This Consent Agreement is being entered into by the parties in full settlement of all liabilities which might have attached as a result of the proceedings.



Respondent admits the jurisdictional allegations of the Complaint. Furthermore, Respondent has read the Agreement and admits the facts stipulated therein. Respondent consents to the assessment of the civil penalty set forth in the Agreement and explicitly waives its right to request a hearing on the Complaint, this Agreement, or the attached Consent Order.

RESPONDENT:

BY: Karl W. Horlitz P.E.

DATE: December 2, 1983

COMPLAINANT:

Conrad Simon

CONRAD SIMON

Director

Air and Waste Management Division

DATE: January 20, 1984

CONSENT ORDER


The Regional Administrator of EPA, Region II, concurs in the foregoing Consent Agreement. The Agreement entered into by the parties is hereby approved and issued, effective immediately.

Jacqueline E. Schaffer  
JACQUILINE E. SCHAFER  
Regional Administrator  
U.S. Environmental Protection  
Agency  
26 Federal Plaza  
New York, New York 10278

DATE: Jan. 23 1984

REFERENCE NO. 5

New York State Department of Environmental Conservation  
50 Wolf Road, Albany, New York 12233-0001



Henry G. Williams  
Commissioner

PI  
C1105-5-

Com 09

851031  
UP

AUG 26 1985

Mr. Victor Palese  
John Hassal, Inc.  
Contiague Road  
Westbury, NY 11590

Dear Mr. Palese:

Re: Reclassification of NYD002045417  
to Generator-Only Status

The New York State Department of Environmental Conservation (DEC) is now fully responsible for administration of the Resource Conservation and Recovery Act (RCRA) regulatory program for hazardous waste facilities operating under interim status with Part A RCRA Permits.

In order to qualify as an interim status hazardous waste treatment, storage or disposal (TSD) facility pursuant to Section 3005(e) of RCRA and 6NYCRR Part 373, a facility was required to be in existence on November 19, 1980, and to be conducting a hazardous waste activity requiring a RCRA and/or Part 373 Permit. Based on information submitted by your company, it appears that your facility has never qualified for interim status pursuant to Section 3005(e) of RCRA and/or 6NYCRR Part 373, insofar as it never conducted a RCRA or 373 permittable activity. Therefore, DEC considers your facility to never have operated with interim status under a Part A Permit.

If you have any information which would otherwise indicate that your facility had or does qualify for interim status under RCRA or Part 373, it must be submitted within 14 calendar days of the date of this letter. If you do not respond to this letter within the time provided, your facility will be removed from the list of active TSD facilities.

Please be advised that withdrawal of your Part A Permit application terminates your privilege to operate with interim status in the future. Should you decide to conduct any activity not exempt from the permit requirements of 6NYCRR Part 373 and/or 40 CFR Parts 264, 265 and 270, you must first obtain full Part 373 and RCRA Permits. Failure to obtain the proper permits will subject you to enforcement actions pursuant to Section 3008 of RCRA and Article 27, Titles 7 and 9 of the Environmental Conservation Law.

Mr. Palese

2.

Should you have any questions concerning this matter, please contact Mr. George Heitzman, of my staff, at (518) 457-3274.

Sincerely,

*John L. Middelkoop, P.E.*

John L. Middelkoop, P.E.  
Supervisor, Permits Section  
Bureau of Hazardous Waste Technology  
Division of Solid and Hazardous Waste

cc: Richard A. Baker (EPA Region II - Permits Administration Branch)  
James M. Reidy (EPA Region II - Solid Waste Branch)  
David Mafrici (NYSDEC - Bureau of Hazardous Waste Operations)  
T. Sanford (Regional Solid Waste Engineer, NYSDEC - Region 1)

REFERENCE NO. 6

Final Effluent Limitations

During the period beginning EDP (2/3/75) and lasting  
(Give Date)  
until the date of expiration of this permit, discharges from outfalls 001  
(Specify Outfall Number)  
shall be limited and monitored by the permittee as specified below:

(a) The following shall be limited and monitored by the permittee as specified:

Outfall Number	Effluent Characteristic	Discharge Limitation in kg/day (lbs./day)		Other Limitations (Specify Units)		Monitoring Requirements	
		Daily Average	Daily Maximum	Average	Maximum	Measurement Frequency	Sample Type
001	Flow			n/a		Total each	Batch
	Chromium (Hexavalent)			.1 mg/l		Each	Batch
	Chromium (Total)			1.0 .25 mg/l		"	"
	Copper			.4 mg/l		"	"
	Iron			.6 mg/l		"	"
	Nickel			1.0 mg/l		"	"
	Oil			10 mg/l	15 mg/l	"	"

For the purposes of this subsection, the daily average discharge is the total discharge by weight during a calendar month divided by the number of days in the month that the production or commercial facility was operating.

For the purposes of this subsection, the daily maximum discharge means the total discharge by weight during any calendar day.

(b) The pH shall not be less than 6.0 nor greater than 8.5.  
The pH shall be monitored as follows: Each Batch

**REFERENCE NO. 7**



COUNTY OF NASSAU  
DEPARTMENT OF PUBLIC WORKS  
MINEOLA, NEW YORK 11301

August 15, 1983

Raman S. Iyer  
Holzmacher, McLendon & Murrell  
125 Baylis Road  
Suite 140  
Melville, N. Y. 11747

Dear Raman:

We have completed our review of the weekly laboratory reports on John Hassall waste water discharges and have found them satisfactory. In light of this record, we recommend that the frequency of self monitoring by John Hassall be reduced from weekly to once a month. The following parameters are required to be monitored.

Aluminum  
Hexavalent Chromium  
Total Chromium  
Chloride  
Copper  
Iron  
Silver  
Sulfide  
Fluoride  
Chemical Oxygen Demand  
NH<sub>3</sub> - Nitrogen  
Total Dissolved Solids  
Oil and Grease  
pH

Please note that chloride was added to the list of parameters requested in your letter of July 29, 1983. The monthly analysis results of the self monitoring are to be sent to my attention. To be included with the report would be the weekly flowmeter readings for that month.

Very truly yours,

Matthew F. Foster

Asst. Superintendent of Sanitary Engineering

MFF:ab

cc: F. J. Flood

M. Osman

Karl Horlitz, John Hassall ✓



John Hassall has been treating the industrial effluent generated by the various processes and cleaning procedures that are utilized in our special cleaning and finishing department since 1974.

The sluges resulting from the cleaning effluents from manufacturing these special fasteners are the by-products of degreasing and cleaning these parts after they have been headed or upset on the machinery. In order to facilitate the feeding of these parts through secondary operations, these parts have to be clean, brite and dry, so as to negotiate the tracks and feeding devices designed to enhance automatic handling or indexing through the equipment.

A small percentage of our products are nickel plated in our electroplating equipment. This equipment consists of two 175 gallon plating tanks. Considering an average of 242,500 lbs of product manufactured per month, only 700 lbs of these were plated in our equipment. All other plating requirements are handled through outside vendors. Our plating is utilized for emergency measures only, where delivery time is the dominant factor.

#### Waste Treatment

Our waste treatment process consist of three (3) segregated waste water streams. (Industrial washing machines, oil stripping and mixed metals waste waters), in three (3) below grade pre-cast concrete-fiberglass lined oil separation tanks, each @ 9000 gallons, then pre-settling in three (3) below grade pre-cast concrete fiber glass lined settling tanks each @ 9000 gallons, and fitted with air and CO2 defusers for mixing and PH adjustment.

Waste waters after pre-treatment by oil separation and pre-settling are pumped from three (3) separated concrete wet wells, each fitted with a 100 GPM vertical centrifical pump which delivers each of the waste waters to one of the three interior steel treatment tanks, each with a cpapcity of 10,000 gallons. Each treatment tank contains a vertical paddle wheel flocculator, air and CO2 diffusers and oil skimming over flow weirs, and variable take off effluent drains.

The first treatment consists of the addition to the effluent as follows Calcium Hydroxide ( $\text{Ca}(\text{OH})_2$ ), Sodium Sulfide ( $\text{Na}_2\text{S}$ ), Calcium Chloride ( $\text{CaCl}_2$ ), Carbon Dioxide ( $\text{CO}_2$ ) and cationic and non ionic poly electrolyte. The effluent is flocculated and allowed to settle overnight.

The following day, this pre-treated effluent is transferred by pump into tank #2 for the second treatment.

The second treatment consists of the addition to the pre-treated effluue as follows:

Activated carbon, Aluminum Sulfate ( $\text{Al}_2(\text{SO}_4)_3$ ) and an ionic poly electrolyte. This is Flocculated for thorough mixing and allowed to settle overnight. The following day this treated effluent is pumped through the plate and frame shriver filter (this filter was previously prepared and charged with Diatomicious earth, super cell and sorbo-cell

## WASTE ANALYSIS PLAN

The constituents of all hazardous waste generated by John Hassall, Inc.; be it waste water or sludge resulting from treatment to this water, or oily waste, which is contained in drums (for off site disposal) remains the same although quantities of these known substances will differ.

Samples are taken on a "grab" basis and are considered most representatives of the materials in question. Thorough and continuous mixing is achieved by the use of large paddle wheel flocculators within these treatment tanks. Samples are taken off side ports. This sample is then placed into properly labeled sample jars, which have been previously prepared by an Independent Laboratory (H2M) for forwarding to them for analysis. A test method sheet has been enclosed.

All raw waste water and sludges are currently and routinely being sent for E.P. Toxicity analysis on a semi-annual basis.

Oily waste is currently being analyzed on an annual basis.

## OUR HAZARDOUS WASTES

- 1- Spent Stoddard Solvent combined with both cutting and lubricating oils  
(these oils may contain sulfur, paraffin base oils, combined chlorine and phosphorous.)
- 2- Degreasing Solvents
  1. chlorinated safety solvents
  2. spent freon
  3. VG 1.1.1
- 3- Salt Solutions  
From electro chemical grinding. May contain Sodium Nitrite, Sodium Nitrate, and Rochelle Salts.
- 4- Spent Diatomite - (filter aid) containing small amounts of carbon, oil or grease and trace metals. (Fe, Ni, Cr, Cu, Zn)

**REFERENCE NO. 8**

0019-F  
02-8802-07

# **NUS CORPORATION**

**II**

**0189**

JOHN HASALL  
02-8802-07  
SITE MANAGER - E. LEONARD  
LOGBOOK # 0189  
MARCH 8, 1988

GUIDANCE FOR PROPER USE OF LOG BOOKS

**PURPOSE**

- Serves to document on-site activities and be understandable to an outside reader.

- A person not present when field activities were being documented should read each completed page, and countersign and date when satisfied that the

JOHN HASALL / WESTBURY, NY

TDJ # 02-8807.02  
2

TABLE OF CONTENTS

PG 4-12 FIELD NOTES OF 3/9/88

PG 28-<sup>29</sup>~~28~~<sub>24</sub> PHOTO LOG OF 3/9/88

PG 31 SITE MAP OF 3/9/88

PG 32 SAMPLE DATA OF 3/9/88

JOHN HASSALL / WESTBURY, NY

3/9/88

TDD# 02-8802.07



EQUIPMENT ONSITE

VICTOR J. PALESE  
FACILITY MANAGER

- CAMERA SLIDE 30"  
PRINT 469

JOHN HASSALL, INC.  
WESTBURY - LONG ISLAND  
NEW YORK 11590

516-334-6200  
TELEX 144585  
FAX 516-222-1911

- MINIRAD EPA # 4030

- OVA-D EPA # 428 694 SB 3/7/88

- HNU-D EPA # <sup>307139</sup> ~~307139~~ SB 3/7/88

- DRAGER <sup>PH</sup> ~~FUGO~~ PUMP - A EPA # 192105

~~PERSONNEL ONSITE~~ SCBA'S 307184 P. SOLINSKI  
629756 S. LOUCZYK  
192084 P. VON SCHNODDERF

- ESCAPE PACKS 192335 ~~PH~~  
192384 P.V.S.

PERSONNEL ONSITE

E. LEONARD - SITE MANAGER

P. VON SCHNODDERF - SSO

M. GONTIUS - SMO

P. SOLINSKI - SAMPLER

S. LOUCZYK - SAMPLER

WEATHER: PARTLY CLOUDY. TEMP 38-50°F  
WINDS SLIGHT (<5 MPH) FROM NORTH

E. Leonard 3/11/88 P. Solinski 3/11/88



JOHN HASALL / WESTBURY, NY  
TOD # 02-8802-07

3/9/88

5

0640 HRS ARRIVE AT JOHN HASALL, WAITING  
FOR V. PALOSZ

0645 HRS MEET WITH V. PALOSZ. <sup>can</sup> ~~REHARGE~~ SET  
UP DECON AREA BY ENTRANCE  
TO RECHARGE BASIN. START SETTING  
UP DECON AREA

0650 HRS P. VON SCHON, DOLF HODOS ZYL GATE  
SAFETY MEETING. SAMPLERS SUIT UP.

0715 HRS ALL GEARED UP, WAITING ON  
V. PALOSZ TO START LEVEL-B  
RECON

0726 HRS P. SOLINSKI + S. LUKZYK ON AIR  
AND IN TO RECHARGE, TO RECON

0728 HRS NO READINGS ABOVE BACK GROUND <sup>ON OUR OWN</sup>   
AT WEST END OF RECHARGE BASIN   
FROM GROUND OR PIPES ENTERING.   
SIX ~~all~~ <sup>THREE</sup> PIPE TOTAL ENTERING  
NO LONGER ANY DISCHARGE.  
POSSIBLE THAT STORM DRAINS  
B ROOF DRAIN MIGHT STILL  
ENTER BUT UNKNOWN. APPROX  
200 EMPLOYEES ON SITE. RECHARGE  
BASIN FENCED BUT GATE NO LOCKED.  
SITE NOT TOTALLY FENCED. UNDERGROUND  
STORAGE TANKS NOT FENCED.

Edward 3/11/88

P. Solinski 3/16/88

JOHN HASALL / WESTBURY, NY

3/9/88

CDD # 02-8802-07

6

0731 HRS NO READINGS ABOVE BACKGROUND  
AT OTHER ~~THREE~~ INLET PIPES ON  
OVA + HNU.

0736 HRS NO EVANIDE READINGS ON  
DRAGGER TUBE. ~~OUT OF~~ EXIT  
RECHARGE BASIN.

0740 HRS AROUND OUTSIDE OF FOUCE.  
NO READINGS ABOVE BACKGROUND  
ON HNU ON SOUTH SIDE OF  
RECHARGE BASIN. OVA PUMP  
NOT WORKING, WILL USE ONLY HNU FOR REMAINING  
ECON

0744 HRS NO READING ABOVE BACKGROUND  
ON HNU BY MAN COVER TO  
UNDER- STORAGE TANKS. NO  
READINGS ABOVE BACKGROUND ON  
HNU BY AREA OF GREASE TOLL SPILL  
N DEC 1987. TANKS N 10 YEARS OLD  
WILL BE LEAK TESTED IN N 30 DAYS  
~~SOUTHERN SIDE SLOTTED SLOTTED TANK~~  
E4

0745 HRS P. SOLINSKI + S. LONCZYK OFF AIR.

0805 HRS P. VONSCHEIDT, E. LEONARD +  
V. PARESE WALK THE REST OF  
THE SITE. SITE 1, S  
15-ARCS

Chloride 3/11/88 P. Solinski 3/16/88

JOHNY HASALL / WESTBURY, NY  
TDD # 02-8802.07

3/9/88

7

0821 HRS BACK FROM RECON ON THE  
PARK LOT. NO READING ABOVE  
BACK GROUND ON HNU. SAMPLING  
WILL BE CONDUCTED IN THE  
RECHARGE BASIN + BY THE  
UNDERGROUND STORAGE TANKS  
GOING ON OUT, PUMP ON NO  
IGNITION. SAMPLING WILL BE CONDUCTED  
WITH HNU MONITORING ONLY.

0831 HRS INTO RECHARGE BASIN TO  
START SAMPLING. NO RSP. WILL  
BE USED, SOIL MOIST NO DUST.

0834 HRS CLOSE AREA UNDER PIPE #1 (SEE MAP)  
FULLY. NO READINGS ABOVE  
BACK GROUND ON HNU. START OBTAINING  
SAMPLE S-1 (MS/MSD). ROOT + ORGANIC  
0-3" SANDY BROW. SAMPLE DEPTH  
0-6"

0841 HRS P. SOLINSKI FINISH OBTAINING  
S-1.

0849 HRS 6' DOWN FROM PIPE #2 NO  
READINGS ABOVE BACK GROUND ON  
HNU. DARK ORGANIC SAND. P. SOLINSKI  
STARTS OBTAINING S-2 + S-3  
(ENV. DUP.). BLOW ~~BY~~ 3" LIGHT  
SAND. SAMPLE DEPTH 0-6"

CH Leonard 3/11/88

P. Solinski  
3/11/88

JOHN HASALL/WESTBURY, NY

3/9/88

TDD # 02-8802-07

0900 P. SOLINSKI FINISH OBTAINING  
S-2 + S-3.

0905 HRS S. <sup>ell</sup>LOLCZYK STARTS OBTAINING  
S-4. ~~NO~~ AT PIPE #3. NO READINGS  
ABOVE BACKGROUND ON HNU. SOIL  
SANDY BROWN + ORGANIC. DEPTH  
0-6". BROWN 3" LIGHT COLORED SAND.

0911 HRS. S. LOLCZYK FINISH OBTAINING  
S-4

0917 HRS P. SOLINSKI STARTS OBTAINING  
S-5. AT PIPE #4. NO READINGS  
ABOVE BACKGROUND ON HNU.  
SOIL ORGANIC + BROWN + SANDY  
SAMPLE DEPTH 0-6". SPLIT  
SAMPLE WITH BITS RVP  
FILLED 1 BOTTLE N2002 WITH  
SOIL. BROWN 3" SAND LIGHT COLORED

0924 HRS P. SOLINSKI FINISH OBTAINING  
S-5

0928 HRS P. SOLINSKI STARTS OBTAINING  
S-6. NO READINGS ABOVE BACKGROUND  
ON HNU. SOIL DARK, ORGANIC  
+ SANDY WITH GRAVEL, 0-6" DEEP.  
SAMPLE OBTAINED AT PIPE #5.  
BELOW 3" SAND LIGHT COLORED

Ch Leonard 3/11/88

P. Solinski 3/11/88

JOHN HASSELL / WESTBURY, NY  
TDD # 02-8802-07

3/9/88

0936 HRS P. SOLINSKI FINISHES TANNING  
S-4

0940 HRS S. LENCZYK STARTS OBTAINING  
S-7 AT PIPE #6. HNU READINGS  
AT SOIL SURFACE AT 17 PPM.  
BACK OFF WILL SAMPLE ON  
LOVEZ B. READINGS AT SOIL LEVEL,  
NOTHING IN BREATHING ZONE

0947 HRS BACK AT DORON AREA PREP  
FOR SAMPLE S-8.

0954 HRS S. LENCZYK STARTS OBTAINING  
SAMPLE S-8. READING ABOVE  
BACK GROUND ON HNU. ~12 PPM.  
BACK OFF. SMALL STAIN AT  
EDGE OF MANHOLE. THIS  
IS MANHOLE THAT OVER FLOWED  
IN DEC 1987, NO READING IN BREATHING ZONE.

1009 HRS P. SOLINSKI ON AIR. STARTS  
OBTAINING S-8. READING AT  
SOIL 15 PPM. DARK ORGANIC  
SOIL. 50 PPM in soil in  
MIXING BOWL NO READINGS  
IN BREATHING ZONE. 0-6 in  
sampling depth. S. LENCZYK BACK UP.  
SOIL DARK & ORGANIC, U. PALUSZ STATED  
THAT CONTAMINATION WAS REMOVED + THIS WAS FULL

Chlorinated 3/11/88

P. Solinski 3/16/88

JOHN HASALL/WESTBURY, NY  
TOD # 02-8802-07

3/9/88

10

1019 HRS. P. SOLINSKI FINISH SAMPLING  
S-8 + OFF AIR.

1021 HRS. BACK AT DECON AREA.

1023 HRS AT PIPE #6 TO OBTAIN  
S-7. 5ppm ON HNU.

1024 HRS P. SOLINSKI ON AIR.  
STARTS SAMPLING AT 730  
PPM ON HNU IN SOIL  
NOTHING IN BREATHING ZONE  
SAMPLING DEPTH 0-6" SANDY + DARK  
ORGANIC 0-3", 23" ~~PH~~ LIGHT COLORED SAND

1030 HRS P. SOLINSKI FINISH OBTAINING  
S-7.

1032 HRS BACK AT DECON AREA P. SOLINSKI  
OFF AIR.

1040 HRS CLEANING UP + PACKING  
SAMPLES.

1055 HRS S-7 VOA 1 BOTTLE BROKEN,  
MUST RESAMPLE AT PIPE #6.

CR Leonard 3/11/88

D. Shuh  
3/16/88

JOHN HASALL / WESTBURY, NY  
-TOD # 02-8502-07

3/9/88

1101 HRS BACK INTO RECHARGE BASIN TO  
OBTAIN JDA FROM S-7 PIPE#6

1103 HRS P. SOLINSKI ON AIR,

1105 HRS FINISHING OBTAINING S-7.  
P. SOLINSKI OFF AIR.

1110 HRS DISCHARGE PIPE DIA.

#1	8.5"	0.35'
#2	<del>21.5"</del> 10"	0.5'
#3	4.0"	0.4'
#4	<del>10.7"</del>	0.35'
#5		0.7'
#6		0.35'

RECHARGE BASIN APPROX. 10-12' DEEP  
APPROX. 60' X 85'.

1120 HRS CLEANING UP & PACKING SAMPLES.

1140 HRS TRY TO FIND V. PALOSZ TO DROP  
SAMPLE RECEIPT.

1146 HRS COULD NOT CONTACT V. PALOSZ  
LEFT ORIGINAL RECEIPT AT  
FRONT DESK FOR M. PALOSZ.  
V. PALOSZ DID NOT SIGN RECEIPT.

CR Leonard 3/11/88

P. Solinski  
3/6/88

JOHN HARALL/WESTBURY, NY  
TOD # 02-8802-07

3/9/88 12

1152 HRS LEFT SITE HEAD TO FOD  
EX.

1159 AT FOD EX TO DROP OFF  
SAMPLES. ~~LEFT EX~~

1204 LEFT FOD EX.

F2 //

Ch Leonard 3/11/88

J. Colman 3/16/88



JOHN		HASSACK/WESTBURY, NY		TDD# 02-8802.07		3/9/88
DATE	TIME	PHOT	AIF	DESCRIPTION		
3/9/88	0838	RLL	IS-1 IP-1	P. SOLINSKI S-1.	OBTAINING SAMPLE	
3/9/88	0854	RLL	IS-2 IP-2	P. SOLINSKI S-2. (PHOTO TIME IS 0954).	OBTAINING SAMPLE	
3/9/88	0858	RLL	IS-3 IP-3	P. SOLINSKI S-3.	OBTAINING SAMPLE	
3/9/88	0908	RLL	IS-4 IP-4	LENCZYK S. <del>LENCZYK</del> RLL S-4.	OBTAINING SAMPLE	
3/9/88	0920	RLL	IS-5 IP-5	P. SOLINSKI S-5.	OBTAINING SAMPLE	
3/9/88	0932	RLL	IS-6 <del>IS-6</del> IP-6	P. SOLINSKI S-6	OBTAINING SAMPLE	
3/9/88	1015	RLL	IS-7 <del>IP-7</del> IP-7	P. SOLINSKI S-8	OBTAINING SAMPLE	
CH Leonard			3/11/88	P. Solinski. 3/16/88		

28

JOHN HASALL / WESTBURY, NY CDD# 02-8802-07 3/9/88				
DATE	TIME	PHOTO	R/F	DESCRIPTION
3/9/88	1027	ELL	IS-8 IP-8	P. SOLINSKI OBTAINING SAMPLES <del>S-8. S-7. ELL</del>
3/9/88	1034	ELL	IS-9 IP-9	LOOK WEST AT RECHARGE BASIN. <del>FIVE</del> <sup>FIVE</sup> DISCHARGE PIPES. ELL <del>ELL</del>
3/9/88	1035	ELL	IS-10 IP-10	LOOKING NORTH AT RECHARGE BASIN ONE DISCHARGE PIPE. (SOIL UNDER DISCHARGE PIPE HIGH HNU READING)
3/9/88	1036	ELL	IS-11 IP-11	LOOKING N W AT TREATMENT BUILDING AND UNDERGROUND STORAGE TANKS. (SOIL AT EDGE OF <sup>MANHOLE</sup> <del>MANHOLE</del> TO RIGHT <sup>ELL</sup> HIGH HNU READINGS) <del>SECOND FOLLOW</del> <sup>MANWAY</sup> <del>MANWAY</del> <sup>IN FRONT.</sup>
3/9/88	1037	ELL	IS-12 IP-12	JOHN <del>HASALL</del> <sup>ELL</sup> HASALL SIGN ON MAIN MAIN BUILDING


OK Leonard 3/11/88

A Schuler 8/16/88



BRINKMAN  
INSTRUMENT

OLD CANTIQUE ROCK ROAD



**SITE MAP**

**JOHN HASSALL INC., WESTBURY, N.Y.**

(NOT TO SCALE)

**FIGURE 2**



JOHN MARSHALL / WESTBURY, NY

TDD # 02-8802-07

3/9/88

32

SAMPLE #	ORGANIC	INORGANIC
	CLP #	CLP #
S1	BR 268	MBP 664
S2	BR 269	MBP 665
S3	BR 270	MBP 666
S4	BR 271	MBP 667
S5	BR 272	MBP 668
S6	BR 273	MBP 669
S7	BR 274	MBP 670
S8	BR 277	MBP 672
TBLK1	BR 275	NIA
RIN1	BR 266	MBP 671

TDD # 02-8802-07

BRICS# NYEF

CAB# 9116

ORGANIC

LAB: HITTMAN - EBASCO ASSOC INC  
 9551 RUMSEY ROAD  
 COLUMBIA, MD 21045  
 ATT: ~~BBSL~~ BETSY PICURAL

AIRBILL # 7195199561

INORGANIC

LAB: CSMRI ANALYTICAL INC  
 5930 MCINTYRE STREET  
 GOLDEN, CO 80403

ATTN: ANDREW BYRNOS  
 AIRBILL # 7195199572

*Chambers*  
 3/11/88  
*P. Schuch*  
 3/16/88

REFERENCE NO. 9

0006-C  
02-PR02-07

NUS CORPORATION AND SUBSIDIARIES

TELECON NOTE

CONTROL NO:

02-8202-07

DATE:

2/19/88

TIME:

RF

Ø 1455

DISTRIBUTION:

File

BETWEEN:

Joe Schechter

OF: Nassau County  
Health Dept.

PHONE:

(516) 535-3410

AND:

Richard Feinberg

DISCUSSION: RE: JOHN HASSALL

The discharge basin was used before <sup>1975</sup> ~~1985~~ RF and up to the time they switched to county sewerage system. Effluent was being monitored and <sup>at</sup> ~~SPDES~~ SPDES Permit was set up in 1975. He doesn't believe that the recharge basin was backfilled but is not positive of this. He indicated that they were discharging <sup>wastewater</sup> since 1959 in to discharge basins. No spills have been recorded at the facility to his knowledge.

ACTION ITEMS:

**REFERENCE NO. 10**



ESTABLISHED 1850

HN HASSALL, INC. • WESTBURY • LONG ISLAND • N.Y. • 11590

Tel. 516 • 334-6200 • Telex No. 144585

STATEMENT OF PURPOSE

This comprehensive report provides information on both hazardous and non hazardous industrial waste generated, treated and or stored by John Hassall, Inc.

It is intended to make known to all interested parties the full scope of the risks and related management of those risks.

We recognize the burden of responsibility placed upon us relating to the proper methods of handling the byproduct of our manufacturing process.

Information contained herein is known to be accurate.

Victor Palese  
Compliance Officer





ESTABLISHED 1890

JOHN HASSALL, INC. · WESTBURY · LONG ISLAND · N.Y. · 11590

Tel. 516-334-6200 • Telex No. 144595

### PRESENT PLANT OPERATIONS

John Hassall, Inc., is a long-time established company engaged in the manufacture of specialized or "Job Designed" fasteners, nails, screws and rivets.

The present company was established in 1898 to produce nail machines, hardware, nails and screws. The Company was located in New York City until 1953 when it moved to the present location in Westbury, Nassau, County, New York.

Present plant operations include the handling of various metallic wires from which the fasteners are made, cold heading or the forming of the required shape of the fastener and various other secondary operations such as threading, fluting, knurling, slotting, drilling, tapping, turning, grinding and trimming of fasteners. The above mentioned operations result in no appreciable amounts of industrial waste water and are limited to mostly solid wastes consisting of metallic filing or chips. These wastes generally do not present any disposal problem as they are collected in containers and disposed of by a solid waste removal service. (Metal scrap pick-up).

Industrial waste waters originate from (deburring, burnishing and) cleaning. The expended process solutions and rinse waters from these operations comprise the industrial waste waters mentioned in this report.

### EXISTING OPERATIONS AND WASTE SOURCES

The waste waters are composed of primarily expended cleaning solutions and wash waters from the cleaning operations.

Freon TMC and III Trichloroethane are used on a limited basis to degrease certain parts which need to be specifically handled for one reason or another. It is these solvents which comprise our hazardous waste activity. At this time generation of no more than four 55 gallon drums per calendar month seems a reasonable estimate.

### WASHING OF FASTENERS

High speed manufacturing of fasteners requires a petroleum base lubricant on the wires to aid the feeding of the wire through the dies of the forming machines. After the forming operations, many of the fasteners receive a final washing and coating with a rust inhibitor. Presently, this washing and protective coating is performed in a large industrial washing machine. This washing machine operates as two closed systems, where all wash and rinse waters are recycled to holding reservoirs for re-use. The wash reservoir has an approximate capacity of 500 gallons, whereas the rinse reservoir has a 350 gallon capacity.

### CLEANING OF FASTENERS

Small fasteners cannot be cleaned in the industrial washing machine, and are cleaned instead in barrel tumblers to remove oils and soils.

### POLISHING OF STAINLESS STEEL

Many stainless steel fasteners receive heat treatment after the forming operations. Heat treating leaves metallic scales on the fasteners which must be removed. This removal is accomplished by barrel tumbling.

### LIMITED - NICKEL PLATING

A number of fasteners are nickel plated. Fasteners are first cleaned in the industrial washing machine or barrel tumblers. Fasteners are placed in rotating barrels or baskets and immersed in nickel sulfate solutions in the nickel plating tanks. Presently, no dragout, static or running rinse tanks exist.

All nickel waste if any is segregated from the general waste water treatment system. It will be shipped offsite under F006 for disposal.

Our Manufacturing processes result in approximately 3 to 4 55 gallon drums per month of Hazardous waste. At the present time we are storing these drums, on pallets, in our warehouse. These drums are not accumulated, they are shipped off site as soon as possible (monthly).

The warehouse storage facility is secured and locked. Access is only thru Department necessity and authorized personnel. It is a total area of 20,000 square feet. Its main purpose is to store raw material (wire) and prepackaged finished goods (nails, rivets, screws) in bulk. These are stored in cartons, packed on a pallet, and placed on a storage rack four (4) to five (5) tiers high. A special area has been designated for the hazardous waste storage. The area is totally sprinklered. The containment of a leak or spill would be done thru Floor-Dri pick up. Fire extinguishers are also available.

The containers in which this Hazardous Waste is stored (are when necessary), lined with a plastic insert of 3 mils thickness, and secured with the proper drum cover, sealed and labeled, numbered and coded for identification in accordance with Department of Transportation Regulation 19CFR, Part 172.

The drums will be stacked no more than two (2) high (if this should ever become necessary). They will stand a minimum of five (5) inches off the floor and placed two (2) on each pallet, sized (36"X42"X5-1/2"). They shall stand clearly visible to the eye, so as to be easily inspected for leak detection or drum rupture.

The solid waste storage area is marked with a sign "DANGER - UNAUTHORIZED PERSONNEL KEEP OUT". Access to our warehouse is with key only to authorized personnel.

The solid waste storage area, our Industrial Waste Treatment building and the Laboratory are inspected for possible equipment deterioration or failure, and a report is forwarded to the Plant manager.

The Solid Waste Management Facility is located on a reinforced concrete floor, inside a brick building. This building is also the raw material and finished goods storage area. A specific area, marked, outlined and designated as the solid waste storage or hold area is located in this warehouse. The waste is stored in 55 gallon drums, on pallets and located beneath a fully fire sprinklered area. Fire extinguishers are also located nearby. The amounts of stored drums would be no more than a month's collection, or three to four drums. These drums are constantly being monitored by our Compliance Officer, Victor Palese, and the warehouseman. Any spills, leaks or ruptures would be contained by applying floor dry in abundant amounts which can encircle the leak like a dam, and also soak up the spillage. There is no leachate danger present to outside grounds and none of the stored solid waste is subject to salvage on our site.

The roadway and driveway that encircle our Industrial Complex are always kept in the best repair, and kept free of ice and snow, or any road hazard.

## MATERIAL FLOW

Raw materials, in the form of coils of wire, and consisting of varied metals are delivered to the raw material (wire) storage. (A) From this storage area, the wire is delivered to the various machines, as requested by the Nail and Rivet Manufacturing Departments.

At the machines, the wire is cut to length, and upset to the customers specifications. These parts are inspected and the finished parts dumped into a fiber glass collection pan, and weighed at 50 lbs. The orders are stacked on pallets, which through lift truck operations, are delivered to the Cleaning Department.

From the Cleaning Department the work may be scheduled for secondary operations, heat treating, plating or shipping.

Upon reaching the Shipping Department, parts are final inspected, packed stacked and racked for storage or made ready for shipment to the customer.



HASSALL, INC. · WESTBURY · LONG ISLAND · N.Y. · 11590

Tel. 516-334-6200 • Telex No. 144585

#### GENERAL INFORMATION ON NON-HAZARDOUS WASTE GENERATION AND DISPOSAL

Hassall has been treating the industrial effluent generated by various processes and cleaning procedures that are utilized in its special cleaning and finishing department since 1974.

The sludges resulting from the cleaning effluents from manufacturing these special fasteners are the by-products of degreasing and cleaning these parts after they have been headed or upset on the machinery. In order to facilitate the feeding of these parts through secondary operations, these parts have to be clean, bright and dry, so as to negotiate the tracks and feeding devices designed to enhance automatic handling or indexing through the equipment.

#### Waste Treatment

The waste treatment process consists of three (3) segregated waste streams. (Industrial washing machines, oil stripping and mixed metal waste waters), in three (3) below grade pre-cast concrete-fiberglass lined oil separation tanks, each @ 9,000 gallons, then pre-settling in three (3) below grade pre-cast concrete fiberglass lined settling tanks each @ 9,000 gallons, and fitted with air and CO<sub>2</sub> diffusers for mixing and PH adjustment.

The waste waters after pre-treatment by oil separation and pre-settling are pumped from three (3) separated concrete wet wells, each fitted with a 100 GPM vertical centrifugal pump which delivers each of the waste waters to one of the three interior steel treatment tanks, each with a capacity of 10,000 gallons. Each treatment tank contains a vertical paddle wheel flocculator, air and CO<sub>2</sub> diffusers and oil skimming flow weirs, and variable take off effluent drains.

The first treatment consists of the addition to the effluent as follows: Calcium Hydroxide (Ca(OH)<sub>2</sub>), Sodium Sulfide (Na<sub>2</sub>S), Calcium Chloride (CaCl<sub>2</sub>), Carbon Dioxide (CO<sub>2</sub>) and cationic and non ionic poly electrolyte. The effluent is flocculated and allowed to settle overnight.

On the following day, this pre-treated effluent is transferred by pump to tank #2 for the second treatment.

The second treatment consists of the addition to the pre-treated effluent as follows:

Activated carbon, Aluminum Sulfate ( $Al_2(SO_4)_3$ ) and an ionic poly electrolyte. This is flocculated for thorough mixing and allowed to settle overnight. The following day this treated effluent is pumped through the plate and frame shriver filter (this filter was previously prepared and charged with Diatomaceous earth, super cell and sorbo-cell)

This will filter out the remaining suspended solids, oil and grease. The effluent is then treated with ( $H_2O_2$ ) Hydrogen peroxide for sulfide destruction and pumped into the below grade holding tank, equipped with aeration devices to prevent an anaerobic state from occurring.

The effluent is now tested thru the atomic absorption system, and if sewer discharge limitations are met for all parameters, this effluent is pumped into the sewer system. All discharges are recorded on a tamper proof flow meter, monitored and tested by the Nassau County Department of Public Works Cedar Creek Laboratory and evaluated against an Independent Laboratory Analysis by H2M.

#### HOW WE HANDLE OUR SOLID WASTE

After our effluent has been treated and discharged, the treatment plant operator opens the filter press and removes the spent diatomite from the curtained frames. Approximately 200 lbs. of Filter aid are used. This solid waste is directly placed into 55 gallon steel drums which have been lined with a 3 mil liner, and placed in a holding area within our warehouse. Other solid waste includes our Metal Hydroxide sludges; a by product of our treatment process. These sludges consist of carbon-lime-sulfide and precipitated metals (Fe, Ni, Cr, Cu, Zn).

These sludges are directly routed from our treatment tanks to a below grade, non-leaching (final settling) Tanks via sealed pipeline engineered for this purpose.

From here, RGM (carrier #18A033) EPA I.D. No. NY0050592807 972 Nicolls Road, Farmingdale, N.Y. utilizes a vacuum truck, purchased from Super Products Registered (DIA-REO) capable of holding 15 cubic yards of solid waste.

For the present and past years, the John Hassall, Inc. Waste Treatment and Solid Waste Storage Facility has been maintained in excellent operating order. All required paper work for the varied agencies, be they County, State or Government have been forwarded to the proper office, recorded in the correct manner, and the copies provided to wherever necessary. The facility does not endanger wildlife, fish, land or water resources, flood planes or human life.

The facilities shall be maintained and operated so as to function in accordance with the permit when issued, and the designed and intended use of the facility. All equipment in use in this facility shall be maintained to operate effectively.

A contingency plan approved by the Department of Environmental Conservation for any and all emergency situations shall be implemented in accordance with the plan's terms as outlined here in.



HASSALL, INC. • WESTBURY • LONG ISLAND • N.Y. • 11590

Tel. 516 • 334-6200 • Telex No. 144535

OUR HAZARDOUS WASTES

Degreasing Solvents

1. Chlorinated Safety Solvents
2. Spent Freon
3. VG 1.1.1

OUR INDUSTRIAL WASTES

Spent Stoddard Solvent combined with both cutting and lubricating oils

(these oils may contain sulfur, paraffin base oils, combined chlorine and phosphorous.)

Spent Diatomite - (filter aid) containing small amounts of carbon, oil or grease and trace metals. (Fe, Ni, Cr, Cu, Zn)

Carbon/Lime Slurry - by product of Industrial Waste Water Pre-treatment plant

## CLOSURE AND POST CLOSURE

The closure plan as herein defined is in reference to the present hazardous waste storage facility. As determined, the waste would most likely consist of spent trichloroethane and freon T.M.C., on occasion minimum amounts of spent nickel solution. In the event of closure the halogenated waste could be routed to Baron Blakeslee or Pride Solvent for recovery. The Ni (if any) would be disposed through Chemical Management for precipitation of said wastes (approx. cost - less than \$1,000).

In addition to our hazardous waste, John Hassall generates the following industrial wastes:

- (1) hydraulic, lube, cutting oils and mineral spirits (miscible with oils).
- (2) Waste water containing Cu, Cr, Ni, Fe, oil and grease - not exhibiting listed or characteristic hazardous waste.
- (3) Associated waste water sludges.

The spent oils would be pumped into a certified waste oil recovery truck (usually at no cost - these products can be salvaged for resale).

The industrial waste water and associated sludges would be pumped out - treated - dewatered and placed in a secure landfill. The below grade tanks would be cleaned and loaded with clean fill.



manifest are recorded, filed and mailed to the proper authorities.

LIST OF PERMIT NUMBERS

John Hassall, Inc. 516-334-6200  
Cantiague Rock Road  
Westbury, N.Y. 11590

EPA Permit No. NY 000 2045417

Certified Waste Oil-Jim Hack 516-352-6194  
320 Courthouse Road  
Franklin Square, L.I., N.Y. 11010

DEC NY Permit No. IA-052  
Vehicle License No. 56626 GB

RGM Liquid Waste Removal Corp. 516-586-0002  
972 Nicolls Road  
Deer Park, N.Y. 11729

EPA Permit No. NYD 050592807  
DEC NY Permit No. 1A-033

Callia Bros. 1-212-387-8300  
363 Maspeth Avenue  
Brooklyn, N.Y. 55211

EPA Permit No. NYD 980647283

Chemical Management Inc. 516-454-6766  
340 Eastern Parkway  
Farminedale, N.Y. 11735


EPA Permit No. NYD 000691949

Baron Blakeslee 201-687-7383  
49 Central Ave.  
S. Kearney, N.J.

EPA Permit No. NJD 048810279

Pride Solvents Inc. 516-643-4800  
78-88 Lamar St.  
West Babylon, N.Y. 11704

EPA Permit No. NYD 057722258



TE F.

UNDEVELOPED

WESTBURY DRIVE-IN

650 FT.

422 FT.

BRINEMAN  
INSTRUMENT

PROPERTY LINE

650 FT.

CANTIAQUE ROCK ROAD

600 FT.

TOR BAY  
RUN

PERICHO  
WATER  
DISTRICT

SARATOGA DRIVE

RESIDENT

NO SCALE



ESTABLISHED 1850

N HASSALL, INC. • WESTBURY • LONG ISLAND • N.Y. • 1159

Tel. 516-334-6200 • Telex No. 144585

### WASTE ANALYSIS PLAN

Hazardous waste generated by John Hassall, Inc. is routinely checked to assure proper substance identification, analysis is performed on site prior to shipping.

The constituents of industrial waste water and associated sludges remain qualitatively the same although quantities will differ.

Samples are taken on a "grab" basis and are considered most representative of the materials in question. Thorough and continuous mixing is achieved by the use of large paddle wheel flocculators within these treatment tanks. Samples are taken off side ports. This sample is then placed into properly labeled sample jars, which have been previously prepared by an Independent Laboratory (H2M) for forwarding to them for analysis. A test method sheet has been enclosed.

All raw waste water and sludges are currently and routinely being sent for E.P. Toxicity analysis on a semi-annual basis.

Oily waste is currently being analyzed on an annual basis.



ESTABLISHED 1850

HASSALL, INC. · WESTBURY · LONG ISLAND · N.Y. · 1159

Tel. 516-334-6200 • Telex No. 144585

### REPAIR AND INSPECTION OF DRUMS


All drums of hazardous waste are to be maintained in accordance with applicable regulations. All drums used are to be free of any leaks whatsoever and sealed tightly at the bung openings. Hazardous waste labels bearing all applicable information are to be fastened to the drum for proper identification and correspond to a hazardous waste manifest.

Drums are to be stored in the hazardous waste storage area located within our fully enclosed warehouse. They are to be clean, dry and free of dirt. Furthermore, they are to be placed on pallets, not exceeding two drums in height and inspected at least once a week for signs of leaks. If a drum is found to be leaking immediate action must be taken to arrest any contaminants that may have escaped - Hi dry (clay) will be used to absorb any such leak and the spent Hi dry itself placed into a Hazardous Waste Drum bearing all necessary information.

Any remaining hazardous waste will be pumped out of the drum exhibiting the leak and placed into a drum which is leak free. Once again, proper steps to insure labeling and handling will be followed. The damaged drum will be triple rinsed and disposed of with the general scrap.

REFERENCE NO. 11

H2M CORP.



ROBERT G. HOLZMACHER, P.E., P.P., L.S.  
SAMUEL C. McLENDON, P.E.  
HUGO D. FREUDENTHAL, Ph.D.  
NORMAN E. MURRELL, P.E.  
ELIAS S. KALOGERAS, P.E.  
HAROLD A. DOMBECK, P.E.  
ROBERT H. ALBANESE, P.E.

HOLZMACHER, McLENDON and MURRELL

Consulting Engineers, Environmental Scientists & Planners

500 BROAD HOLLOW ROAD, MELVILLE, N. Y. 11746 • (516) 694-3043  
40 PARK PLACE, NEWTON, N. J. 07860 • (201) 383-3544

August 28, 1975

Nassau County Department of Health  
240 Old Country Road  
Mineola, New York 11501

Re: John Hassall, Inc.  
SPDES No. NY0076287  
Ref. No. 28-0077

Attention: Mr. John Welsch

Gentlemen:

Enclosed herewith, please find the SPDES Monitoring Report for the above referenced facility for the month of August 1975. Please note that the third column under "FLOW (GPD)" has been modified to include pH readings.

As you will note, the values for total chromium, total iron, total nickel and oil and grease are all above those specified in John Hassall's SPDES permit. Based upon the suggested interim standards presented in your correspondence of August 9, 1975, the value for total chromium of 27.0 mg/l exceeds the interim requirement of 17.5 mg/l and the total iron value of 66.0 mg/l exceeds the interim requirement of 15.0 mg/l. These values appear high, we believe, due to not wasting sludge from the precipitation step frequently enough. After this was done, the value for iron went down to 8.8 mg/l on the first batch for August.


The performance of the system is limited at the present time, since we do not yet have a polishing filter. When the filter is installed, performance will be at the required permanent effluent limitation level.

There is only one batch reported for July, since there was a plant shutdown of approximately two weeks during the month and only one batch was discharged.

If you have any questions regarding this report, please call or write our office.

Very truly yours,

H2M CORP.

  
John J. Molloy  
Project Engineer

JJM/mb  
enc.

CC: Mr. Karl Horlitz  
Mr. Dennis Moran  
Mr. Russell Mt. Pleasant, P. E.



ROBERT G. HOLZMACHER, P.E.  
SAMUEL C. McLENDON, P.E.  
NORMAN E. MURRELL, P.E.  
ELIAS S. KALOGERAS, P.E.  
HAROLD A. DOMBECK, P.E.  
ROBERT H. ALBANESE, P.E.

HOLZMACHER, McLENDON and MURRELL, P.C. / Consulting Engineers  
500 BROAD HOLLOW ROAD, MELVILLE, NEW YORK 11746  
(516) 694-3040

September 15, 1975

Nassau County Dept. of Health  
240 Old Country Road  
Mineola, New York 11501

Re: John Hassall, Inc.  
SPDES No. NY0076287

Attention: Mr. John Welsch

Gentlemen:

Enclosed please find the SPDES Monitoring Report for the above referenced facility for the month of August 1975.


Please be advised that all reported values for the August samples are within the proposed interim standards. The value for oil and grease (20.4 mg/l), however, is above the final permit condition of 10 mg/l. Until such time as the effluent polishing filter is installed, we will occasionally experience constituent values which exceed the interim and final standards. When the polishing filter is installed, permit conditions for all parameters should be met consistently.

Our previous submission to you was for the month of July, not August, as indicated in the transmittal letter.

If there are any questions in regard to the above, please call or write our office.

Very truly yours,


HOLZMACHER, McLENDON & MURRELL, P. C.

  
John J. Molloy  
Project Engineer

JJM/mb  
enc.

CC: Mr. Karl Horlitz  
Mr. Dennis Moran  
Mr. Russell Mt. Pleasant, P.E.





ROBERT G. HOLZMACHER, P.E.  
SAMUEL C. McLENDON, P.E.  
NORMAN E. MURRELL, P.E.  
ELIAS S. KALOGERAS, P.E.  
HAROLD A. DOMBECK, P.E.  
ROBERT H. ALBANESE, P.E.

HOLZMACHER, McLENDON and MURRELL, P.C. / Consulting Engineers

500 BROAD HOLLOW ROAD, MELVILLE, NEW YORK 11746

(516) 694-3040

November 11, 1975

Nassau County Health Department  
240 Old Country Road  
Mineola, New York 11501

Re: John Hassall, Inc.  
SPDES No. NY0076287

Attention: Mr. John Welsch

Gentlemen:

Enclosed please find the SPDES monitoring report for the above referenced facility for the month of October, 1975.

The poor performance during the month of October is attributed to metals carry over from the below grade settling tanks. Over the past year's operation, sludge buildup in these tanks had reached the point where solids carry over into the treatment plant was noted. The situation was corrected by having all below grade settling tanks pumped out by scavenger service. Increased efficiencies should be noted in next month's performance.

Please note that the final effluent polishing filter should arrive on schedule in early December. Once the filter is installed and process modifications are implemented, final effluent standards will be met. Our original schedule of February 1, 1976 for full compliance still appears very favorable.

If you have any questions concerning the enclosed, please contact the writer at your convenience.

Very truly yours,

HOLZMACHER, McLENDON & MURRELL, P. C.

  
John J. Molloy

JJM/mb  
enc.

CC: Mr. Russell Mt. Pleasant, P. E.  
Mr. Dennis Moran  
Mr. Karl Horlitz



ROBERT G. HOLZMACHER P.E., L.S.  
SAMUEL C. McLENDON P.E.  
NORMAN E. MURRELL, P.E.  
ELIAS S. KALOGERAS, P.E.  
HAROLD A. DOMBECK, P.E.  
ROBERT H. ALBANESE, P.E.

HOLZMACHER, McLENDON and MURRELL, P.C. / Consulting Engineers

500 BROAD HOLLOW ROAD, MELVILLE, NEW YORK 11746

(516) 694-3040

December 12, 1975

Nassau County Health Department  
240 Old Country Road  
Mineola, New York 11501

Re: John Hassall, Inc.  
SPDES No. NY0076287

Attention: Mr. John Welsch

Gentlemen:

Enclosed please find the SPDES monitoring report for the above referenced facility for the month of November 1975.


For this reporting period, the iron, oil and grease and chromium (total) have exceeded the permit conditions. Despite their non-compliance, the treatment plant has shown limited improvement from last month's performance. We are attributing the improved performance to the pumpdown of the below grade tanks.

The polishing filter has arrived and been mounted in place. We now await delivery of the precoat tank and some valves before the construction will be completed. The overall timing still appears to be as originally laid out with the installation to be completed by mid January 1976 and starting operations to be completed by February 1976.

If you have any questions, please do not hesitate to contact our office.

Very truly yours,

HOLZMACHER, McLENDON & MURRELL, P. C.

  
John J. Molloy

JJM/mb  
enc.

CC: Mr. Russell Mt. Pleasant, P.E.  
Mr. Dennis Moran  
Mr. Karl Horlitz

ROBERT G. HOLZMACHER, P.E., P.P., L.S.  
SAMUEL C. McLENDON, P.E.  
NORMAN E. MURRELL, P.E.  
HUGO D. FREUDENTHAL, Ph.D.  
HAROLD A. DOMBECK, P.E.  
ROBERT H. ALBANESE, P.E.

ISRAEL WILENITZ, Ph.D., P.E.  
CARL E. BECKER, P.E.  
CHRISTOPHER POWERS, P.E.  
CHARLES E. BANKS, P.E.  
FRANK N. COPPA, P.E.

H2M CORP.



HOLZMACHER, McLENDON and MURRELL, P.C.

Consulting Engineers, Environmental Scientists & Planners  
500 BROAD HOLLOW ROAD, MELVILLE, N. Y. 11746 • (516) 494-3040  
40 PARK PLACE, NEWTON, N. J. 07860 • (201) 383-3544

February 24, 1976

Nassau County Health Department  
240 Old Country Road  
Mineola, New York 11501

Re: John Hassall, Inc.  
SPDES Permit No.  
NY0076287

Attention: Mr. John Welsch

Gentlemen:

Enclosed please find the SPDES Industrial Discharge Monitoring Report for the above referenced Facility for the month of January 1976. With the exception of the Oil & Grease, all parameters are within the interim permit limitations.

With respect to the installation of the final effluent and polishing filter, please be advised that construction has been completed and that startup operations are proceeding. There have been no batches discharged for the month of February for which we would have to meet final effluent limitations.

We will keep your office appraised of our progress in this regard. If you have any questions or comments, please call or write this office.

Very truly yours,

HOLZMACHER, McLENDON & MURRELL, P.C.

  
John J. Malloy  
Project Engineer

JJM:jj  
Enc.

cc: Mr. Russell Mt. Pleasant, P.E., Albany  
Mr. Dennis Moran, NYSDEC, Stony Brook  
Mr. Karl Horlitz, John Hassall

JOHN G. HOLZWACHER, P.E., P.P., L.S.  
SAMUEL C. McLENDON, P.E.  
NORMAN E. MURRELL, P.E.  
HUGO D. FREUDENTHAL, Ph.D.  
HAROLD A. DOMBECK, P.E.  
ROBERT H. ALBANESE, P.E.

ISRAEL WILENITZ, Ph.D., P.E.  
CARL E. BECKER, P.E.  
CHRISTOPHER POWERS, P.E.  
CHARLES E. BANKS, P.E.  
FRANK N. COPPA, P.E.

H2M CORP.



HOLZWACHER, McLENDON and MURRELL, P.C.

Consulting Engineers, Environmental Scientists & Planners

500 BROAD HOLLOW ROAD, MELVILLE, N. Y. 11746 • (516) 694-3040

40 PARK PLACE, NEWTON, N. J. 07860 • (201) 383-3544

April 20, 1976

Nassau County Health Dept.  
240 Old Country Road  
Mineola, New York 11501

Re: John Hassall, Inc.  
SPDES Permit No. NY0076287  
EVLI75-3

Attention: Mr. John Welsch

Gentlemen:

Enclosed please find the SPDES Industrial Discharge Monitoring Report for the above referenced facility for the month of March, 1976.

Effluent data for the month indicates that average values for total chromium, iron, and nickel exceeded permit conditions. Average effluent values for hexavalent chromium, copper and oil and grease were within permit conditions. Data for March 31 indicates that the copper value for that batch exceeded permit conditions.

As you will recall from our previous monthly report, nickel was of particular concern and the data for March indicates steady improvement of the effluent value for nickel. The final batch met the standard for nickel. However, attempts at resolving nickel problems has apparently caused a deterioration in both iron and chromium values.

Since we have been attempting various process changes (principally pH control and chemical addition rate) during the last two months, we felt that some contamination has occurred in the final clarifier. In order to rectify this situation, the clarifier was washed down and cleaned after the first batch in April. We still await further processing to determine whether the situation has improved. If further attempts at treatment plant optimization fail to yield satisfactory results,

*we will attempt to further  
isolate waste streams*

ED. MURPHY, P.E.  
IAN E. MURRELL, P.E.  
HUGO D. FREUDENTHAL, PH.D.  
HEROLD A. DOMBECK, P.E.  
ROBERT H. ALBANESE, P.E.

ISRAEL WILENITZ, PH.D., P.E.  
CARL E. BECKER, P.E.  
CHRISTOPHER POWERS, P.E.  
CHARLES E. BANKS, P.E.  
FRANK N. COPPA, P.E.

H2M CORP.



HOLZMACHER, McLENDON and MURRELL, P.C.

Consulting Engineers, Environmental Scientists & Planners  
300 BROAD HOLLOW ROAD, MELVILLE, N. Y. 11746 • (516) 694-3040  
40 PARK PLACE, NEWTON, N. J. 07860 • (201) 383-3544

May 4, 1976

Mr. Karl Horlitz, Plant Manager  
John Hassall, Incorporated  
Cantiague Rock Road  
P.O. Box 366  
Westbury, New York 11590

Re: Wastewater Treatment  
MI73-11

Dear Karl:

We have been providing ongoing engineering services to bring your wastewater treatment plant within ground water effluent limitations. This work has led us to conclude that this process, as currently operated, cannot meet these objectives.

Our work since early February, 1976 has been directed at starting up the polishing filter and gaining operational experience with it. This work has been successful, but we have not been able to achieve SPDES limitations for three of the required constituents: nickel, iron, and total chromium. We have been able to adequately and consistently treat for copper, hexavalent chromium and oil and grease.

As you are well aware, the problems we have experienced with your grossly polluted wastewater have been substantial. The very high oil and solvent content, the high dissolved solids levels, and the mixed metal nature of your wastewater leaves little flexibility in processing with what has been recognized as the best available technology.

The treatment process we have been employing is based upon employing calcium chloride to break the oil in water emulsion and sodium sulfide to reduce hexavalent chromium and precipitate the

heavy metals as sulfides. Sorbocell ( an alum activated diatomaceous earth) is used to absorb residual oils and serves as a body feed during filtration. Powdered activated carbon is also employed and serves to lower the chemical oxygen demand (COD) of your wastewater, while also removing color and odor.

We have to a large extent been successful in treating your wastewater, but have not been able to completely meet objectives. The effluent data since February, 1976, when the polishing filter became operational, indicates:

<u>CONSTITUTENT</u>	<u>UNTREATED</u> mg/l	<u>EFFLUENT</u> mg/l	<u>SPDES LIMIT</u> mg/l
Copper	65	0.12	0.4
Iron	80	2.8	0.6
Nickel	50	3.9	1.0
Chromium	65	3.9	1.0
Hexavalent Chromium	5	0.03	0.1
Oil and Grease	-	10	10

Although we have closely approached effluent limitations, we do not appear to be able to increase performance beyond these levels with present process chemistry. We have attempted, both on a laboratory and full scale basis, all reasonable possibilities on pH adjustment, chemical addition rate, order of reactions and frequency of filtration without satisfactory results.

Since we feel that the remaining metals are neither suspended or tied-up organically, they must be complexed inorganically or the limits of co-precipitation with this process chemistry has been reached. In order to limit the potential for soluble chloride complex formation and to test the limits of hydroxide co-precipitation, we recommend that a full scale evaluation of lime treatment be made. Lime will not only enable us to employ hydroxide precipitation, but also should provide the emulsion breaking characteristics of calcium chloride. The sodium sulfide feed rate will be lowered and held to only that which is required to accomplish hexavalent chromium reduction under alkaline conditions.

Treatment plant processing will be patterned directly from the existing and will include lime precipitation, followed by recarbona-


HOLZMACHER, McLENDON and MURRELL, P.C. / Consulting Engineers

tion, Sorbocell body feed, filtration, and carbon contracting. We feel that eight weeks will be required to fully evaluate these process modifications. Initial results for the modified process should become apparent after the week of May 10, 1976.

If you have any questions, please call or write this office.

Yours very truly,

HOLZMACHER, McLENDON AND MURRELL, P.C.

  
John J. Molloy  
Project Engineer

JJM/sh  
cc: Mr. John Welsch

ROBERT C. HOLZMACHER, P.E., P.P., L.S.  
SAMUEL C. McLENDON, P.E.  
NORMAN E. MURRELL, P.E.  
HUGO D. FREUDENTHAL, Ph.D.  
HAROLD A. DOMBECK, P.E.  
ROBERT H. ALBANESE, P.E.

ISRAEL WILENITZ, Ph.D., P.E.  
CARL E. BECKER, P.E.  
CHRISTOPHER POWERS, P.E.  
CHARLES E. BANKS, P.E.  
FRANK N. COPPA, P.E.

H2M CORP.



HOLZMACHER, McLENDON and MURRELL, P.C.

Consulting Engineers, Environmental Scientists & Planners  
500 BROAD HOLLOW ROAD, MELVILLE, N. Y. 11746 • (516) 694-3040  
40 PARK PLACE, NEWTON, N. J. 07860 • (201) 383-3544

June 16, 1976

Mr. John Welsch  
Nassau County Health Department  
240 Old Country Road  
Mineola, New York 11501

Re: John Hassall, Inc.  
SPDES Permit No. NY 0076287  
MI73-11

Dear John:

As you are aware from our previous correspondence for the above referenced facility, we are experiencing problems in attaining final effluent limitations.

Our attempts since February, 1976, when all planned construction was completed, have been directed at achieving compliance with ground water standards with a sulfide-calcium chloride system followed by activated carbon adsorption and filtration. We were unsuccessful in achieving compliance employing this system. Therefore, we switched into a lime-sulfide system in late May, 1976. Currently we are attempting to optimize this system and cannot yet meet ground water standards.

We will require additional time to fully evaluate this revised processing format and explore the feasibility of further segregation within the manufacturing area. If our attempts in this regard are still unable to achieve objectives, we will have to develop definitive plans for upgrading the system to achieve operational levels.

The need for further time to evaluate the lime-sulfide system and to develop contingency plans in the event of failure to achieve compliance, necessitates our requesting a modification to the compliance schedule for John Hassall, Inc. Therefore, we hereby request that a modified compliance schedule be added to the John Hassall permit. We request that the schedule be amended so that achievement of operational levels be delayed until November, 1976.



MACHER, McLENDON and MURRELL, P.C. / Consulting Engineers

Mr. John Welsch  
Nassau County Health Dept.


2

June 16, 1976

Considering all the time and effort expended to date on this project, we feel that the additional time requested can be readily justified. If you have any questions, or require more information, please call or write this office.

Very truly yours,

HOLZMACHER, McLENDON & MURRELL, P.C.



John J. Molloy  
Project Engineer

JJM/jj

cc: Mr. Karl Horlitz

ROBERT G. HOLZMACHER, P.E., P.P., L.S.

SAMUEL C. McLENDON, P.E.

NORMAN E. MURRELL, P.E.

HUGO D. FREUDENTHAL, Ph.D.

HAROLD A. DOMBECK, P.E.

ROBERT H. ALBANESE, P.E.

ISRAEL WILENITZ, Ph.D., P.E.

CARL E. BECKER, P.E.

CHRISTOPHER POWERS, P.E.

CHARLES E. BANKS, P.E.

FRANK N. COPPA, P.E.

H2M CORP.



HOLZMACHER, McLENDON and MURRELL, P.C.

Consulting Engineers, Environmental Scientists & Planners

500 BROAD HOLLOW ROAD, MELVILLE, N. Y. 11746 • (516) 694-3040

40 PARK PLACE, NEWTON, N. J. 07860 • (201) 383-3544

August 20, 1976

Nassau County Department of Health  
240 Old Country Road  
Mineola, New York 11501

Re: John Hassall, Inc.  
SPDES Permit No. NY0076287  
EVLI 75-3

Attention: Mr. John F. Welsch

Gentlemen:

Enclosed please find the SPDES Industrial Discharge Monitoring Report for the above-referenced facility for the month of July 1976.

Effluent data for the month indicates that average values for total chromium, iron and nickel exceeded permit limitations. Average and individual effluent values for copper, hexavalent chromium and oil and grease were within permit conditions.

The effluent data for the month reflects the process changes we have implemented in order to resolve the control problems for nickel, iron and chromium. The data presented is based on our modified lime-sulfide process and the results continue to be encouraging. We are currently attempting to optimize the modified process to achieve our permit limitations. We will keep you apprised of our progress in this regard.

If you have any questions or comments, please call or write our office.

Very truly yours,

H2M CORP.

John J. Molloy  
Project Engineer

SCW/abc

CC: Russell Mt. Pleasant, P.E.  
Dennis Moran, NYSDEC  
Karl Horlitz

HOLZMACHER, P.E., P.P., L.S.  
McLENDON, P.E.  
MURRELL, P.E.  
HUGO C. FREUDENTHAL, Ph.D.  
HAROLD A. DOMBECK, P.E.  
ROBERT H. ALBANESE, P.E.

ISRAEL WILENITZ, Ph.D., P.E.  
CARL E. BECKER, P.E.  
CHRISTOPHER POWERS, P.E.  
CHARLES E. BANKS, P.E.  
FRANK N. COPPA, P.E.

H2M CORP.



HOLZMACHER, McLENDON and MURRELL, P.C.

Consulting Engineers, Environmental Scientists & Planners  
500 BROAD HOLLOW ROAD, MELVILLE, N. Y. 11746 • (516) 694-3040  
40 PARK PLACE, NEWTON, N. J. 07860 • (201) 383-3544

September 29, 1976

Nassau County Department of Health  
240 Old Country Road  
Mineola, New York 11501

Re: John Hassall, Inc.  
SPDES Permit No. NY0076287  
EVLI 75-3

Attention: Mr. John F. Welsch

Gentlemen:

Enclosed please find the SPDES Industrial Discharge Monitoring Report for the above referenced facility for the month of August 1976.

Effluent data for the month indicates that average values for total chromium, iron and nickel exceeded permit limitations. Average and individual effluent values for copper, hexavalent chromium and oil and grease were within permit conditions.

The effluent data for the month reflects the process changes we have implemented in order to resolve the control problems for nickel, iron and chromium. The data presented is based on our modified lime-sulfide process and the results continue to be encouraging. We are currently attempting to optimize the modified process to achieve our permit limitations. We will keep you apprised of our progress in this regard.

If you have any questions or comments, please call or write our office.

Very truly yours,

H2M CORP.

  
John J. Molloy  
Project Engineer

JJM/jj  
Enc.

cc: Russell Mt. Pleasant, P.E.  
Dennis Moran, NYSDEC  
Karl Horlitz

ROBERT G. HOLZMACHER, P.E.  
SAMUEL C. McLENDON, P.E.  
NORMAN E. MURRELL, P.E.  
HUGO D. FREUDENTHAL, P.E.  
HAROLD A. DOMBECK, P.E.  
ROBERT M. ALBANESE, P.E.

CARL E. BECKER, P.E.  
CHRISTOPHER POWERS, P.E.  
CHARLES E. BANKS, P.E.  
FRANK N. COPPA, P.E.

## H2M CORP.



**HOLZMACHER, McLENDON and MURRELL, P.C.**

Consulting Engineers, Environmental Scientists & Planners

500 BROAD HOLLOW ROAD, MELVILLE, N.Y. 11746 (516) 694-3040 ☐

341 CONKLIN STREET, FARMINGDALE, N.Y. 11735 (516) 694-3410 ☐

40 PARK PLACE, NEWTON, N.J. 07806 (201) 383-3544 ☐

October 22, 1976

Nassau County Department of Health  
240 Old Country Road  
Mineola, New York 11501

Re: John Hassall, Inc.  
SPDES Permit No. NY0076287  
EVLI 75-3

Attention: Mr. John F. Welsch

Gentlemen:

Enclosed please find the SPDES Industrial Discharge Monitoring Report for the above-referenced facility for the month of September 1976.

Effluent data for the month indicates that average values for total chromium, copper, iron and nickel exceeded permit limitations. Average effluent values for hexavalent chromium and oil and grease were within permit conditions.

The effluent data for the month reflects the process changes we have implemented in order to resolve the control problems for nickel, iron and chromium. The changes recently implemented have resulted in poorer system performance. Therefore, we have reverted back to our lime-sulfide system, which gave us good performance in earlier reports. After we get the system back under control, we will attempt to increase performance by process optimization.

If you have any questions or comments, please call or write our office.

Very truly yours,

H2M CORP.

  
John J. Molloy  
Project Engineer

JJM/abc  
Enclosure

CC: Russell Mt. Pleasant, P.E.  
Dennis Moran, NYSDEC  
Karl Horlitz

ROBERT G. HOLZMACHER, P.E., P.P., L.S.  
SAMUEL C. McLENDON, P.E.  
NORMAN E. MURRELL, P.E.  
HUGO D. FREUDENTHAL, Ph.D.  
HAROLD A. DOMBECK, P.E.  
ROBERT H. ALBANESE, P.E.

CARL E. BECKER, P.E.  
CHRISTOPHER POWERS, P.E.  
CHARLES E. BANKS, P.E.  
FRANK N. COPPA, P.E.

## H2M CORP.



**HOLZMACHER, McLENDON and MURRELL, P.C.**

Consulting Engineers, Environmental Scientists & Planners

500 BROAD HOLLOW ROAD, MELVILLE, N.Y. 11746 (516) 694-3040

341 CONKLIN STREET, FARMINGDALE, N.Y. 11735 (516) 694-3410

40 PARK PLACE, NEWTON, N.J. 07860 (201) 383-3544

January 25, 1977

Nassau County Department of Health  
340 Old Country Road  
Mineola, New York 11501

Re: John Hassall, Inc.  
SPDES Permit No. NY0076287  
EVLI 75-3

Attention: Mr. John F. Welsch

Gentlemen:

Enclosed please find the SPDES Industrial Discharge Monitoring Report for the above referenced facility for the month of December, 1976.

Effluent data for the month indicates that average values for total chromium, copper, iron and nickel exceeded permit limitations. Average effluent values for hexavalent chromium were within permit conditions.

The effluent data for the month reflects the process changes we have implemented in order to resolve the control problems for nickel, iron and chromium. The changes recently implemented have resulted in poorer system performances. Therefore, we have reverted back to our lime-sulfide system, which gave us good performance in earlier reports. After we get the system back under control, we will attempt to increase performance by process optimization.

If you have any questions or comments, please call or write our office.

Very truly yours,

H 2 M CORP.

JJM:sh

CC: Russell Mt. Pleasant, P.E.  
Dennis Moran, NYSDEC  
Karl Horlitz

John J. Molloy  
Project Engineer

HOLZMACHER, McLENDON & MURRELL, P.C.  
J.C. McLENDON, P.E.  
MAN E. MURRELL, P.E.  
JUGO D. FREUDENTHAL, Ph.D.  
HAROLD A. DOMBECK, P.E.  
ROBERT H. ALBANESE, P.E.

CARL E. BECKER, P.E.  
CHRISTOPHER POWERS, P.E.  
CHARLES E. BANKS, P.E.  
FRANK N. COPPA, P.E.

## H2M CORP.



**HOLZMACHER, McLENDON and MURRELL, P.C.**

Consulting Engineers, Environmental Scientists & Planners

500 BROAD HOLLOW ROAD, MELVILLE, N.Y. 11746 (516) 694-3040 ☒

341 CONKLIN STREET, FARMINGDALE, N.Y. 11735 (516) 694-3410 ☐

40 PARK PLACE, NEWTON, N.J. 07860 (201) 383-3544 ☐

February 25, 1977

Nassau County  
Department of Health  
240 Old Country Road  
Mineola, New York 11501

Re: John Hassall, Inc.  
SPDES Permit NO. NY0076287  
EVLI 75-3

Attention: Mr. John F. Welsch

Gentlemen:

Enclosed please find the SPDES Industrial Discharge Monitoring Report for the above-referenced facility for the month of January, 1977.

Effluent data for the month indicates that average values for total chromium, iron and nickel exceeded permit limitations. Average effluent values for hexavalent chromium and copper were within permit conditions.

The effluent data for the month reflects the continued difficulty in resolving the control problems for nickel, iron and chromium. The changes recently implemented have resulted in somewhat better performance. However, even after reverting back to our lime-sulfide system, we are still unable to meet final effluent limitations. In this regard, we are currently having waste water from the industrial washing machine evaluated for emulsified oil removal by ultra-filtration. We are also evaluating the feasibility of employing ultra-filtration as a final polish for our filter effluent. We will keep your office advised concerning our progress in these matters.

If you have any questions or comments, please call or write our office.

Very truly yours,

HOLZMACHER, McLENDON & MURRELL, P.C.

JJM:abc  
CC: R. Mt. Pleasant, P.E.  
T. Snyder (NYSDEC)  
K. Horlitz

  
John J. Molloy  
Project Engineer

ROBERT G. HOLZMACHER, P.E., P.P., L.S.  
SAMUEL C. McLENDON, P.E.  
NORMAN E. MURRELL, P.E.  
HUGO D. FREUDENTHAL, Ph.D.  
CAROL A. DOMBECK, P.E.  
ROBERT H. ALBANESE, P.E.

CARL E. BECKER, P.E.  
CHRISTOPHER POWERS, P.E.  
CHARLES E. BANKS, P.E.  
FRANK N. COPPA, P.E.

## H2M CORP.



**HOLZMACHER, McLENDON and MURRELL, P.C.**

Consulting Engineers, Environmental Scientists & Planners

500 BROAD HOLLOW ROAD, MELVILLE, N.Y. 11746 (516) 694-3040 ☒

341 CONKLIN STREET, FARMINGDALE, N.Y. 11735 (516) 694-3410 ☐

40 PARK PLACE, NEWTON, N.J. 07860 (201) 383-3544 ☐

March 25, 1977

Nassau County  
Department of Health  
240 Old Country Road  
Mineola, New York 11501

Re: John Hassall, Inc.  
SPDES Permit No. NY0076287  
EVLI 75-3

Attention: Mr. John F. Welsch

Gentlemen:

Enclosed please find the SPDES Industrial Discharge Monitoring Report for the above-referenced facility for the month of February 1977.


Effluent data for the month indicates that average values for total chromium, iron and nickel exceeded permit limitations. Average effluent values for hexavalent chromium, oil and grease, and copper were within permit conditions.

The effluent data for the month reflects the continued difficulty in resolving the control problems for nickel, iron and chromium. The changes recently implemented have resulted in somewhat better performance. However, even after reverting back to our lime-sulfide system, we are still unable to meet final effluent limitations. In this regard, we are currently having wastewater from the industrial washing machine evaluated for emulsified oil removal by ultra-filtration. We are also evaluating the feasibility of employing ultra-filtration as a final polish for our filter effluent. We will keep your office advised concerning our progress in these matters.

HOLZMACHER, P.E. P.P.L.S.  
SAMUEL C. McLENDON, P.E.  
NORMAN E. MURRELL, P.E.  
HUGO D. FREUDENTHAL, Ph.D.  
HAROLD A. DOMBECK, P.E.  
ROBERT H. ALBANESE, P.E.

CARL E. BECKER, P.E.  
CHRISTOPHER POWERS, P.E.  
CHARLES E. BANKS, P.E.  
FRANK N. COPPA, P.E.  
DONALD A. SIOSS, P.E.

## H2M CORP.



**HOLZMACHER, McLENDON and MURRELL, P.C.**

Consulting Engineers, Environmental Scientists & Planners

500 BROAD HOLLOW ROAD, MELVILLE, N.Y. 11746 (516) 694-3040 ☐

341 CONKLIN STREET, FARMINGDALE, N.Y. 11735 (516) 694-3410 ☐

40 PARK PLACE, NEWTON, N.J. 07860 (201) 383-3544 ☐

November 21, 1977

Nassau County Department  
of Health  
240 Old Country Road  
Mineola, New York 11501

Re: John Hassall, Inc.  
SPDES Permit No. NY0076287  
EVLI 75-3

Attention: Mr. John F. Welsch

Gentlemen:

Enclosed please find the SPDES Industrial Discharge  
Monitoring Report for the above referenced facility for  
the month of October, 1977.


Effluent values for oil and grease, total chrome, nickel,  
and iron exceeded permit conditions. Maximum effluent values  
for hexavalent chrome and copper were within permit limitations.

The effluent data reflects continued difficulty in re-  
solving the control problems for nickel and chromium. We will  
keep your office advised concerning our progress in regard to  
correcting these problems.

If you have any questions or comments, please call or  
write this office.

Very truly yours,

HOLZMACHER, McLENDON & MURRELL, P.C.

  
John J. Molloy, P.E.

JJM/jj  
Enc.

cc: R. Mt. Pleasant, P.E.  
T. Snyder (NYSDEC)  
K. Horlitz



ROBERT G. HOLZMACHER, P.E.  
SAMUEL C. McLENDON, P.E.  
NORMAN E. MURRELL, P.E.  
HUGO D. FREUDENTHAL, Ph.D.  
HAROLD A. DOMBECK, P.E.  
ROBERT H. ALBANESE, P.E.

CARL E. BECKER, P.E.  
CHRISTOPHER POWERS, P.E.  
CHARLES E. BANKS, P.E.  
FRANK N. COPPA, P.E.  
DONALD A. SIOSS, P.E.

## H2M CORP.



**HOLZMACHER, McLENDON and MURRELL, P.C.**

Consulting Engineers, Environmental Scientists & Planners

500 BROAD HOLLOW ROAD, MELVILLE, N.Y. 11746 (516) 694-3041

341 CONKLIN STREET, FARMINGDALE, N.Y. 11735 (516) 694-3410

40 PARK PLACE, NEWTON, N.J. 07860 (201) 383-3544

November 11, 1977

Nassau County  
Department of Health  
240 Old Country Road  
Mineola, New York 11501

Re: John Hassall, Inc.  
SPDES Permit No. NY0076287

Attn: Mr. John F. Welsch

Gentlemen:

Enclosed please find the SPDES Industrial Discharge Monitoring Report for the above referenced facility for the month of September, 1977.

Effluent data for the month indicates that maximum values for total chromium, nickel, iron, and oil exceeded permit limitations. Average effluent values for hexavalent chromium and copper were within permit conditions.

The effluent data reflects continued difficulty in resolving the control problems for nickel and chromium. Problems with respect to oil and iron during the month were apparently due to mechanical difficulties with process equipment. This is presently being corrected. We will keep your office advised concerning our progress in regard to correcting these problems.

If you have any questions or comments, please call or write this office.

Very truly yours,

**HOLZMACHER, McLENDON & MURRELL, P.C.**

*John J. Molloy*  
John J. Molloy, P.E.

JJM:sdh  
Encl.

cc: R. Mt. Pleasant, P.E.  
T. Snyder (NYSDEC)  
K. Horlitz

**HOLZMACHER, McLENDON and MURRELL, P.C.**

CONSULTING ENGINEERS, ENVIRONMENTAL SCIENTISTS and PLANNERS

500 BROAD HOLLOW ROAD, MELVILLE, N.Y. 11746 (516) 694-3040 ☐  
560 BROAD HOLLOW ROAD, MELVILLE, N.Y. 11746 (516) 752-9080 ☐  
341 CONKLIN STREET, FARMINGDALE, N.Y. 11735 (516) 694-3410 ☐  
40 PARK PLACE, NEWTON, N.J. 07860 (201) 383-3544 ☐



ROBERT J. HOLZMACHER, P.E.  
SAMUEL J. MCLENDON, P.E.  
NORMAN E. MURRELL, P.E.  
HAROLD A. DOWNEY, P.E.  
HUGO D. FREEDMAN, P.E.  
ROBERT M. ALBANESE, P.E.  
CARL E. BECKER, P.E.  
CHRISTOPHER POWERS, P.E.  
FRANK N. COPPA, P.E.  
JOHN J. MOLLOY, P.E.  
CHARLES E. BANKS, P.E.  
DONALD A. SIOSS, P.E.  
JOHN W. TOWERS, P.E.

June 26, 1978

Nassau County Department of Health  
240 Old Country Road  
Mineola, New York 11501

Re: John Hassall, Inc.  
SPDES Permit No. NY0076257  
EVLI 75-03

Attention: Mr. John F. Welsch

Gentlemen:

Enclosed please find the SPDES Industrial Discharge Monitoring Report for the above referenced facility for the month of May 1978.


Effluent data for the month indicates that maximum values for total chromium, iron, nickel, and oil and grease exceeded permit limitations. All other effluent values were within permit limitations.

→ The effluent data reflects continued difficulty in resolving the control problems for nickel and chromium. We will keep your office advised concerning our progress in regard to correcting these problems.

If you have any questions or comments, please call or write this office.

Very truly yours,

HOLZMACHER, McLENDON & MURRELL, P.C.

  
John J. Molloy, P.E.

RMS/jjj  
Enc.

cc: Mr. R. Mt. Pleasant, P.E.  
Mr. Ted Snyder (NYSDEC)  
Mr. Karl Horlitz

# HOLZMACHER, McLENDON and MURRELL, P.C.

CONSULTING ENGINEERS, ENVIRONMENTAL SCIENTISTS and PLANNERS

575 BROAD HOLLOW ROAD MELVILLE NY 11747 516 694 3040  
560 BROAD HOLLOW ROAD MELVILLE NY 11747 516 752 9060  
175 FULTON STREET FARMINGDALE NY 11735 516 694 3410  
109 WEST MAIN STREET RIVERHEAD NY 11901 516 737 3480  
40 PARK PLACE NEWTON NY 12860 508 383 3544  
TELECOPIER 408 4100 516 752 9060

ROBERT G. HOLZMACHER P.E. P.P.L.S.  
SAMUEL C. McLENDON P.E.  
NORMAN E. MURRELL P.E.  
HAROLD A. DOMBECK P.E.  
HUGO D. FREUDENTHAL Ph.D.  
CARL E. BECKER P.E.  
JOHN J. MOLLOY P.E.  
DONALD A. SIOSS P.E.  
GARY E. LOESCH P.E.  
BRIJ M. SHRIVASTAVA P.E.  
CHARLES E. BANKS P.E.

January 28, 1981

Nassau County Department of Health  
240 Old Country Road  
Mineola, NY 11501

Re: John Hassall, Inc.  
SPDES Permit No. NY0076287

Attention: Mr. Joseph Schechter

Gentlemen:

Enclosed please find the SPDES Industrial Discharge  
Monitoring Report for the month of December, 1980.

Effluent data for the month indicates violation of permit  
conditions for total iron and total chromium. Data for pH,  
copper, nickel, oil, and hexavalent chromium met permit  
conditions.

As you are aware, we are currently working under a  
compliance order to modify waste treatment practices at  
the plant and move to a "zero discharge" system.

If you have any questions, please call or write this  
office.

Yours very truly,

HOLZMACHER, McLENDON, & MURRELL, P.C.

Gary J. Miller

PAGE 1 of 1	SPDES NO. NY0076287	SCAVENGER PICKUP	Registration No.	ions	00	30-201	0	HORIZED AGENT	ager
-------------	------------------------	------------------	------------------	------	----	--------	---	---------------	------

**HOLZMACHER, McLENDON and MURRELL, P.C.**

**H2M Corp.**



CONSULTING ENGINEERS, ENVIRONMENTAL SCIENTISTS and PLANNERS

575 BROAD HOLLOW ROAD MELVILLE NY 11747 (516) 694-3040 ☒  
560 BROAD HOLLOW ROAD MELVILLE NY 11747 (516) 752-9060 ☐  
375 FULTON STREET FARMINGDALE NY 11735 (516) 694-3410 ☐  
209 WEST MAIN STREET RIVERHEAD NY 11901 (516) 727-3480 ☐  
40 PARK PLACE NEWTON NJ 07860 (201) 383-3544 ☐  
TELECOPIER ext 4100 (516) 752-9067

ROBERT G. HOLZMACHER, P.E., P.P.L.S.  
SAMUEL C. McLENDON, P.E.  
NORMAN E. MURRELL, P.E.  
HAROLD A. DOMBECK, P.E.  
HUGO D. FREUDENTHAL, Ph.D.  
CARL E. BECKER, P.E.  
JOHN J. MOLLOY, P.E.  
DONALD A. SIOSS, P.E.  
GARY E. LOESCH, P.E.  
BRIJ M. SHRIVASTAVA, P.E.  
CHARLES E. BANKS, P.E.

February 26, 1981

Nassau County Department  
of Health  
240 Old Country Road  
Mineola, NY 11501

Re: John Hassall, Inc.  
SPDES Permit No. NY0076287

Attention: Mr. Joseph Schecter

Gentlemen:

Enclosed please find the SPDES Industrial Discharge  
Monitoring Report for the month of January, 1981.

Effluent data for the month indicates violation of per-  
mit conditions for total chromium and total iron. Data for  
pH, copper, nickel, oil and hexavalent chromium met permit  
conditions.

As you are aware, we are currently working under a  
compliance order to modify waste treatment practices at the  
plant and move to a "zero discharge" system.

If you have any questions regarding this matter, please  
call or write this office.

Very truly yours,

HOLZMACHER, McLENDON & MURRELL, P.C.

*Brian A. Shields*

Brian A. Shields

BAS/lml  
Enc.

cc: Mr. R. Mt. Pleasant, P.E.  
Mr. Ted Snyder  
Mr. Karl Horlitz

**RECEIVED**

MAR 6 1981

NCDH  
BLRM

**HOLZMACHER, McLENDON and MURRELL, P.C.**

**H2M Corp.**



CONSULTING ENGINEERS, ENVIRONMENTAL SCIENTISTS and PLANNERS

575 BROAD HOLLOW ROAD MELVILLE NY 11747 (516) 694 3040 ☐

125 BAYLIS ROAD MELVILLE NY 11747 (516) 752 9060 ☐

375 FULTON STREET FARMINGDALE NY 11735 (516) 694 3410 ☐

209 WEST MAIN STREET RIVERHEAD NY 11901 (516) 727 3480 ☐

TELECOPIER ext 4100 (516) 752 9067

ROBERT G. HOLZMACHER P.E.  
SAMUEL C. McLENDON P.E.  
NORMAN E. MURRELL P.E.  
HAROLD A. DOMBECK P.E.  
HUGO D. FREUDENTHAL Ph.D.

CARL E. BECKER P.E.  
JOHN J. MOLLOY P.E.  
DONALD A. SIOSS P.E.  
GARY E. LOESCH P.E.  
BRIJ M. SHRIVASTAVA P.E.  
CHARLES E. BANKS P.E.

March 24, 1981

Nassau County Department of Health  
240 Old Country Road  
Mineola, NY 11501

Re: John Hassall, Inc.  
SPDES Permit No. NY0076287

Attention: Mr. Joseph Schechter

Gentlemen:

Enclosed please find the SPDES Industrial Discharge Monitoring Report for the month of February, 1981.

Effluent data for the month indicates violation of permit conditions for total chromium, total nickel and total iron. Data for pH, copper, oil and hexavalent chromium met permit conditions.

As you are aware, we are currently working under a compliance order to modify waste treatment practices at the plant and move to a "zero discharge" system.

If you have any questions regarding this matter, please call or write this office.

Very truly yours,

HOLZMACHER, McLENDON & MURRELL, P.C.

*Brian A. Shields*

Brian A. Shields

BAS/lml  
Enclosures

cc: Mr. R. Mt. Pleasant, P.E.  
Mr. Ted Snyder  
Mr. Karl Horlitz

**RECEIVED**

APR 2 1981

NCDH  
BLRM



HOLZMACHER, McLENDON and MURRELL, P.C. • CONSULTING ENGINEERS, ENVIRONMENTAL SCIENTISTS and PLANNERS  
125 BAYLIS ROAD, MELVILLE, N Y 11747 • 516-752-9060

April 28, 1981

Nassau County Department of Health  
240 Old Country Road  
Mineola, NY 11501

Re: John Hassall, Inc.  
SPDES No. NY0076237

Attention: Mr. Joseph Schechter

Gentlemen:

Enclosed please find the SPDES Industrial Discharge Monitoring Report for the month of March, 1981.

Effluent data for the month indicates violation of permit conditions for total chromium. Data for all other parameters met permit conditions.

As you are aware, we are currently working under a compliance order to modify waste treatment practices at the plant and move to a "zero discharge" system.

If you have any questions regarding this matter, please call or write this office.

Very truly yours,

HOLZMACHER, McLENDON & MURRELL, P.C.

*Brian A. Shields*

Brian A. Shields

BAS/lml  
Enclosures

cc: Mr. R. Mt. Pleasant, P.E.  
Mr. Ted Snyder  
Mr. Karl Horlitz, P.E.

RECEIVED

MAY 04 1981

BLRM



HOLZMACHER, McLENDON and MURRELL, P.C. • CONSULTING ENGINEERS, ENVIRONMENTAL SCIENTISTS and PLANNERS  
125 BAYLIS ROAD, MELVILLE, N Y 11747 • 516-752-9060

June 1, 1981

Nassau County Department of Health  
240 Old Country Road  
Mineola, NY 11501

Re: John Hassall, Inc.  
SPDES No. NY 0076287

Attention: Mr. Joseph Schechter

Gentlemen:

Enclosed please find the SPDES Industrial Discharge Monitoring Report for the month of April, 1981.

Effluent data for the month indicates violation of permit conditions for oil, total chromium, nickel and iron. Data for all other parameters met permit conditions.

As you are aware, we are currently working under a compliance order to modify waste treatment practices at the plant and move to a "zero discharge" system.

If you have any questions regarding this matter, please call or write this office.

Very truly yours,

HOLZMACHER, McLENDON & MURRELL, P.C.

*Brian A. Shields*

Brian A. Shields

BAS/lml  
Enclosures

cc: Mr. R. Mt. Pleasant, P.E.  
Mr. Ted Snyder  
Mr. Karl Horlitz, P.E.

RECEIVED

JUN 10 1981

NCDH  
BLRM



HOLZMACHER, McLENDON and MURRELL, P.C. • CONSULTING ENGINEERS, ENVIRONMENTAL SCIENTISTS and PLANNERS

125 BAYLIS ROAD, MELVILLE, N Y 11747 • 516-752-9060

June 25, 1981

Nassau County Department of Health  
240 Old Country Road  
Mineola, New York 11501

Re: John Hassall, Inc.  
SPDES Permit No. NY0076287

Attention: Mr. Joseph Schechter

Gentlemen:

Enclosed please find the SPDES Industrial Discharge Monitoring Report for the month of May, 1981.

Effluent data for the month indicates violation of permit conditions for total chromium, total nickel and total iron. Data for all other parameters met permit conditions.

As you are aware, we are currently working under a compliance order to modify waste treatment practices at the plant and move to a "zero discharge" system.

If you have any questions regarding this matter, please call or write this office.

Very truly yours,

HOLZMACHER, McLENDON & MURRELL, P.C.

*Brian A. Shields*

Brian A. Shields

BAS/lml  
Enclosures

cc: Mr. R. Mt. Pleasant, P.E.  
Mr. Ted Snyder  
Mr. Karl Horlitz, P.E.





HOLZMACHER, McLENDON and MURRELL, P.C. • CONSULTING ENGINEERS, ENVIRONMENTAL SCIENTISTS and PLANNERS  
125 BAYLIS ROAD, MELVILLE, N.Y. 11747 • 516-752-9060

September 1, 1981

Nassau County Dept. of Health  
240 Old Country Road  
Mineola, New York 11501

Re: John Hassall, Inc.  
SPDES Permit No. NY0076287

Attention: Mr. Joseph Schechter

Gentlemen:

Enclosed please find the SPDES Industrial Discharge Monitoring Report for the month of July, 1981.

Effluent data for the month indicates violation of permit conditions for copper and iron. Consequently, no batches were discharged during the month of July, 1981. Data for all other parameters met permit conditions.

As you are aware, since the County sewers are now available for hookup, we are proceeding with documenting waste characteristics with respect to the sewer use ordinance. Plans for the sewers have been prepared and submitted to the County. Bidding has commenced on the sewers with bids due by September 7, 1981. Please note that all parameters, therefore, met permit conditions for the month of June, 1981.

If you have any questions regarding this matter, please call or write this office.

Very truly yours,

HOLZMACHER, McLENDON & MURRELL, P.C.

*Brian A. Shields*

Brian A. Shields

BAS/jj

Enclosure

cc: Mr. Russell Mt. Pleasant, P.E.  
Mr. Ted Snyder  
Mr. Karl Horlitz, P.E.



HOLZMACHER, McLENDON and MURRELL, P.C. • CONSULTING ENGINEERS, ENVIRONMENTAL SCIENTISTS and PLANNERS  
125 BAYLIS ROAD, MELVILLE, N.Y. 11747 • 516-752-9060

October 6, 1981

Nassau County Department of Health  
240 Old Country Road  
Mineola, New York 11501

Re: John Hassall, Inc.  
SPDES Permit No. NY0076287

Attention: Mr. Joseph Schechter

Gentlemen:

Enclosed please find the SPDES Industrial Discharge Monitoring Report for the month of August, 1981.

Effluent data for the month indicates violation of permit conditions for pH and iron. Data for all other parameters met permit conditions.

As you are aware, all future batches not meeting permit conditions will be held for scavenger pickup.

If you have any questions regarding this matter, please call or write this office.

Very truly yours,

HOLZMACHER, McLENDON & MURRELL, P.C.

*Brian A. Shields*

Brian A. Shields

BAS/lml  
Enclosures

cc: Mr. R. Mt. Pleasant, P.E.  
Mr. Ted Snyder  
Mr. Karl Horlitz



HOLZMACHER, McLENDON and MURRELL, P.C. • CONSULTING ENGINEERS, ENVIRONMENTAL SCIENTISTS and PLANNERS

125 BAYLIS ROAD, MELVILLE, N.Y. 11747 • 516-752-9060

October 29, 1981

Nassau County Department of Health  
240 Old Country Road  
Mineola, New York 11501

Re: John Hassall, Inc.  
SPDES Permit No. NY0076287

Attention: Mr. Joseph Schechter

Gentlemen:

Enclosed please find the SPDES Industrial Discharge  
Monitoring Report for the month of September 1981.

Effluent data for the month indicates violation of  
permit conditions for pH, chromium and iron. Data for all  
other parameters met permit conditions.

As you are aware, all future batches not meeting  
permit conditions will be held for scavenger pickup.

If you have any questions regarding this matter,  
please call or write this office.

Very truly yours,

HOLZMACHER, McLENDON & MURRELL, P.C.

*Brian A. Shields*

Brian A. Shields

BAS/lml  
Enclosures

cc: Mr. R. Mt. Pleasant, P.E.  
Mr. Ted Snyder  
Mr. Karl Horlitz



HOLZMACHER, McLENDON and MURRELL, P.C. • CONSULTING ENGINEERS, ENVIRONMENTAL SCIENTISTS and PLANNERS

125 BAYLIS ROAD, MELVILLE N.Y. 11747 • 516-752-9060

December 2, 1981

Nassau County Department of Health  
240 Old Country Road  
Mineola, New York 11501

Re: John Hassall, Inc.  
SPDES Permit No. NY 0076287

Attention: Mr. Joseph Schechter

Gentlemen:

Enclosed please find the SPDES Industrial Discharge Monitoring Report for the month of October, 1981.

Effluent data for the month indicates violation of permit conditions for pH, chromium and iron. Data for all other parameters met permit conditions.

As you are aware, all batches not meeting permit conditions will be held for scavenger pickup.

If you have any questions regarding this matter, please call or write this office.

Very truly yours,

HOLZMACHER, McLENDON & MURRELL, P.C.

*Brian A. Shields*

Brian A. Shields

BAS/lml  
Enclosures

cc: Mr. R.C. Mt. Pleasant, P.E.  
Mr. Ted Snyder  
Mr. Karl Horlitz

**RECEIVED**

DEC 7 1981

NCDH  
BLRM



HOLZMACHER, McLENDON and MURRELL, P.C. • CONSULTING ENGINEERS, ENVIRONMENTAL SCIENTISTS and PLANNERS  
125 BAYLIS ROAD, SUITE 140, MELVILLE, N.Y. 11747 • 516-752-9060

October 25, 1982

Nassau County Department of Health  
240 Old Country Road  
Mineola, New York 11501

Re: John Hassal, Inc.

Attention: Mr. Joseph Schechter

Gentlemen:

Enclosed please find the SPDES Discharge Monitoring Report and the SPDES Industrial Discharge Monitoring Report from John Hassal, Inc. for the months of August and September, 1982.

In this regard, note that John Hassal Inc. (JHI) discharged their first batch of treated wastewater in the Nassau County Sewer System on August 25, 1982. Also, during September, 1982, all the treated wastewater batches from JHI was discharged in the sewers.

If you have any questions, please contact this office.

Very truly yours,

HOLZMACHER, McLENDON & MURRELL, P.C.

A handwritten signature in dark ink, appearing to read 'Raman S. Iyer', is written over the typed name.

Raman S. Iyer

RSI/mf

Enc.

cc: Mr. George Hansen  
Mr. Ted Snyder  
Mr. Karl Horlitz  
Mr. Mathew Foster

J. HASSALL, INC.  
INDUSTRIAL WASTE TREATMENT  
AND DISPOSAL FACILITIES

ANALYSIS OF UNTREATED WASTE WATERS

<u>Constituent</u>	<u>Average</u>	<u>Maximum</u>
Hexavalent Chromium (CR+6)	10. mg/l	20 mg/l
Chromium (Cr)	12. mg/l	30 mg/l
Copper (Cu)	25. mg/l	130 mg/l
Nickel (Ni)	9. mg/l	20 mg/l
Cyanide (Cn)	10. mg/l	30 mg/l
Iron (Fe)	10. mg/l	250 mg/l
Oil & Grease	approx. 3%	approx. 10%
pH	3 to 8	2 to 11

**REFERENCE NO. 12**

CONTROL NO:

DATE:

3/17/88

TIME:

1150

DISTRIBUTION:

JOHN HASSALL

02-8802-07

BETWEEN:

V. PALOSE

OF: JOHN

HASSALL

PHONE:

(516) 334-6200

AND:

E. LEONARD (NUS)

DISCUSSION:

RE: SPILL AT HASSALL

- VOLUME OF SPILL ~50-100 GALLONS
- OCCURRED IN DECEMBER 1987
- HOLDING TANK FOR TREATED WATER  
OVERFLOWED. OIL LAYER ON TOP  
WAS DISCHARGED ONTO GROUND
- DUE TO PUMP SWITCH MALFUNCTION
- NOT REPORT TO COUNTY OR STATE  
OTHER BACKGROUND
- NO ONSITE WELLS
- SITE ~ 15 ACRES 1/2 JOHN HASSALL  
OTHER HALF RENTED.

ACTION ITEMS:

E. Leonard 3/17/88



REFERENCE NO. 13

NUS CORPORATION AND SUBSIDIARIES

TELECON NOTE

CONTROL NO:

DATE:

3/17/88

TIME:

1132HRS

DISTRIBUTION:

JOHN HASSALL

02-8802-07

BETWEEN:

J. SCHULTER

OF: NASSAU CO.

HEALTH DEPT.

PHONE:

EXT 2256

(516) 535-3410

AND:

IZ. LEONARD (NUS)

DISCUSSION:

25: SPILL AT HASSALL

REQUESTED REPORT ON OIL/GREASE AT  
HASSALL 10 DEC 1987.

MR SCHULTER STATE THAT HE DID NOT  
KNOW ABOUT SPILL, AND THERE WERE  
NO KNOWN REPORTS, TO EITHER NCHD OR  
NYSDEC.

IZ Leonard 3/17/88

ACTION ITEMS:

**REFERENCE NO. 14**

**NUS CORPORATION AND SUBSIDIARIES**

**TELECON NOTE**

**CONTROL NO:**

02-8802-07

**DATE:**

2/18/88

**TIME:**

1105

**DISTRIBUTION:**

File

**BETWEEN:**

Jack McCrosson

**OF:**

Hicksville Water District

**PHONE:**

(516) 931-0184

**AND:**

Rich Feinberg (NUS)

**DISCUSSION:**

Mr. McCrosson gave me locations of many water supply wells in the Hicksville/Westbury area. He also said that there were ~ 50,000 people using the water from these wells.

**ACTION ITEMS:**

See Map in Note's file for well locations

**REFERENCE NO. 15**

[6560-01]

[FRL 910-3]

# AQUIFERS UNDERLYING NASSAU AND SUFFOLK COUNTIES, NEW YORK

## Determination

Notice is hereby given that pursuant to Section 1424(e) of the Safe Drinking Water Act (42 U.S.C. 300f, 300h-3(e); 88 Stat. 1660 et seq.; Pub. L. 93-523) the Administrator of the Environmental Protection Agency has determined that the aquifer system underlying Nassau and Suffolk Counties, Long Island, New York, is the principal source of drinking water for these counties and that, if the aquifer system were contaminated, it would create a significant hazard to public health.

## BACKGROUND

The Safe Drinking Water Act was enacted on December 16, 1974. Section 1424(e) of the Act states: "If the Administrator determines, on his own initiative or upon petition, that an area has an aquifer which is the sole or principal drinking water source for the area and which, if contaminated, would create a significant hazard to public health, he shall publish notice of that determination in the *FEDERAL REGISTER*. After the publication of any such notice, no commitment for Federal financial assistance (through a grant, contract, loan guarantee, or otherwise) may be entered into for any project which the Administrator determines may contaminate such

aquifer through a recharge zone so as to create a significant hazard to public health but a commitment for Federal financial assistance may, if authorized under another provision of law, be entered into to plan or design the project to assure that it will not so contaminate the aquifer."

On January 21, 1975, the Environmental Defense Fund petitioned the Administrator to designate the aquifers underlying Nassau and Suffolk Counties, Long Island, New York, as a sole source aquifer under the provisions of the Act. A notice of receipt of this petition, together with a request for comments, was published in the *FEDERAL REGISTER*, Thursday, June 12, 1975. Written comments were submitted by the Environmental Defense Fund (EDF) on August 7, 1975, supporting their petition. A letter from the Director of the Nassau-Suffolk Regional Planning Board, dated October 1, 1976, requested that designation be delayed until after the completion of the areawide waste management (208) planning process for Long Island.

Because of the limited response to the *FEDERAL REGISTER* notice, EPA issued a press release and mailed an information sheet to elected officials and environmental groups on Long Island in March 1977. In addition, a presentation was made to the Citizens Advisory Committee (CAC) of the 208 planning agency and to the executive committee of the Long Island Water Conference. In response to these activities EPA received three comments: a letter from EDF questioning why project review would exclude direct Federal projects, a letter from a member of the East Hampton Planning Board expressing support for the designation, and a letter from the CAC requesting that designation be delayed until after the completion and approval of the Long Island 208 plan.

In considering the comments received, we could not agree with the letters requesting further delay since we do not believe that the review process under Section 1424(e) will constrain the options of 208 planning.

On the basis of the information which is available to this Agency, the Administrator has made the following findings, which are the basis for the determination noted above:

(1) The aquifers underlying Nassau and Suffolk Counties are the sole or principal drinking water source for the area. They supply good quality water for about 2.5 million people. Current water supply treatment practice for public supplies is generally limited to disinfection for drinking purposes, with some plants capable of nitrate removal. There are also numerous private sources. There is no alternative source of drinking water supply which could economically replace this aquifer system.

(2) The aquifer system is vulnerable to contamination through its recharge zone. Since contamination of a ground-water aquifer can be difficult or impossible to reverse, contamination of the the aquifer system underlying Nassau and Suffolk Counties, New York, would pose a significant hazard to those people dependent on the aquifer system for drinking purposes.

Among the determinations which the Administrator must make in connection with the designation of an area under Section 1424(e) is that the area's sole or principal source aquifer or aquifers, "if contaminated, would create a significant hazard to public health . . . ." Obviously, threats to the quality of the drinking water supply for such a large population could create a significant hazard to public health. The EPA does not construe this provision to require a determination that projects planned or likely to be constructed will in fact create such a hazard; it is sufficient to demonstrate that approximately 2.5 million people depend on the aquifer system underlying Nassau and Suffolk Counties as their principal source of drinking water, and that the aquifer system is vulnerable to contamination through its recharge zone.

Section 1424(e) of the Act requires that a Federal agency may not commit funds to a project which may contaminate the aquifer system through a recharge zone so as to create a significant hazard to public health. The recharge zone is that area through which water enters into the aquifer system. Because of groundwater movement within these aquifers, the recharge zone is considered to be the entire area of Nassau and Suffolk Counties. However, both horizontal and vertical boundaries of the recharge zone are discussed in the background document under the section entitled "Area of Consideration."

The data upon which these findings are based are available to the public and may be inspected during normal business hours at the office of the Environmental Protection Agency, Region II, 26 Federal Plaza, New York, New York 10007. It includes a support document for designation of the aquifers underlying Nassau and Suffolk Counties, New York, and maps of the area within which projects will be subject to review.

A copy of the above documentation is also available at the U.S. Waterside Mail, Environmental Protection Agency, Public Information and Reference Unit, Room 2922, 401 M Street S.W., Washington, D.C. 20460.

The EPA has issued proposed regulations for the selective review of Federal financially assisted projects which may contaminate the aquifer system underlying Nassau and Suffolk Counties, New York, through the recharge

zone so as to create a significant hazard to public health. These proposed regulations were published in the *FEDERAL REGISTER* issue of September 29, 1977, and public comments were requested. They will be used as interim guidance for project review until their promulgation during 1978.

EPA, Region II, is working with the Federal agencies which may in the near future fund projects in the area of concern to EPA to develop inter-agency procedures whereby EPA will be notified of proposed commitments for projects which could contaminate the bicounty area's sole source aquifer system. Although the project review process cannot be delegated, the Regional Administrator in Region II will rely to the maximum extent possible upon any existing or future State and local control mechanisms in protecting the ground-water quality of the aquifer system underlying Nassau and Suffolk Counties, New York. Included in the review of any Federal financially assisted project will be coordination with the State and local agencies. Their determinations will be given full consideration and the Federal review process will function so as to complement and support State and local mechanisms.

Dated: June 12, 1978.

DOUGLAS M. COSTLE,  
Administrator.

(FR Doc. 78-17067 Filed 6-20-78; 8:45 am)

**REFERENCE NO. 16**



HYDROGEOLOGY AND GROUND-WATER QUALITY OF THE  
NORTHERN PART OF THE TOWN OF OYSTER BAY,  
NASSAU COUNTY, NEW YORK, IN 1980

By Chabot Kilburn and Richard K. Krulikas

---

U.S. GEOLOGICAL SURVEY

Water-Resources Investigations  
Report 85-4051

Prepared in cooperation with the  
NASSAU COUNTY DEPARTMENT OF PUBLIC WORKS



Syosset, New York

1987

## HYDROGEOLOGY

The ground-water reservoir underlying the northern part of the Town of Oyster Bay consists of unconsolidated glacial deposits of Pleistocene age and coastal-plain deposits of continental and marine origin of Late Cretaceous age. These unconsolidated deposits consist of gravel, sand, silt, and clay and are underlain by bedrock of early Paleozoic and (or) Precambrian age. The bedrock, which is relatively impermeable, forms the base of the ground-water reservoir.

The thickness, character, and water-bearing properties of the aquifer and the relationships between hydrogeologic and geologic units underlying the study area are depicted in table 1. The correlations should be considered direct relationships as implied in the tables. The upper and lower boundaries of the hydrogeologic units are determined mainly from gross lithologic differences between units rather than the age of the deposits, which forms the basis for geologic correlations. For example, the upper and lower limits of the confining units (Port Washington confining unit and Raritan clay) are placed at intervals where the lithologic sequence changes from predominantly clay to sand or sand and gravel, and these positions may have no time-stratigraphic significance. For this reason, and because differentiation between sediments of Pleistocene and Cretaceous age is difficult and uncertain, it is possible that some deposits of Pleistocene age have been included in the upper part of the Magothy aquifer, which, by present definition, is approximately equivalent to the Magothy Formation-Matawan Group, undifferentiated, of Late Cretaceous age. The three hydrogeologic sections (pl. 1B) show the inferred extent, lateral and vertical relationships, and the variations in depth, thickness, lithology, and structure of these units.

### Description of Hydrogeologic Units

#### *Bedrock*

Bedrock of early Paleozoic and (or) Precambrian age underlies all of western Long Island (Fisher and others, 1962). The bedrock generally consists of metamorphic and igneous crystalline rocks--schist, gneiss, and granite--and lies at depths ranging from about 350 ft below sea level along the north shore to about 950 ft below sea level in the southeast part of the study area (pl. 2A, and hydrogeologic sections, pl. 1B).

Bedrock is generally regarded as the base of the ground-water reservoir on Long Island because of its density and low permeability. No wells in the Town of Oyster Bay are known to obtain water from bedrock.

#### *Lloyd Aquifer*

The Lloyd aquifer is the equivalent of the Lloyd Sand Member of the Raritan Formation of Late Cretaceous age (Cohen and others, 1968, p. 18). It consists of discontinuous layers of gravel, sand, sandy clay, silt, and clay, and lies roughly parallel to the bedrock surface at depths ranging from about

200 ft below sea level along the north shore to about 700 ft below sea level in the southeast part of the study area (pl. 2B). Its thickness ranges from 0 to 250 ft from northwest to southeast, respectively.

The Lloyd aquifer is a major aquifer in the Town of Oyster Bay. It is probably hydraulically continuous with the adjacent Port Washington aquifer and upper glacial aquifer in the northern part of the study area. Water in the Lloyd aquifer is confined under artesian pressure beneath the Raritan clay.

Well yields during test pumping of large-capacity public-supply wells screened in the Lloyd aquifer have ranged from 500 gal/min to as much as 1600 gal/min.

#### *Raritan Clay*

The Raritan clay is a distinct hydrogeologic unit that extends throughout much of the Town of Oyster Bay (pl. 3A). In this area, the Raritan clay may be equivalent to the unnamed clay member of the Raritan Formation of Late Cretaceous age. The Raritan clay consists mainly of light to dark gray, red, white, or yellow clay and variable amounts of silt, and clayey silty fine sand. Sandy beds of varying thickness are common. The top of the Raritan clay is roughly parallel to that of the underlying Lloyd sand member. The upper-surface altitude of the Raritan clay ranges from 150 ft below sea level along the north shore to about 550 ft below sea level in the southeastern part of the study area. Its thickness ranges from 0 to 200 ft from northwest to southeast, respectively.

The Raritan clay is a significant hydrogeologic unit because it confines water in the underlying Lloyd aquifer. Although its hydraulic conductivity is very low, it does not entirely prevent movement of water between the Magothy and Lloyd aquifers. Some public-supply and other wells obtain part of their water supply from the sandy zones in the upper part of the Raritan clay.

#### *Magothy Aquifer*

The Magothy aquifer is the equivalent of the Matawan Group-Magothy Formation undifferentiated of upper Cretaceous age. Deposits in this unit consist of beds and lenses of light-gray, fine to coarse sand with some interstitial clay. Detailed lithologic descriptions are given in Soren (1978); Ku and others (1975); and Jensen and Soren (1974).

The top of the Magothy aquifer is not planar, unlike the surfaces of the underlying units. The Magothy surface was deeply eroded during Tertiary time and probably was considerably eroded in Pleistocene time. The upper surface altitude of the Magothy ranges from as high as 200 ft above sea level in the center of the study area to 200 ft below sea level along the northeast edge of the study area (pl. 3B). Its thickness ranges from 0 to 650 ft from northwest to southeast, respectively.

The Magothy aquifer is the principal aquifer underlying Long Island and is the island's main source of water for public supply. The sand beds within the aquifer are moderately to highly permeable. The reported yields during

pumping tests of several public-supply wells screened in the Magothy aquifer in the Town of Oyster Bay ranged from 300 gal/min to as much as 1,500 gal/min. The average yield was about 1,000 gal/min.

The large amount of clay in the upper half of the aquifer causes the water to become increasingly confined with depth. Along the north shore, the Magothy aquifer is probably in hydraulic continuity with the adjacent Port Washington aquifer. The Magothy also has a generally high degree of hydraulic continuity with the overlying upper glacial aquifer, but the degree of continuity may vary considerably from place to place.

#### *Port Washington Aquifer*

Two previously unrecognized hydrogeologic units in the northern part of the Town of Oyster Bay are defined as the Port Washington aquifer and Port Washington confining unit. The units were first recognized in the northern part of the Town of North Hempstead (Kilburn, 1979). The inferred limits of the units are shown in plates 4A and 4B, and their relationships to the other hydrologic units are shown on the hydrogeologic sections on plate 1B.

The Port Washington aquifer is a sequence of deposits of Pleistocene and (or) Late Cretaceous age that underlie the north-shore area of the Town of Oyster Bay. The deposits form a distinct hydrogeologic unit that rests upon bedrock and is overlain by a thick sequence of confining clay. The south edge of the deposits overlap and abut the adjacent Cretaceous units. The sediments of the Port Washington aquifer form part of the valley fill in the channels cut into the Cretaceous deposits. These deposits consist largely of sand or sand and gravel and varying amounts of interbedded clay, silt, and sandy clay.

The altitude of the top of the Port Washington aquifer ranges from 150 ft below sea level along the north shore to 450 ft below sea level along the south shore (pl. 4A). Its thickness ranges from 0 to more than 150 ft in the central parts of the study area.

The Port Washington aquifer is moderately to highly permeable and is a major aquifer in the northern parts of the Town of Oyster Bay. The reported yields during pumping tests of public-supply wells screened in the aquifer range from 300 gal/min to 1,200 gal/min. Water in the aquifer is confined beneath the Port Washington confining unit. The hydrogeologic relationships between the Port Washington aquifer and the abutting Lloyd, Magothy, and upper glacial aquifers, as shown in the hydrogeologic sections on plate 1B, suggest that these deposits could be in lateral hydraulic continuity. Potentiometric studies of the head in the Lloyd aquifer made by Swarzenski (1963), Kimmel (1973), and Kilburn (1979) tend to verify a lateral hydraulic continuity between the Port Washington and Lloyd aquifers.

#### *Port Washington Confining Unit*

The Port Washington confining unit is a sequence of deposits of Pleistocene or Late Cretaceous to Holocene(?) age that locally underlies the north shore. The unit consists mainly of clay and silt, with scattered lenses

of sand or sand and gravel. (See Kilburn, 1979, for a more detailed description.) The deposits that form the Port Washington confining unit overlie the Port Washington aquifer or overlap the adjacent Cretaceous units and may form part of the valley fill that occupies channels cut into the other Cretaceous deposits. The unit may locally include or consist of erosional remnants of the clay member of the Raritan Formation.

The altitude of the top of the Port Washington confining unit ranges from 100 ft above sea level in the central part of the study area to 300 ft below sea level along the northeastern part (pl. 4B). Its thickness ranges from 0 to more than 150 ft in the central part of the study area.

### *Upper Glacial Aquifer*

The upper glacial aquifer consists of deposits of late Pleistocene and Holocene age that overlie the Magothy aquifer and the Port Washington confining unit and locally abut against or overlie the Port Washington aquifer. The extent and relationships of these deposits to the adjacent hydrogeologic units are shown on plate 1B.

The upper deposits consist mainly of stratified beds of fine to coarse sand and of sand and gravel but also contain thin beds of silt and clay interbedded with coarse-grained material. The outwash that constitutes the bulk of the upper Pleistocene deposits is yellow and brown or, in some places, gray. (See Perlmutter, 1949, and Kilburn, 1979, for further descriptions.)

The upper glacial aquifer, which contains the water table in most of the area, transmits all recharge to the underlying aquifers. Precipitation filtering downward to the water table is the principal source of ground-water recharge. In the past, the upper glacial aquifer was tapped as a water supply by many public-supply wells. Because it has become contaminated by cesspool effluents, fertilizers, and other substances, however, its use for public supply has decreased. Wells tapping the aquifer are now used mainly to supply water for domestic use, irrigation, and commercial and industrial purposes.

The sand and gravel deposits in the upper glacial aquifer are highly permeable and yield large amounts of water to properly constructed wells. The yields of large-capacity public-supply wells screened in the aquifer have been reported to range from 400 gal/min to 1,400 gal/min.

The recent deposits of Holocene age along beaches, streams, swamps, and the bottoms of bays and lakes have not been differentiated from the upper glacial aquifer because they are too thin.

### **Correlation of Units**

The differentiation between deposits of Pleistocene and Cretaceous age throughout most of the northern part of the Town of Oyster Bay is uncertain. On Long Island, the contact between Pleistocene and Cretaceous deposits is an erosional unconformity that is commonly marked by an abrupt lithologic and




PLATE 6A. WATER-TABLE CONFIGURATION IN 1980

0 1/2 1 2 MILES  
0 1/2 1 2 KILOMETERS

**REFERENCE NO. 17**

Town of Hempstead

0035-C  
02-8802-07

JOSEPH N. MONDELLO  
Presiding Supervisor

GREGORY P. PETERSON  
Supervisor

Council Members  
EUGENE L. WEISBEIN  
JOSEPH G. CAIRO, JR.  
MARTIN B. BERNSTEIN  
RICHARD V. GUARDINO, JR.  
ANGIE M. CULLIN  
PATRICK A. ZAGARINO

DANIEL M. FISHER, JR.  
Town Clerk

ROBERT D. LIVINGSTON, JR.  
Receiver of Taxes

Department  
of  
Water

1995 PROSPECT AVENUE, EAST MEADOW, N.Y. 11554  
(516) 794-8300



DANIEL DAVIS, P.E.  
Commissioner

April 6, 1988

Mr. Edward L. Leonard  
NUS Corporation  
1090 King Georges Post Road  
Suite 1103  
Edison, NJ 08837

Dear Mr. Leonard:

Below is the information requested in your letter of March 30, 1988. There are two wells located on Iris Place in the Bowling Green Estates Water District. Both wells are located in the magothy range and serves a population of approximately 12,000. Well #1, N-8956 is 535 feet deep; Well #2, N-8957 is 598 feet deep.

I am returning your map with the locations of the above wells marked in red.

If you should require any further assistance, please do not hesitate to contact me at (516) 794-8300, Ext. 204.

Very truly yours,


  
Harold V. Morgan  
Administrative Assistant

HVM:th

enc. (2)

RECEIVED  
APR 07 1988  
NUS CORPORATION  
REGION 1C  
SENT TO \_\_\_\_\_





Old Westbury

STATE UNIVERSITY COLLEGE  
AT OLD WESTBURY

Jaricho

Hicksville  
(NY 145)

New Cassel

HEMPSTEAD  
Westbury South

Hicksville

EISENHOWER

AREA OF INTEREST

**REFERENCE NO. 18**

# HICKSVILLE WATER DISTRICT

4 DEAN STREET  
HICKSVILLE, N. Y. 11802

PHONE  
(516) 931-0184

RECEIVED

March 22, 1988

1988 MAR 22

ALL INFORMATION  
IS CONFIDENTIAL

NUS Corporation  
1090 King Georges Post Road  
Suite 1103  
Edison, New Jersey

Att: Mr. E.L. Leonard

Dear Mr. Leonard:

Enclosing please find the list you requested containing well numbers, depth and aquifers used by the nineteen (19) wells operated by the Hicksville Water District.

If I may be of any further assistance please feel free to contact me at the above number.

Very truly yours,

HICKSVILLE WATER DISTRICT

  
John J. McCrosson  
Assistant Superintendent

Enc

JJM/jps

# HICKSVILLE WATER DISTRICT

4 DEAN STREET  
HICKSVILLE, N. Y. 11802


PHONE  
(516) 931-0184

March 22, 1988

<u>H.W.D. WELL #</u>	<u>COUNTY WELL #</u>	<u>DEPTH</u>	<u>AQUIFER</u>
1-4	N-7562	545 feet	Magthoy
1-5	N-8249	495 feet	Magthoy
1-6	N-9488	583 feet	Magthoy
2-2	N-5336	545 feet	Magthoy
3-2	N-8525	505 feet	Magthoy
4-2	N-8526	601 feet	Magthoy
5-2	N-7561	551 feet	Magthoy
5-3	N-9212	610 feet	Magthoy
6-1	N-3953	419 feet	Magthoy
6-2	N-3878	428 feet	Magthoy
7-1	N-6190	605 feet	Magthoy
7-2	N-6191	555 feet	Magthoy
8-1	N-6192	632 feet	Magthoy
8-2	N-6193	472 feet	Magthoy
8-3	N-9180	637 feet	Magthoy
9-1	N-8778	590 feet	Magthoy
9-2	N-8779	585 feet	Magthoy
9-3	N-10208	600 feet	Magthoy
10-1	N-9463	625 feet	Magthoy

\*\*11-1

Under construction will not be in operation  
until early 1989.



**REFERENCE NO. 19**

# Village of Old Westbury

0031-C  
02-8fc2-07

MAYOR

INCORPORATED MAY 10, 1924

GILBERT M. COLOMBO, JR.

1 STORE HILL ROAD

VILLAGE CLERK - TREASURER

TRUSTEES

P.O. BOX 290

R. BUSCARELLO

E. A. SIMPSON

OLD WESTBURY, N.Y. 11568

SUPT. PUBLIC WORKS

R. GACHOT

**RECEIVED** (516) 626-0800

A. J. LINDON

S. WEINSTEIN

VILLAGE JUSTICE

H. BLAU

W. F. RUEGER

APR 05 REC'D

NUS CORPORATION  
REGION II

SENT TO \_\_\_\_\_

April 4, 1988

Edward L. Leonard  
Nus Corporation  
1090 King Georges Post Road  
Suite 1103  
Edison, New Jersey 08837

Dear Mr. Leonard:

As requested, enclosed please find your area of interest map showing location and number of our wells and the outline of our water district within the area.

The following is the additional information on well depth and formation.

Well #1 N152  
Depth of screen 478'  
Formation magothy


Well #4 N7549  
Depth of screen 499'  
Formation magothy

Well #5 N8658  
Depth of screen 610'  
Formation magothy

Village population served by these three wells is approximately 3200.


Blue lines on attached map indicates the boundary line of our water district within your area of interest.

Very truly yours,



Arthur J. Lindon  
Supt. Public Works

AJL:hs  
Att.





REFERENCE NO. 20



## Westbury Water District

160 Drexel Avenue Westbury, L.I., N.Y. 11590  
516-333-0427

DONALD A. CROUCHLEY, Chairman  
FRANK J. IADEVIA, Secretary  
ALFRED ARDIS, Treasurer  
ITALO J. VACCHIO, Superintendent

RECEIVED

March 21, 1988

NUS Corporation  
1090 King Georges Post Road  
Suite 1103  
Edison, New Jersey 08837

Attention: E. L. Leonard

Dear Mr. Leonard:

In response to your letter of March 17, 1988, (copy attached), please find below the requested information:

1. See attached map.

2. STATE WELL NO.	W.W.D. WELL NO.	DEPTH	AQUIFERS
N-101	6	341'	Magothy
N-7785	7	400'	Magothy
N-2602	9	805'	Lloyd
N-5007	10	560'	Magothy
N-5654	11	561'	Magothy
N-5655	12	260'	Magothy
N-6819	12A	270'	Magothy
N-7353	14	390'	Magothy
N-8007	15	564'	Magothy
N-8497	16	544'	Magothy
N-104510	17	600'	Magothy

4. Population estimated to be 24,000. All wells are interconnected.

5. None known.

6. 1. Carle Place Water District  
2. Town of Hempstead Water District  
3. Inc. Village of Old Westbury  
4. Hicksville Water District  
5. Jericho Water District

March 21, 1988


Westbury Water District

Page #2.

Should you require any other information, please contact me at the above address.


Very truly yours,

WESTBURY WATER DISTRICT

A handwritten signature in dark ink, appearing to read "Italo J. Vacchio". The signature is written in a cursive style with a large, looped "V" and "C".

Italo J. Vacchio  
Superintendent

IJV/mh  
Enc.



WVD  
WELL NO. 11

DISTRIBUTION SYSTEM  
of the

WESTBURY WATER DISTRICT

TOWN of NORTH HEMPSTEAD

NASSAU COUNTY, NEW YORK

MAR 6 1968

REFERENCE NO. 21

## NUS CORPORATION AND SUBSIDIARIES

TELECON NOTE

CONTROL NO:

DATE:

4/22/88

TIME:

1400 HRS

DISTRIBUTION:

JOHN HASSALL

02-8802-07

BETWEEN:

STAFF ENGINEER

OF: NASSAU CO. PUBLIC  
WORKS (BUILDING/DRAINAGE)

PHONE:

(516) 535-4322

AND:

E. LEONARD (NUS)

DISCUSSION:

RE: STORM WATER RUNOFF

STORM WATER RUNOFF IN NASSAU CO.  
DOES NOT ENTER A POTW. IT ENTERS  
EITHER A RECHARGE BASIN OR A SMALL  
BROOK/STREAM (RARE). IF A BASIN IS  
ON SITE, MOST LIKELY RUNOFF WILL  
ENTER IT.

E. Leonard 4/22/88

ACTION ITEMS:

**REFERENCE NO. 22**

0052-C  
22-5802-07



EDWARD P. BRACKEN, JR., CHAIRMAN  
NICHOLAS J. BARTILUCCI, TREASURER  
KENNETH J. DUNNE, SECRETARY  
WILLIAM EVERS, SUPERINTENDENT  
GREG G. HENDRICKSON, OFFICE MANAGER

125 CONVENT ROAD  
SYOSSET, NEW YORK 11791  
TEL. 921-8280

May 9, 1988

Mr. Edward Leonard  
NUS Corporation  
1090 King Georges Post Road  
Suite 1103  
Edison, New Jersey 08837

Dear Mr. Leonard:

Please find enclosed your "Marked-up" map which shows Jericho Water District boundaries in yellow. I have listed J.W.D. wells in red, with the number at each location. The wells are all interconnected with the rest of our wells, which total 20. We serve approximately 63,000 people.


The eight wells in this area are all in the magothy aquifer and their depths are as follows:

# 6	514'
# 7	484'
# 9	565'
#10	453'
#14	615'
#15	535'
#16	490'
#22	459'

Other water utilities have been marked on map with notation. If you have any further questions, please do not hesitate to call me.


Very truly yours,

Board of Commissioners  
Jericho Water District

  
William Evers  
District Superintendent

WE/ar





**REFERENCE NO. 23**

# **Uncontrolled Hazardous Waste Site Ranking System**

---

## **A Users Manual (HW-10)**

Originally Published in  
the July 16, 1982, *Federal Register*

United States  
Environmental Protection  
Agency

1984

**MEAN ANNUAL LAKE EVAPORATION**  
(In Inches)

Based on period 1946-55

The map displays contour lines for mean annual lake evaporation across the United States. The values range from 20 inches in the northeast to 80 inches in the southwest. Major cities labeled include: Havre, Great Falls, Billings, Rapid City, North Platte, Lincoln, Omaha, Dodge City, Amarillo, Oklahoma City, Tulsa, Fort Worth, Dallas, Houston, San Antonio, Austin, Little Rock, Memphis, Nashville, Knoxville, Atlanta, Birmingham, Jacksonville, Tallahassee, Miami, Tampa, Orlando, St. Petersburg, Pensacola, New Orleans, Mobile, Biloxi, Savannah, Charleston, Columbia, Raleigh, Norfolk, Richmond, Washington, D.C., Philadelphia, New York, Albany, Hartford, New Haven, Boston, Concord, Portland, Burlington, and Caribou. The Gulf of Mexico is labeled at the bottom. An inset map shows the Hawaiian Islands.

**MEAN ANNUAL LAKE EVAPORATION**  
(In Inches)

Based on period 1946-55

The map displays contour lines for mean annual lake evaporation across the United States. The values generally increase from the northwest (around 20-30 inches) towards the southeast (reaching 80 inches or more). Key cities labeled include: Havre, Great Falls, Billings, Rapid City, North Platte, Lincoln, Dodge City, Amarillo, Oklahoma City, Little Rock, Memphis, Nashville, Knoxville, Atlanta, Birmingham, Little Rock, St. Louis, Kansas City, Des Moines, Dubuque, Chicago, Green Bay, Milwaukee, Minneapolis, St. Paul, Duluth, International Falls, S. Ste. Marie, Lansing, Detroit, Buffalo, Pittsburgh, Harrisburg, Philadelphia, New York, New Haven, Hartford, Albany, Burlington, Portland, Bangor, Concord, Boston, Washington, D.C., Richmond, Norfolk, Raleigh, Wilmington, Columbia, Charleston, Jacksonville, Miami, Tampa, New Orleans, Houston, San Antonio, Austin, Dallas, Fort Worth, and Albuquerque. The Gulf of Mexico is labeled at the bottom. An inset map in the bottom left corner shows the Hawaiian Islands.



TABLE 2  
PERMEABILITY OF GEOLOGIC MATERIALS\*

Type of Material	Approximate Range of Hydraulic Conductivity	Assigned Value
Clay, compact till, shale; unfractured metamorphic and igneous rocks	$<10^{-7}$ cm/sec	0
Silt, loess, silty clays, silty loams, clay loams; less permeable limestones, dolomites, and sandstone; moderately permeable till	$10^{-5} - 10^{-7}$ cm/sec	1
Fine sand and silty sand; sandy loams; loamy sands; moderately permeable limestones, dolomites, and sandstone (no karst); moderately fractured igneous and metamorphic rocks, some coarse till	$10^{-3} - 10^{-5}$ cm/sec	2
Gravel, sand; highly fractured igneous and metamorphic rocks; permeable basalt and lavas; karst limestone and dolomite	$>10^{-3}$ cm/sec	3

\*Derived from:

Davis, S. N., Porosity and Permeability of Natural Materials in Flow-Through Porous Media, R.J.M. DeWiest ed., Academic Press, New York, 1969

Freeze, R.A. and J.A. Cherry, Groundwater, Prentice-Hall, Inc., New York, 1979

REFERENCE NO. 24



JOHN HASSALL, INC. WESTBURY · LONG ISLAND · N.Y. · 1159

Tel. 516 · 334-6200 • Telex No. 144585

February 10, 1984

Mr. Ernest A. Regna  
E.P.A. - Solid Waste Branch  
E.P.A. - Region II  
26 Federal Plaza  
New York, N.Y. 10278

Re: E.P.A. Identification Number NYD002045417  
(Withdrawal of Part A Interim Status 40CFR265)

Dear Mr. Regna:

John Hassall, Inc. in accordance with 40CFR Section 270.11 is hereby submitting a formal request for the withdrawal of its Part A RCRA permit application. The original application dated August 12, 1980 listed the descriptions of hazardous waste under the following categories:

(A) Non-Specific Sources

F 001  
F 007  
F 008  
F 009  
F 010  
F 012

(C) Commercial Chemical Product Hazardous Waste K 029

The original application should not have included F 007, F 008, F 009, F 010, F 012 and K 029. It should have only contained F 001 listed under category C.

History of Cyanide Usage at John Hassall, Inc.

Cyanide usage was limited to the following two specific operations.



February 10, 1984

(#1) Case Hardening of Steel:

The process involved a heat treat operation which forged steel in a furnace and inserted it into Na Cn powder. The steel was once again forged and quenched in a water bath releasing small amounts of Na Cn into the water (most of the Cn was absorbed into the metal). The water was directed into our Waste Water Treatment Facility for proper disposal. When this system was employed it was rarely in use.

In 1972 it was discontinued for case hardening applications and replaced by "Hard-N-Tuff", which is a safe non-toxic compound produced by American Chemical and Flux Products. The extent of our case hardening past and present is reflected by our purchases of the Cyanide replacement "Hard-N-Tuff" since 1972 (Purchase Orders enclosed).

Purchases:

November 17, 1972	1	3 lb. can
November 30, 1976	1	3 lb. can
April 30, 1981	1	3 lb. can

(#2) Stripping of Zinc Plated Parts:

Prior to 1974 Sodium Cyanide (Na Cn) was only used to remove Zinc Plate from small quantities of stocked parts to facilitate immediate shipment to customers requiring a non-zinc finish (this was the exception, not the rule). Any stripping solution was directed to our Waste Water Treatment Facility for proper disposal.

Since 1974 John Hassall, Inc. has discontinued this practice of in-house stripping, subsequently Cyanide is no longer used anywhere in any operation at our facility.

F 001

In the form of III Trichlorethane is presently in use, however, it is used in degreasing operations and collected in 55 gallon drums for off site manifested disposal. It is stored no longer than ninety days in compliance with all regulations.

K 029

Is not applicable to our operation in any manner. John Hassall, Inc. does not now and never has produced any solvent of any type.

Mr. Ernest A. Regna

- 3 -

February 10, 1984

Based upon the preceding information and bringing to your attention CFR 264.1,G,5 wherein our Waste Water Treatment Plant is exempt due to its totally enclosed status, we request formal withdrawal of our Part A RCRA application.

Very truly yours,

**REFERENCE NO. 25**

SITE NAME: JOHN HASSALL  
 TDM: 02-0002-07  
 SAMPLING DATE: 3/9/88  
 EPA CASE NO.: 9116 LAB: HITTMAN-EMASCO ASSOC., INC.

VOLATILES	NYEF-81 (NS/MSD)	NYEF-82	NYEF-83 (DUP)	NYEF-84	NYEF-85	NYEF-86	NYEF-87	NYEF-88	NYEF-R1M1 (NS/MSD)	NYEF-TBLK1
Sample ID No.	DR268	DR269	DR270	DR271	DR272	DR273	DR274	DR277	DR266	DR275
Traffic Report No.	SEDIMENT	SEDIMENT	SEDIMENT	SEDIMENT	SEDIMENT	SEDIMENT	SEDIMENT	SOIL	WATER	WATER
Matrix	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/L	ug/L
Units	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Dilution Factor	11	15	22	31	9	10	13	15	—	—
Percent Moisture										

Chloromethane										
Bromomethane										
Vinyl Chloride										
Chloroethane										
Methylene Chloride									B	B
Acetone									B	B
Carbon Disulfide										
1,1-Dichloroethane										
1,1-Dichloroethane										
Trans-1,2-Dichloroethane (total)										
Chloroform										
1,2-Dichloroethane										
2-Butanone		R	R	J		R	R	R	R	R
1,1,1-Trichloroethane										
Carbon Tetrachloride										
Vinyl Acetate										
Bromodichloromethane										
1,2-Dichloropropane										
cis-1,3-Dichloropropene										
Trichloroethene		J	J	11	J	8	15			
Dibromochloromethane										
1,1,2-Trichloroethane										
Benzene										
cis-1,3-Dichloropropene										
Bromoform										
4-Methyl-2-Pentanone										
2-Hexanone										
Tetrachloroethene										
1,1,2,2-Tetrachloroethane										
Toluene		J		10		8	21			
Chlorobenzene										
Ethylbenzene										
Styrene										
Xylenes (Total)										

# NOTES:

Blank space - compound analyzed for but not detected  
 B - compound found in lab blank as well as sample, indicates possible/probable blank contamination  
 E - estimated value  
 J - estimated value, compound present below CREL but above TDL  
 R - analysis did not pass EPA QA/QC  
 N - Presumptive evidence of the presence of a compound, but can't be identified  
 NR - analysis not required  
 Detection limits elevated if Dilution Factor >1 and/or percent moisture >0%

**SITE NAME: JOHN HASSALL**

**TDD#: 02-8402-07**

SAMPLING DATE: 3/9/88

EPA CASE NO.: 9116 LAB: HITTMON-ERASCO ASSOC., INC.

[illegible]

SITE NAME: JOHN HASSALL  
 TDD#: 02-0002-07  
 SAMPLING DATE: 3/9/88  
 EPA CASE NO.: 9116 LAB: HITTMAN-EDASCO ASSOC., INC.

SEMI-VOLATILES

Sample ID No.	NYEF-81 (HS/MSD)	NYEF-82	NYEF-83 (DUP)	NYEF-84	NYEF-85	NYEF-86	NYEF-87	NYEF-88	NYEF-RIN1 (HS/MSD)	NYEF-TBLK1
Traffic Report No.	BR268	BR269	BR270	BR271	BR272	BR273	BR274	BR277	BR266	BR275
Matrix:	SEDIMENT	SEDIMENT	SEDIMENT	SEDIMENT	SEDIMENT	SEDIMENT	SEDIMENT	SOIL	WATER	WATER
Units	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/L	ug/L
Dilution Factor	1.00	1.00	1.00	1.00	1.00	1.00	1.00	10.00	1.00	N/A
Percent Moisture	11	15	22	31	9	10	13	15	--	N/A

Pentachlorophenol										NR
Phenanthrene	1000	1000	510	J	J	J	J			NR
Anthracene	J	530	J							NR
Di-n-butylphthalate		J								NR
Fluoranthene	790	1600	440	J	J	J	J			NR
Pyrene	750 E	1200	J	J	J	J	J			NR
Butylbenzylphthalate		J	J				J			NR
3,3'-Dichlorobenzidine										NR
Benzo(a)anthracene	680	2000	J	J	J	J				NR
bis(2-Ethylhexyl)phthalate	J	550	540	J	J	J	440	J		NR
Chrysene	820	2800	780	J	J	J				NR
Di-n-Octyl Phthalate										NR
Benzo(b)fluoranthene	1500	3900	1600		J	J		J		NR
Benzo(k)fluoranthene					J			J		NR
Benzo(a)pyrene	730	2500	590	J	J	J		J		NR
Indeno(1,2,3-cd)pyrene	760	2000	800	J	J	J	J			NR
Dibenz(a,h)anthracene	J	J	J	J						NR
Benzo(g,h,i)perylene	690	1730	650	J	J	J	J			NR

NOTES:

Blank space - compound analyzed for but not detected

B - compound found in lab blank as well as sample, indicates possible/probable blank contamination

E - estimated value

J - estimated value, compound present below CREL but above IDL

R - analysis did not pass EPA QA/QC

N - Presumptive evidence of the presence of a compound, but can't be identified

NR - analysis not required

Detection limits elevated if Dilution Factor >1 and/or percent moisture >0%

SITE NAME: JOHN HASSALL

TDDM: 02-8602-07

SAMPLING DATE: 3/9/88

EPA CASE NO.: 9116 LAB: HITTMAN-ERASCO ASSOC., INC.

PESTICIDES

Sample ID No.	NYEF-S1 (MS/MSD)	NYEF-S2	NYEF-S3 (DUP)	NYEF-S4	NYEF-S5	NYEF-S6	NYEF-S7	NYEF-S8	NYEF-R1N1 (MS/MSD)	NYEF-TBLK1
Traffic Report No.	DR268	DR269	DR270	DR271	DR272	DR273	DR274	DR277	DR266	DR275
Matrix	SEDIMENT	SEDIMENT	SEDIMENT	SEDIMENT	SEDIMENT	SEDIMENT	SEDIMENT	SOIL	WATER	WATER
Units	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/L	ug/L
Dilution Factor	1.00	1.00	1.00	1.00	1.00	1.00	10.00	10.00	1.00	N/A
Percent Moisture	11	15	22	31	9	10	13	15	--	N/A
alpha-BHC										NR
beta-BHC										NR
delta-BHC										NR
gamma-BHC (Lindane)										NR
Heptachlor										NR
Aldrin										NR
Heptachlor epoxide										NR
Endosulfan I										NR
Dieldrin										NR
4,4'-DDE				24		29		550 E		NR
Endrin										NR
Endosulfan II										NR
4,4'-DDD								450 E		NR
Endosulfan sulfate										NR
4,4'-DDT	150 E			100	57	120	520 E	1500 E		NR
Methoxychlor										NR
Endrin ketone										NR
Chlordane		200 A	260 A							NR
Toxaphene										NR
Aroclor-1016										NR
Aroclor-1221										NR
Aroclor-1232										NR
Aroclor-1242										NR
Aroclor-1248										NR
Aroclor-1254						210				NR
Aroclor-1260		1100	1300							NR

NOTES:

Blank space - compound analyzed for but not detected

B - compound found in lab blank as well as sample, indicates possible/probable blank contamination

E - estimated value

J - estimated value, compound present below CRL but above IDL

R - analysis did not pass EPA QA/QC

N - Presumptive evidence of the presence of a compound, but can't be identified

NR - analysis not required

A - the sum of alpha and gamma chlordane

Detection limits elevated if Dilution Factor >1 and/or percent moisture >0%

SITE NAME: JOHN MASSALL  
 TDD#: 02-0602-07  
 SAMPLING DATE: 3/9/88  
 EPA CASE NO.: 9116  
 LAB NAME: CSMRI

INORGANICS

Sample ID No.	NYEF-S1 (HS/HSD)	NYEF-S2	NYEF-S3 (DUP)	NYEF-S4	NYEF-S5	NYEF-S6	NYEF-S7	NYEF-S8	NYEF-RIN1 (HS/HSD)	NYEF-TOLK1
Traffic Report No.	NBP664	NBP665	NBP666	NBP667	NBP668	NBP669	NBP670	NBP672	NBP671	N/A
Matrix	SEDIMENT	SEDIMENT	SEDIMENT	SEDIMENT	SEDIMENT	SEDIMENT	SEDIMENT	SOIL	WATER	N/A
Units	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/kg	ug/L	ug/L
Dilution Factor										
Aluminum	2360	3570	3930	16700	3100	2510	3070	14000	J	NR
Antimony										NR
Arsenic		2.7 E		6.8 E				12 E		NR
Barium	J	J	J	J	J	J	J	J		NR
Beryllium				J					J	NR
Cadmium							1.2	1.4		NR
Calcium	1880	J	J	J	3780	1340	J	4940		NR
Chromium	64 E	151 E	146 E	19 E	39 E	17 E	90 E	51 E		NR
Cobalt	J		J	J	J			J		NR
Copper	33	25	25	17	30	20	250	64		NR
Iron	5080	7230	6320	16800	4890	3930	9190	13200	J	NR
Lead	92	145	127	36	21	13	40	43		NR
Magnesium	J	J	J	2160	J	J	J	1870	J	NR
Manganese	78	51	51	155	104	84	88	173		NR
Mercury								0.82		NR
Nickel	48	21	20	13	45	20	206	49		NR
Potassium	J	J	J	J	J	J	J	J		NR
Selenium										NR
Silver	4			3.2	2.9	2.2				NR
Sodium			J	J						NR
Thallium										NR
Vanadium	J	28	29	31	J	J	J	28		NR
Zinc	167	57	59	58	75	37	154	78	J	NR
Cyanide		0.63								NR

NOTES:

Blank space - compound analyzed for but  
 not detected  
 E - estimated value  
 J - estimated value, compound present  
 below CROL but above TML  
 R - analysis did not pass EPA QA/QC  
 NR - analysis not required



Date: Nov. 6, 1987

Number: HW-4

Revision: 3

Title: Attachment 2 - CLP Data Assessment Checklist  
(GC and GC/MS Analysis).  
PART II: MMB Review - TOTAL REVIEW

*Oxymer*

CASE # 9116 LAB Hittman SITE John Hassell

19.0 Conclusions: (NOTE: Reviewers must red-line unacceptable data on sample data (FORM I) sheets; red-line data does not imply the compound is not present). Only the MMB reviewer has the authority to red-line unacceptable data. The letter J indicates an estimated value. In addition to the two definitions stated in the contract it also implies that the analyte is present but the quantitative value contains an unspecified degree of error. If an accurate quantity is desired, resampling/analysis is recommended.

19.1 Data Assessment 1- Method blanks measure laboratory contaminations.

Method blanks contaminations can be caused by dirty glassware, impure solvents, etc. In order to be valid, the concentration of an analyte in a sample must be at least 5 times (10 times for the common contaminants) the concentration of that analyte in the method blank. For method blank contamination, the following samples had Acetone qualified with "U" BR 277. The following samples had Methylene chloride qualified with "U" BR 268, BR 270, BR 272, BR 273. The following samples had Di-n-octylphthalate qualified with "U" BR 268, BR 269, BR 271, BR 273, BR 274, BR 277.  
2- Rinse blanks consist of pouring analyte free water over the cleaned piece of sampling equipment into a sample container.

19.2 Contract Problems/Non-compliance 1- The laboratory did not reextract and reanalyze samples which exhibited surrogate recoveries outside contract specifications. 2- Several analytes exhibited %RSD and %D outside contract specifications. 3- No SDG Number

Reviewer's Signature: Michael S. Hamer

Date: 8-10-88

Verified By: G. Keras

Date: 9/9/88

The same validity principal as in No #1. Because of rinse blank contamination, the following samples had Acetone qualified with "U" BR 268, BR 269, BR 270, BR 271, BR 272 and BR 273.

3. Trip blanks consist of analyte free water sealed in 40.0ml vials that are taken into the field during sampling. A field blank contamination is caused by contaminating the samples in shipping, storage or in the field. The same validity principal apply as in No #1. Because of trip blank contamination, the following samples had Methylene chloride qualified with "U" ~~BR 271~~, BR 264, BR 271, BR 274, BR 274DL, BR 277, BR 277DL.

4. All samples are spiked with surrogate compounds prior to sample preparation in order to evaluate the efficiency of the technique and laboratory performance. If one in the UOA or two or more in BN/A Analysis was outside of QC Contract specifications for any samples, Re-analysis of these samples are required. In the UOA sample NO BR 277, BR 277DL, BR 274 yielded surrogate Recovery outside Contract specification. The Lab did not reanalyze the samples according to the Contract. Because of this reason all non detects were qualified with "UJ" - No positive hits observed.

In the BN/A Analysis sample NO BR 277 yielded surrogate Recovery outside Contract specification. The same sample BR 277DL yielded recovery outside QC specifications. because of ~~this~~ this reason all non detects were qualified with "UJ". Naphthalene and 2-methylnaphthalene with "J". 2-Fluorophenol yielded recovery outside QC limits in sample NO BR 274 - No action was taken.

In the pesticide analysis, Dibutylchloronate was Diluted out in Sample No BR 277 "0% Recovery". because of this reason all non detects qualified with "UJ" and all positive with "J" 4,4' DDE, 4,4' DDD and 4,4' DDT qualified with "J" in Sample No BR 277.

5. In order to measure the Concentration of an analyte in a sample, an initial and Continuing Calibration are performed. One of the measured parameter is the analyte's response factor (RF). The response factor measures the instrument response. An analyte's Response factor either in the initial or Continuing Calibration must be  $\geq 0.5$ . A value  $< 0.5$  indicates potential Detection and Quantitation errors. For this reason 2-Butanone was qualified with "R" in the following samples BR 275, BR 266, BR 268, BR 269, BR 271, BR 272, BR 273, BR 274, BR 277.

and qualified with "J" in sample No BR 270.

Another measured parameters are (%RSD) percent relative standard deviation which measure the stability of the response factor over increasing Concentration and (%D) percent differences, which compare the daily response factor with the average response factor RRF from the initial Calibration. %D reflects instrument daily performance. %RSD must be  $< 30\%$  and %D  $< 25\%$ . In the pesticide fraction %D must be  $< 15\%$  in the primary Column.

The following analytes exhibited %RSD  $> 30\%$  in the following Associated samples:

Acetone in : BR 275, BR 266, BR 268 to BR 274, BR 277

2-Butanone in : BR 275, BR 266, BR 268 to BR 274, BR 277

2-Hexanone in : BR 274 and BR 277

The following analyte exhibited %D > 25% in the following  
Samples : (associated samples)

Bromomethane	BR 275, BR 266, BR 268, BR 270, BR 272, BR 273
Acetone	BR 275, BR 266, BR 268 to BR 274, BR 277, BR 274 DL, 277 DL
2-Hexanone	BR 275, BR 266, BR 268 to BR 274, BR 277.
Methylene chloride	BR 268, BR 270, BR 272, BR 273
Carbon disulfide	BR 269, BR 271
2-Butanone	BR 269, BR 271
1,1,2 Trichloro ethane	BR 269, BR 271
2-Chloro ethyl vinyl ether	BR 269, BR 271, BR 274 DL, BR 277 DL
Bromoform	BR 269, BR 271
4-Methyl-2-pentanone	BR 269, BR 271, BR 274 DL, BR 277 DL
1,1,2,2 Tetrachloroethane	BR 269, BR 271
1,2 Dichloroethane	BR 269, BR 271, BR 274 DL, BR 277 DL
Carbon tetrachloride	BR 274, BR 277
Vinyl acetate	BR 274, BR 277, BR 274 DL, BR 277 DL
Bromodichloromethane	BR 274 DL, BR 277 DL
Trans 1,3-dichloropropene	BR 274 DL, BR 277 DL
Cis 1,3-dichloropropene	BR 274 DL, BR 277 DL
Benzyl alcohol	BR 266, BR 270 to BR 274, BR 277, BR 268
Pyrene	BR 266, BR 270 to BR 274, BR 277, BR 268
Butyl benzyl phthalate	BR 266, BR 270 to BR 274, BR 277, BR 268
bis (2-chloroisopropyl) ether	BR 269, BR 277 DL
2,4 Dinitrophenol	" "
2,4 Dinitrotoluene	" "
Diethyl phthalate	" "
4-nitroaniline	" "
4,4 DDT	BR 268

DDT qualified with "J" in BR268 because %D  
inhibited > 15% in the primary column for 4,4'-DDT.  
sample No BR274 had 4,4'-DDT qualified with "J" because  
of high background due to interferences from the sample  
Matrix which could cause inaccurate integration of  
4,4'-DDT peaks.

\* Analysis "A" are the sum of the alpha and gamma chlordane

6- Matrixspike/Matrixspike Duplicate data are generated to determine  
long term precision and accuracy of the analytical Methods  
on various matrices. In the BNA and pesticide/PCP Fractions,  
The spiked Compounds either they diluted out or yielded recoveries  
outside Contract specifications, most probably because of sample Matrix  
interferences. No action was taken.

M.H 8-10-88

## SECTION I

### CASE NARRATIVE

Laboratory: Hittman Ebasco Associates  
CASE: 9116  
Contract Number: 68-01-7280

The problems and solutions encountered during the analysis of samples BR-266, BR-268 through BR-275, and BR-275. Samples were received on 3/10/88.

#### 1) Internal Standards and Quantitation Dilution Factor.

The internal standards are present at a concentration of forty ng/ul for Base-Neutral/Acids. To convert to micrograms/kilograms for soils requires an additional dilution factor for use by the program. As an example, a thirty gram sample requires a dilution factor of 33.3 to convert to micrograms per kilogram and does not mean that the actual sample was diluted. This is why the dilution factor on the quantitation report may not match the dilution factor on the form I's. This also holds true for medium level volatile soils which has the internal standard at a concentration of 50ng/mL.

#### 2) Concentration Listed on Quant Report and Spectral Sheets.

The concentration values on the Quant report may not agree with the values on the Individual Compound sheets. The Quant reports are sometimes updated after generation of the full report. The spectra are not effected, just the reported concentration. The spectra are present only for comparison with the reference spectra, thus the concentration listed on the spectral sheets, generated for every hit, may not agree with the quant report, from which the concentrations used on the Form I originate.

#### 3) TIC's with Probabilities Less than One are not Reported.

The library searches on tentitively identified compounds will report only those compounds that have a calculated probability match greater than one percent. Therefore some peaks will have less than three "hits" from the computer and may not have any at all. At the present time the library search program can not be made to list at least three "hits" regardless of the percent probability.

#### 4) TIC's are Time Stamped with the Time of the Library Search.

The time stamped on the TIC's is not the time of sample injection or quantitation, but the time of the actual search.

#### 5) Matrix Concentrations for Soils Reported on Form III.

The matrix spike concentration listed on our soil matrix spike Form III, reflects the actual aqueous spike concentration multiplied by the dilution factor. This dilution factor takes into account the sample weight, percent

100001

solids and the 0.5ml used for pesticide analysis. The resulting concentration is reported ug/Kg on Form III.

6) Correction factor for Base Neutral Acids.

A correction factor to take into account the the pesticide faction during extraction. During extraction of a 10 milliliter sample, half a milliliter (0.5) is used for the pesticides, leaving 9.5 milliliters for the base nuetral acid fraction. The half a milliliter has a correction factor of 1.05 for the pesticide extract in the dilution factor for base nuetral acids, located on the quanitation report.

7) Matrix Spike and Matrix Spike Duplicate for BNA soils.

Sample BR-277 was used for the matrix spike and matrix spike duplicate. The sample was diluted 1:10 and the MS and MSD were performed on the diluted sample.

8) Trace Levels of Contaminants in VOA Blanks.

There was a trace amount of methylene chloride and acetone found in the volatiles blank, but neither exceeded five times the CRDL. There were also trace levels of non-target compounds.

9) Trace amount of contaminant found in the Semivolatile Soil Blank.

There was a trace amount of Di-n-octyl phthalate found in the semi-volatile blank, but at less than the CRDL. There were also trace levels of non-target compounds.

10) Sample BR-275 was analyzed for volatiles only.

11) Samples Analyzed At Medium Level.

Samples BR-277, BR-274, and the MS/MSD for BR-274 were analyzed at medium level for the volatiles.

12) Surrogates Out Of Criteria For Volatile Analysis.

Samples BR-277 ,BR-274, and the MS/MSD for BR-274 had several surrogates out of criteria. Both of these samples however had high levels of non-target compounds which required the samples to be run at medium level. Sample BR-271 had Toluene-d8 out of criteria for the original analysis. The MS/MSD which served as the reanalysis was within criteria for all surrogates.

13) Sample diluted for Semivolatile Analysis.

Sample BR-277 was diluted 1:10 for the Semivolatile Analysis due to high levels of non-target compounds.

14) Surrogates Out Of Control For Semivolatile Analysis.

Sample BR-277 had Nitrobenzene-d5 out of Control for both the original sample and the MS/MSD which served as the reanalysis. Sample BR-274 had one

10002

surrogate, 2-fluorophenol out of control.

#### 14) Pesticide Calculations Used.

$CF = \text{Area}(\text{or Height}) / \text{Concentration} / \text{Volume injected}$

CF = Calibration Factor

$\text{Mass Injected} = \text{Area}(\text{or Height}) / CF$

$\text{Sample conc} = (\text{Mass Injected})(\text{Volume Injected})(DF)$

$DF = (Ve) / ((Ws)(D))$

Where  $Ve = (Vie/Vc) \times (Vf) \times (1000)$

$Vie$  = Volume of initial extract, generally 10.0mLs

$Vc$  = Volume of extract removed for cleanup, generally 0.5mLs

$Vf$  = Final volume of extract for Pesticide analysis taking into account any dilutions

$D$  = % Solid

$Ws$  = Weight of sample used

#### 15) Retention Time Window for Pesticides.


The retention time window for the pesticides was set at one percent of the retention time since that calculated by the twenty four hour method results in unrealistically narrow windows.

#### 16) Naming Convention for Pesticides/PCBs.

We are naming the pesticides and PCBs following the naming convention to be used in the 10/86 IFB. These are as follows:

Name	EPA Sample Number
Evaluation Mix A	EVALA
Evaluation Mix B	EVALB
Evaluation Mix C	EVALC
Individual Mix A	INDA
Individual Mix B	INDB
Toxaphene	TOXAPH
Arochlor 1016	AR1016
Arochlor 1221	AR1221
Arochlor 1232	AR1232
Arochlor 1242	AR1242
Arochlor 1248	AR1248
Arochlor 1254	AR1254
Arochlor 1260	AR1260
Arochlor 1016/1260 Mix	AR1660

This data is released by:

  
Julie Dixon  
Data Review Supervisor  
4/18/88

100003



CASE NARRATIVE EPA cs.9116

The 3%SP2100 column was used for confirmation. The ending standards exceeded criteria. No samples were run after the standards that exceeded criteria.

The 1.5%SP2250/1.95%SP2410 column was used for quantitation of all compounds except for the DDT series and methoxychlor. Degradation was 23% in the EvalB at 20:22, the dilutions of BR274, BR277, and the MS and MSD were analyzed following this standard. Methoxychlor elutes very closely with DBC, the result is poor integration. The percent difference on the Form IX is flagged C coelutes with DBC. This column was used to confirm DDT, no methoxychlor was found in the samples.

Both Aroclor 1260 and 1254 were detected in the samples for this case. The pattern was not initially recognized and an ending aroclor standard was not analyzed.

Samples BR277, BR277MS, and BR277MSD had to be analyzed at a 1:10 dilution. Even after diluting the samples were still very dirty. A rising baseline and undefined peaks may be preventing proper integration. The lowest concentration of the DDT series was reported on the Form I even though this was not from the column called quant.

Sample BR274 has the same type of matrix interference as

100004

mentioned above. It is more severe in this sample and any quantitation is impossible. There is a retention time that is in the DDT retention time window on both columns, however, the chromatogram does not show a clear peak. Because quantitation is impossible, DDT was flagged D on the Form I. This sample was not listed on the Form X.

Because of the above mentioned matrix interference of sample BR277 the matrix spike and MSD needed to be diluted. All of the spiked compounds were diluted below the detection limit. They were flagged DL on the soil Form III. BR 274 was also analyzed at a dilution, the surrogate recovery for all of these samples was flagged DL.

Both alpha and gamma chlordanes were detected in BR269 and BR270. The early technical chlordanes were not present. The concentration on the Form I's are flagged A and are the sum of the alpha and gamma chlordanes based on the concentrations in the INDB mix. These samples also have peaks that match the retention times in Aroclor 1260. The pattern is not clear, probably because of matrix interference. The calculations were done based on the peaks that matched retention times.

100005

# Organics Analysis Data Sheet (Page 1)

Sample Number  
**BR-268**  
HEAT #865

Laboratory Name Hittman Phasco Assoc. Inc.  
Lab Sample ID No: >AC047  
Sample Matrix Soil  
Data Release Authorized By [Signature]

Case No: 9116  
QC Report No: 58  
Contract No: 68-01-7280  
Date Sample Received: 3/10/88

## Volatile Compounds

Concentration: Low Medium (Circle One)  
Date Extracted/Prepared 3-14-88  
Date Analyzed: 3-14-88  
Conc/Dil Factor: 1 pH 7.2  
Percent Moisture. (Not Decanted) 11%

CAS Number		ug/l or ug/Kg (Circle One)
74-87-3	Chloromethane	11 u
74-83-9	Bromomethane	11 u
75-01-4	Vinyl Chloride	11 u
75-00-2	Chloroethane	11 u
75-09-2	Methylene Chloride	120 ug
67-64-1	Acetone	69 u
75-15-0	Carbon Disulfide	6 u
75-35-4	1, 1-Dichloroethane	6 u
75-34-3	1, 1-Dichloroethane	6 u
156-60-5	Trans-1, 2-Dichloroethane	6 u
67-66-3	Chloroform	6 u
107-06-2	1, 2-Dichloroethane	6 u
78-93-3	2-Butanone	17 u
71-55-6	1, 1, 1-Trichloroethane	6 u
56-23-5	Carbon Tetrachloride	6 u
108-05-4	Vinyl Acetate	11 u
75-27-4	Bromodichloromethane	6 u

CAS Number		ug/l or ug/Kg (Circle One)
78-87-5	1, 2-Dichloropropane	6 u
10061-02-6	Trans-1, 3-Dichloropropene	6 u
79-01-6	Trichloroethene	6 u
124-48-1	Dibromochloromethane	6 u
79-00-5	1, 1, 2-Trichloroethane	6 u
71-43-2	Benzene	6 u
10061-01-5	cis-1, 3-Dichloropropene	6 u
110-75-8	2-Chloroethylvinylether	11 u
75-25-2	Bromoform	6 u
108-10-1	4-Methyl-2-Pentanone	11 u
591-78-6	2-Hexanone	11 u
127-18-4	Tetrachloroethane	6 u
79-34-5	1, 1, 2, 2-Tetrachloroethane	6 u
108-88-3	Toluene	6 u
108-90-7	Chlorobenzene	6 u
100-41-4	Ethylbenzene	6 u
100-42-5	Styrene	6 u
	Total Xylenes	11 u

## Data Reporting Guidelines

For reporting results to EPA, the following results qualifiers are used. Additional flags or footnotes explaining results are encouraged. However, the definition of each flag must be explicit.

- Value** If the result is a value greater than or equal to the detection limit report the value.
- U** Indicates compound was analyzed for but not detected. Report the minimum detection limit for the sample with the U to g. 10U based on necessary concentration/dilution action. (This is not necessarily the instrument detection limit.) The footnote should read U Compound was analyzed for but not detected. The number is the minimum attainable detection limit for the sample.
- J** Indicates an estimated value. This flag is used either when estimating a concentration for tentatively identified compounds where a 1:1 response is assumed or when the mass spectral data indicated the presence of a compound that meets the identification criteria but the result is less than the specified detection limit but greater than zero to g. 10U. If limit of detection is 10 ug/l and a concentration of 3 ug/l is calculated, report as 3J.

- E** This flag applies to pesticide parameters where the identification has been confirmed by GC/MS. Single component pesticides  $\geq 10$  ng/l in the final extract should be confirmed by GC/MS.
- B** This flag is used when the analyte is found in the blank as well as a sample. It indicates possible probable blank contamination and warns the data user to take appropriate action.
- Other** Other specific flags and footnotes may be required to properly define the results. If used they must be fully described and such descriptions attached to the data summary report.

302001

# Organics Analysis Data Sheet (Page 1)

Sample Number  
**BR-269**  
HEAT # 866

Laboratory Name Hittman Ebasco Assoc. Inc.  
Lab Sample ID No. 2 ACO63  
Sample Matrix Soil  
Data Release Authorized By: [Signature]

Case No. 9116  
QC Report No. 38  
Contract No. 68-01-7280  
Date Sample Received: 3/10/88

## Volatile Compounds

Concentration: Low Medium (Circle One)  
Date Extracted/Prepared 3-16-88  
Date Analyzed: 3-16-88  
Conc/Dil Factor: 1 pH 4.4  
Percent Moisture. (Not Decanted) 15%

CAS Number		ug/l or ug/Kg (Circle One)
74-87-3	Chloromethane	12 u
74-83-9	Bromomethane	12 u
75-01-4	Vinyl Chloride	12 u
75-00-3	Chloroethane	12 u
75-09-2	Methylene Chloride	11 u
67-64-1	Acetone	51 u
75-15-0	Carbon Disulfide	6 u
75-35-4	1, 1-Dichloroethene	6 u
75-34-3	1, 1-Dichloroethane	6 u
156-60-5	Trans-1, 2-Dichloroethene	6 u
67-66-3	Chloroform	6 u
107-06-2	1, 2-Dichloroethane	6 u
78-93-3	2-Butanone R	12 u
71-55-6	1, 1, 1-Trichloroethane	6 u
56-23-5	Carbon Tetrachloride	6 u
108-05-4	Vinyl Acetate	12 u
75-27-4	Bromodichloromethane	6 u

CAS Number		ug/l or ug/Kg (Circle One)
78-87-5	1, 2-Dichloropropane	6 u
10061-02-6	Trans-1, 3-Dichloropropene	6 u
79-01-6	Trichloroethene	3 u
124-48-1	Dibromochloromethane	6 u
79-00-5	1, 1, 2-Trichloroethane	6 u
71-43-2	Benzene	6 u
10061-01-5	cis-1, 3-Dichloropropene	6 u
110-75-8	2-Chloroethylvinylether	12 u
75-25-2	Bromoform	6 u
108-10-1	4-Methyl-2-Pentanone	12 u
591-78-6	2-Hexanone	7 u
127-18-4	Tetrachloroethene	6 u
79-34-5	1, 1, 2, 2-Tetrachloroethane	6 u
108-88-3	Toluene	6 u
108-90-7	Chlorobenzene	6 u
100-41-4	Ethylbenzene	6 u
100-42-5	Styrene	6 u
	Total Xylenes	12 u

## Data Reporting Qualifiers

For reporting results to EPA, the following results qualifiers are used. Additional flags or footnotes explaining results are encouraged. However, the definition of each flag must be explicit.

- Value** If the result is a value greater than or equal to the detection limit report the value.
- U** Indicates compound was analyzed for but not detected. Report the minimum detection limit for the sample with the U (e.g., 10U) based on necessary concentration/dilution action. (This is not necessarily the instrument detection limit.) The footnote should read U Compound was analyzed for but not detected. The number is the minimum attainable detection limit for the sample.
- J** Indicates an estimated value. This flag is used either when estimating a concentration for tentatively identified compounds where a 1:1 response is assumed or when the mass spectral data indicated the presence of a compound that meets the identification criteria but the result is less than the specified detection limit but greater than zero (e.g., 10U). If limit of detection is 10 ug/l and a concentration of 3 ug/l is calculated, report as 3J.

- C** This flag applies to pesticide parameters where the identification has been confirmed by GC-MS. Single component pesticides  $\geq 10$  ng ul in the final extract should be confirmed by GC-MS.
- B** This flag is used when the analyte is found in the blank as well as a sample. It indicates possible probable blank contamination and warns the data user to take appropriate action.
- Other** Other specific flags and footnotes may be required to properly define the results. If used they must be fully described and such description attached to the data summary report.

303001

# Organics Analysis Data Sheet (Page 1)

Sample Number  
**BR-270**  
HEAT # **867**

Laboratory Name Hittman Phasen Assoc. Inc.  
Lab Sample ID No: 2AC049  
Sample Matrix Soil  
Data Release Authorized By: [Signature]

Case No: 9116  
QC Report No: 38  
Contract No: 68-01-7280  
Date Sample Received: 3-10-88

## Volatile Compounds

Concentration: Low Medium (Circle One)  
Date Extracted/Prepared 3-14-88  
Date Analyzed: 3-14-88  
Conc/Dil Factor: 1 pH 4.2  
Percent Moisture. (Not Decanted) 22.9%

CAS Number		ug/l or ug/Kg (Circle One)
74-87-3	Chloromethane	13 u
74-83-9	Bromomethane	13 u
75-01-4	Vinyl Chloride	13 u
75-00-3	Chloroethane	13 u
75-09-2	Methylene Chloride	110 u
67-64-1	Acetone	81 u
75-15-0	Carbon Disulfide	6 u
75-35-4	1, 1-Dichloroethane	6 u
75-34-3	1, 1-Dichloroethane	6 u
156-60-5	Trans-1, 2-Dichloroethane	6 u
67-65-3	Chloroform	6 u
107-06-2	1, 2-Dichloroethane	6 u
78-93-3	2-Butanone	6 u
71-55-6	1, 1, 1-Trichloroethane	6 u
56-23-5	Carbon Tetrachloride	6 u
108-05-4	Vinyl Acetate	13 u
75-27-4	Bromodichloromethane	6 u

CAS Number		ug/l or ug/Kg (Circle One)
78-87-5	1, 2-Dichloropropane	6 u
10061-02-6	Trans-1, 3-Dichloropropene	6 u
79-01-6	Trichloroethene	6 u
124-48-1	Dibromochloromethane	6 u
79-00-5	1, 1, 2-Trichloroethane	6 u
71-43-2	Benzene	6 u
10061-01-5	cis-1, 3-Dichloropropene	6 u
110-75-8	2-Chloroethylvinylether	13 u
75-25-2	Bromoform	6 u
108-10-1	4-Methyl-2-Pentanone	13 u
591-78-6	2-Hexanone	13 u
127-18-4	Tetrachloroethene	6 u
79-34-5	1, 1, 2, 2-Tetrachloroethane	6 u
108-88-3	Toluene	10 u
108-90-7	Chlorobenzene	6 u
100-41-4	Ethylbenzene	6 u
100-42-5	Styrene	6 u
	Total Xylenes	13 u

## Data Reporting Guidelines

For reporting results to EPA, the following results qualifiers are used. Additional flags or footnotes explaining results are encouraged. However, the definition of each flag must be explained.

- Values: If the result is a value greater than or equal to the detection limit report the value.
- U: Indicates compound was analyzed for but not detected. Report the minimum detection limit for the sample with the U to g. 10U based on necessary concentration/dilution action. (This is not necessarily the instrument detection limit.) The footnote should read U. Compound was analyzed for but not detected. The number is the minimum attainable detection limit for the sample.
- J: Indicates an estimated value. This flag is used either when estimating a concentration for sensitively detected compounds where a 1:1 response is assumed or when the mass spectral data indicates the presence of a compound that meets the identification criteria but the result is less than the specified detection limit but greater than zero to g. 10U. If limit of detection is 10 ug/l and a concentration of 3 ug/l is calculated, report as 3J.

- C: This flag applies to gas chromatograms where the identification has been confirmed by GC/MS. Single component peaks less than 2.10 ng of in the final extract should be confirmed by GC/MS.
- B: This flag is used when the analyte is found in the blank as well as a sample. It indicates possible probable blank contamination and warns the data user to take appropriate action.
- Other: Other specific flags and footnotes may be required to accurately define the results. If used they must be fully described and such descriptions attached to the data summary report.

304001

# Organics Analysis Data Sheet (Page 1)

Sample Number

BR-271

HEAT #868

Laboratory Name Hittman Ebasco Assoc. Inc.  
Lab Sample ID No. 2AC064  
Sample Matrix Soil  
Data Release Authorized By Julie Dixon

Case No. 9116  
QC Report No. JK  
Contract No. 68-01-7280  
Date Sample Received 3/10/88

## Volatile Compounds

Concentration: Low Medium (Circle One)

Date Extracted/Prepared 3/16/88

Date Analyzed: 3/16/88

Conc/Dil Factor: 1 pH 5.1

Percent Moisture (Not Decanted) 31.90

CAS  
Number

ug/l or ug/Kg  
(Circle One)

74-87-3	Chloromethane	14	u
74-83-9	Bromomethane	14	u
75-01-4	Vinyl Chloride	14	u
75-00-3	Chloroethane	14	u
75-09-2	Methylene Chloride	52	u
67-64-1	Acetone	62	u
75-15-0	Carbon Disulfide	7	u
75-35-4	1, 1-Dichloroethene	7	u
75-34-3	1, 1-Dichloroethane	7	u
156-60-5	Trans-1, 2-Dichloroethene	7	u
67-66-3	Chloroform	7	u
107-06-2	1, 2-Dichloroethane	7	u
78-93-3	2-Butanone	14	u
71-55-6	1, 1, 1-Trichloroethane	7	u
56-23-5	Carbon Tetrachloride	7	u
108-05-4	Vinyl Acetate	14	u
75-27-4	Bromodichloromethane	7	u

CAS  
Number

ug/l or ug/Kg  
(Circle One)

78-87-5	1, 2-Dichloropropane	7	u
10061-02-6	Trans-1, 3-Dichloropropene	7	u
79-01-6	Trichloroethene	7	u
124-48-1	Dibromochloromethane	7	u
79-00-5	1, 1, 2-Trichloroethane	7	u
71-43-2	Benzene	7	u
10061-01-5	cis-1, 3-Dichloropropene	7	u
110-75-8	2-Chloroethylvinylether	14	u
75-25-2	Bromoform	7	u
108-10-1	4-Methyl-2-Pentanone	14	u
591-78-6	2-Hexanone	7	u
127-18-4	Tetrachloroethene	7	u
79-34-5	1, 1, 2, 2-Tetrachloroethane	7	u
108-88-3	Toluene	7	u
108-90-7	Chlorobenzene	7	u
100-41-4	Ethylbenzene	7	u
100-42-5	Styrene	7	u
	Total Xylenes	14	u

## Data Reporting Qualifiers

For reporting results to EPA, the following results qualifiers are used. Additional flags or footnotes explaining results are encouraged. However, the definition of each flag must be explicit.

Value If the result is a value greater than or equal to the detection limit report the value

U Indicates compound was analyzed for but not detected. Report the minimum detection limit for the sample with the U (e.g., 10U) based on necessary concentration/dilution action. (This is not necessarily the instrument detection limit.) The footnote should read U. Compound was analyzed for but not detected. The number is the minimum attainable detection limit for the sample.

J Indicates an estimated value. This flag is used either when estimating a concentration for tentatively identified compounds where a 1:1 response is assumed or when the mass spectral data indicates the presence of a compound that meets the identification criteria but the result is less than the specified detection limit but greater than zero (e.g., 10U). If limit of detection is 10 ug/l and a concentration of 3 ug/l is calculated, report as 3J.

C This flag applies to pesticide parameters where the identification has been confirmed by GC-MS. Single component pesticides  $\geq 10$  ug/l in the final extract should be confirmed by GC-MS.

B This flag is used when the analyte is found in the blank as well as a sample. It indicates possible probable blank contamination and warns the data user to take appropriate action.

Other Other specific flags and footnotes may be required to properly define the results. If used they must be fully described and such description attached to the data summary report.

305001

**Organics Analysis Data Sheet**  
(Page 1)

**BR-272**  
HEAI # 864

Story Name Hittman Elasco Assoc. Inc.  
Sample ID No. > AC052  
Sample Matrix Soil  
Data Release Authorized By: [Signature]

Case No: 9116  
OC Report No: 35  
Contract No: 68-01-7280  
Date Sample Received 3-10-88

**Volatile Compounds**

Concentration: Low Medium (Circle One)  
Date Extracted/Prepared 3-14-88  
Date Analyzed: 3-14-88  
Conc/Dil Factor: 1 pH 6.6  
Percent Moisture. (Not Decanted) 9%

CAS Number		ug/l or ug/Kg (Circle One)
74-87-3	Chloromethane	11 u
74-83-9	Bromomethane	11 u
75-01-4	Vinyl Chloride	11 u
75-00-3	Chloroethane	11 u
75-09-2	Methylene Chloride	110 u
67-64-1	Acetone	36 u
75-15-0	Carbon Disulfide	6 u
75-35-4	1, 1-Dichloroethene	6 u
75-34-3	1, 1-Dichloroethane	6 u
156-60-5	Trans-1, 2-Dichloroethene	6 u
67-66-3	Chloroform	6 u
107-06-2	1, 2-Dichloroethane	6 u
78-93-3	2-Butanone	11 u
71-55-6	1, 1, 1-Trichloroethane	6 u
56-23-5	Carbon Tetrachloride	6 u
108-05-4	Vinyl Acetate	11 u
75-27-4	Bromodichloromethane	6 u

CAS Number		ug/l or ug/Kg (Circle One)
78-87-5	1, 2-Dichloropropane	6 u
10061-02-6	Trans-1, 3-Dichloropropene	6 u
79-01-6	Trichloroethene	8 u
124-48-1	Dibromochloromethane	6 u
79-00-5	1, 1, 2-Trichloroethane	6 u
71-43-2	Benzene	6 u
10061-01-5	cis-1, 3-Dichloropropene	6 u
110-75-8	2-Chloroethylvinylether	11 u
75-25-2	Bromoform	6 u
108-10-1	4-Methyl-2-Pentanol	11 u
591-78-6	2-Hexanone	10 u
127-18-4	Tetrachloroethene	6 u
79-34-5	1, 1, 2, 2-Tetrachloroethane	6 u
108-88-3	Toluene	8 u
108-90-7	Chlorobenzene	6 u
100-41-4	Ethylbenzene	6 u
100-42-5	Styrene	6 u
	Total Xylenes	11 u

**Data Reporting Qualifiers**

For reporting results to EPA, the following results qualifiers are used. Additional flags or footnotes explaining results are encouraged. However, the definition of each flag must be explicit.

- Value** If the result is a value greater than or equal to the detection limit report the value.
- U** Indicates compound was analyzed for but not detected. Report the minimum detection limit for the sample with the U (e.g., 10U) based on necessary concentration/dilution action. (This is not necessarily the instrument detection limit.) The footnote should read U. Compound was analyzed for but not detected. The number is the minimum attainable detection limit for the sample.
- J** Indicates an estimated value. This flag is used either when estimating a concentration for tentatively identified compounds where a 1:1 response is assumed or when the mass spectral data indicated the presence of a compound that meets the identification criteria but the result is less than the specified detection limit but greater than zero (e.g., 10U). If limit of detection is 10 ug/l and a concentration of 3 ug/l is calculated, report as 3J.

- C** This flag applies to pesticides where the identification has been confirmed by GC-MS. Single component pesticides  $\geq 10$  ng/l in the final extract should be confirmed by GC-MS.
- B** This flag is used when the analyte is found in the blank as well as a sample. It indicates possible probable blank contamination and warns the data user to take appropriate action.
- Other** Other specific flags and footnotes may be required to accurately define the results. If used they must be fully described and such description attached to the data summary report.

**306001**

**Organics Analysis Data Sheet**  
(Page 1)

Sample Number  
**BR-273**  
HEAI # 870

Laboratory Name Hittman Ebasco Assoc. Inc.  
Lab Sample ID No. >AC053  
Sample Matrix Soil  
Data Release Authorized By [Signature]

Case No. 9116  
QC Report No. 28  
Contract No. 68-01-7280  
Date Sample Received 3-10-88

**Volatile Compounds**

Concentration: Low Medium (Circle One)  
Date Extracted/Prepared 3-14-88  
Date Analyzed: 3-14-88  
Conc/Dil Factor: 1 pH 6.4  
Percent Moisture (Not Decanted) 10%

CAS Number		ug/l or ug/Kg (Circle One)
73	Chloromethane	11 U
75-00-3	Bromomethane	11 U
75-01-4	Vinyl Chloride	11 U
75-00-3	Chloroethane	11 U
75-09-2	Methylene Chloride	130 U
67-64-1	Acetone	89 U
75-15-0	Carbon Disulfide	6 U
75-35-4	1,1-Dichloroethene	6 U
75-34-3	1,1-Dichloroethane	6 U
156-60-5	Trans-1,2-Dichloroethene	6 U
67-66-3	Chloroform	6 U
107-06-2	1,2-Dichloroethane	6 U
78-93-3	2-Butanone	11 U
71-55-6	1,1,1-Trichloroethane	6 U
56-23-5	Carbon Tetrachloride	6 U
108-05-4	Vinyl Acetate	11 U
75-27-4	Bromodichloromethane	6 U

CAS Number		ug/l or ug/Kg (Circle One)
78-87-5	1,2-Dichloropropane	6 U
10061-02-6	Trans-1,3-Dichloropropene	6 U
79-01-6	Trichloroethene	15 U
124-48-1	Dibromochloromethane	6 U
79-00-5	1,1,2-Trichloroethane	6 U
71-43-2	Benzene	6 U
10061-01-5	cis-1,3-Dichloropropene	6 U
110-75-8	2-Chloroethylvinylether	11 U
75-25-2	Bromoform	6 U
108-10-1	4-Methyl-2-Pentanone	11 U
591-78-6	2-Hexanone	11 U
127-18-4	Tetrachloroethene	6 U
79-34-5	1,1,2,2-Tetrachloroethane	6 U
108-88-3	Toluene	21 U
108-90-7	Chlorobenzene	6 U
100-41-4	Ethylbenzene	6 U
100-42-5	Styrene	6 U
	Total Xylenes	11 U

**Data Reporting Qualifiers**

For reporting results to EPA, the following results qualifiers are used. Additional flags or footnotes explaining results are encouraged. However, the definition of each flag must be explained.

- Value** If the result is a value greater than or equal to the detection limit, report the value.
- U** Indicates compound was analyzed for but not detected. Report the minimum detection limit for the sample with the U (e.g., 10U) based on necessary concentration/dilution action. (This is not necessarily the instrument detection limit.) The footnote should read U. Compound was analyzed for but not detected. The number is the minimum attainable detection limit for the sample.
- J** Indicates an estimated value. This flag is used either when estimating a concentration for tentatively identified compounds where a 1:1 response is assumed or when the mass spectral data indicated the presence of a compound that meets the identification criteria but the result is less than the specified detection limit but greater than zero (e.g., 10U). If limit of detection is 10 ug/l and a concentration of 3 ug/l is calculated, report as 3J.

- C** This flag applies to pesticide parameters where the identification has been confirmed by GC/MS. Single component pesticides  $\geq 10$  ng/g in the final extract should be confirmed by GC/MS.
- B** This flag is used when the analyte is found in the blank as well as a sample. It indicates possible probable blank contamination and warns the data user to take appropriate action.
- Other** Other specific flags and footnotes may be required to properly define the results. If used they must be fully described and such description attached to the data summary report.

307001



# Organics Analysis Data Sheet (Page 1)

Sample Number

B-274

HERI # 871

Laboratory Name Hittman Ebasco Assoc. Inc.  
Lab Sample ID No. 2003  
Sample Matrix: Soil  
Data Release Authorized By: John Dwyer

Case No: 9116  
QC Report No: 358  
Contract No: 68-01-7280  
Date Sample Received: 3-10-88

## Volatile Compounds

Concentration: Low Medium (Circle One)  
Date Extracted/Prepared 3-17-88  
Date Analyzed: 3-17-88  
Conc/Dil Factor: 1 pH 6.8  
Percent Moisture: (Not Decanted) 137

CAS Number		ug/l or <u>ug/Kg</u> (Circle One)
74-87-3	Chloromethane	<u>1400 u</u>
74-83-9	Bromomethane	<u>1400 u</u>
75-01-4	Vinyl Chloride	<u>1400 u</u>
75-00-3	Chloroethane	<u>1400 u</u>
75-09-2	Methylene Chloride	<u>820 u</u>
67-64-1	Acetone	<u>1400 u</u>
75-15-0	Carbon Disulfide	<u>720 u</u>
75-35-4	1, 1-Dichloroethene	<u>720 u</u>
75-34-3	1, 1-Dichloroethane	<u>720 u</u>
156-60-5	Trans-1, 2-Dichloroethene	<u>720 u</u>
67-66-3	Chloroform	<u>720 u</u>
107-06-2	1, 2-Dichloroethane	<u>720 u</u>
78-93-3	2-Butanone	<u>1400 u</u>
71-55-6	1, 1, 1-Trichloroethane	<u>720 u</u>
56-23-5	Carbon Tetrachloride	<u>720 u</u>
108-05-4	Vinyl Acetate	<u>1400 u</u>
75-27-4	Bromodichloromethane	<u>720 u</u>

CAS Number		ug/l or <u>ug/Kg</u> (Circle One)
78-87-5	1, 2-Dichloropropane	<u>720 u</u>
10061-02-6	Trans-1, 3-Dichloropropene	<u>720 u</u>
79-01-6	Trichloroethene	<u>720 u</u>
124-48-1	Dibromochloromethane	<u>720 u</u>
79-00-5	1, 1, 2-Trichloroethane	<u>720 u</u>
71-43-2	Benzene	<u>720 u</u>
10061-01-5	cis-1, 3-Dichloropropene	<u>720 u</u>
110-75-8	2-Chloroethylvinylether	<u>1400 u</u>
75-25-2	Bromoform	<u>720 u</u>
108-10-1	4-Methyl-2-Pentanone	<u>1400 u</u>
591-78-6	2-Hexanone	<u>1400 u</u>
127-18-4	Tetrachloroethene	<u>720 u</u>
79-34-5	1, 1, 2, 2-Tetrachloroethane	<u>720 u</u>
108-88-3	Toluene	<u>720 u</u>
108-90-7	Chlorobenzene	<u>720 u</u>
100-41-4	Ethylbenzene	<u>720 u</u>
100-42-5	Styrene	<u>720 u</u>
	Total Xylenes	<u>1400 u</u>

## Data Reporting Qualifiers

For reporting results to EPA, the following results qualifiers are used  
Additional flags or footnotes explaining results are encouraged. However, the definition of each flag must be explicit.

- Value** If the result is a value greater than or equal to the detection limit report the value
- U** Indicates compound was analyzed for but not detected. Report the minimum detection limit for the sample with the U (e.g., 10U) based on necessary concentration/dilution action. (This is not necessarily the instrument detection limit.) The footnote should read U. Compound was analyzed for but not detected. The number is the minimum attainable detection limit for the sample.
- J** Indicates an estimated value. This flag is used either when estimating a concentration for tentatively identified compounds where a 1:1 response is assumed or when the mass spectral data indicated the presence of a compound that meets the identification criteria but the result is less than the specified detection limit but greater than zero (e.g., 10J). If limit of detection is 10 ug/l and a concentration of 3 ug/l is calculated, report as 3J.

- C** This flag applies to pesticide parameters where the identification has been confirmed by GC/MS. Single component pesticides  $\geq 10$  ng/l in the final extract should be confirmed by GC/MS.
- B** This flag is used when the analyte is found in the blank as well as a sample. It indicates possible, probable blank contamination and warns the data user to take appropriate action.
- Other** Other specific flags and footnotes may be required to properly define the results. If used they must be fully described and such description attached to the data summary report.

308001

# Organics Analysis Data Sheet (Page 1)

Sample Number  
**BR-277**  
HEAT #873

Laboratory Name Hittman Ebasco Assoc. Inc.  
Lab Sample ID No: 2CCO30  
Sample Matrix Soil  
Data Release Authorized By: [Signature]

Case No: 9116  
QC Report No: 38  
Contract No: 68-01-7280  
Date Sample Received: 3/10/88

## Volatile Compounds

Concentration: Low Medium (Circle One)

Date Extracted/Prepared 3-17-88

Date Analyzed: 3-17-88

Conc/Dil Factor: 1 pH 6.7

Percent Moisture (Not Decanted) 15%

CAS  
Number

ug/l or ug/Kg  
(Circle One)

74-87-3	Chloromethane	1500 U
74-83-9	Bromomethane	1500 U
75-01-4	Vinyl Chloride	1500 U
75-00-3	Chloroethane	1500 U
75-09-2	Methylene Chloride	780 U
67-64-1	Acetone	1500 U
75-15-0	Carbon Disulfide	740 U
75-35-4	1, 1-Dichloroethane	740 U
75-34-3	1, 1-Dichloroethane	740 U
156-60-5	Trans-1, 2-Dichloroethane	740 U
67-66-3	Chloroform	740 U
107-06-2	1, 2-Dichloroethane	740 U
78-93-3	2-Butanone	1500 U
71-55-6	1, 1, 1-Trichloroethane	740 U
56-23-5	Carbon Tetrachloride	740 U
108-05-4	Vinyl Acetate	1500 U
75-27-4	Bromodichloromethane	740 U

CAS  
Number

ug/l or ug/Kg  
(Circle One)

78-87-5	1, 2-Dichloropropane	740 U
10061-02-6	Trans-1, 3-Dichloropropene	740 U
79-01-6	Trichloroethene	740 U
124-48-1	Dibromochloromethane	740 U
79-00-5	1, 1, 2-Trichloroethane	740 U
71-43-2	Benzene	740 U
10061-01-5	cis-1, 3-Dichloropropene	740 U
110-75-8	2-Chloroethylvinylether	1500 U
75-25-2	Bromoform	740 U
108-10-1	4-Methyl-2-Pentanone	1500 U
591-78-6	2-Hexanone	1500 U
127-18-4	Tetrachloroethane	740 U
79-34-5	1, 1, 2, 2-Tetrachloroethane	740 U
108-88-3	Toluene	740 U
108-90-7	Chlorobenzene	740 U
100-41-4	Ethylbenzene	740 U
100-42-5	Styrene	740 U
	Total Xylenes	1500 U

## Data Reporting Qualifiers

For reporting results to EPA, the following results qualifiers are used. Additional flags or footnotes explaining results are encouraged. However, the definition of each flag must be explained.

- Value: If the result is a value greater than or equal to the detection limit, report the value.
- U: Indicates compound was analyzed for but not detected. Report the minimum detection limit for the sample with the U (e.g., 10U) based on necessary concentration/reduction action. (This is not necessarily the instrument detection limit.) The footnote should read: U Compound was analyzed for but not detected. The number is the minimum attainable detection limit for the sample.
- J: Indicates an estimated value. This flag is used either when estimating a concentration for tentatively identified compounds where a 1:1 response is assumed or when the mass spectral data indicated the presence of a compound that meets the identification criteria but the result is less than the specified detection limit but greater than zero (e.g., 10U). If limit of detection is 10 ug/l and a concentration of 3 ug/l is calculated, report as 3J.

- E: This flag applies to pesticide parameters where the identification has been confirmed by GC-MS. Single component pesticides ≥ 10 ug/l in the final extract should be confirmed by GC-MS.
- B: This flag is used when the analyte is found in the blank as well as a sample. It indicates possible probable blank contamination and warns the data user to take appropriate action.
- Other: Other specific flags and footnotes may be required to properly define the results. If used, they must be fully described and such description attached to the data summary report.

304001

**Organics Analysis Data Sheet**  
(Page 1)

Sample Number  
**BR-266**  
HEAT# 864

Laboratory Name Hittman Ebasco Assoc. Inc.

Case No: 9116

Lab Sample ID No >AC041

OC Report No: 38

Sample Matrix Water

Contract No: 68-01-7280

Date Release Authorized By John Dixon

Date Sample Received 3/10/88

**Volatile Compounds**

Concentration: Low Medium (Circle One)

Date Extracted/Prepared 3-11-88

Date Analyzed: 3-11-88

Conc/Dil Factor: 1 pH 7

Percent Moisture: (Not Decanted) N/A

CAS Number		ug/l or ug/Kg (Circle One)
74-87-3	Chloromethane	10 U
74-83-9	Bromomethane	10 U
75-01-4	Vinyl Chloride	10 U
75-00-3	Chloroethane	10 U
75-08-2	1,1-Dichloroethane	11 R
67-64-1	Acetone	13 B
75-15-0	Carbon Disulfide	5 U
75-35-4	1,1-Dichloroethane	5 U
75-34-3	1,1-Dichloroethane	5 U
56-60-5	Trans-1,2-Dichloroethane	5 U
66-3	Chloroform	5 U
107-06-2	1,2-Dichloroethane	5 U
78-93-3	2-Butanone	10 U
71-55-6	1,1,1-Trichloroethane	5 U
56-23-5	Carbon Tetrachloride	5 U
108-05-4	Vinyl Acetate	10 U
75-27-4	Bromodichloromethane	5 U

CAS Number		ug/l or ug/Kg (Circle One)
78-87-5	1,2-Dichloropropane	5 U
10061-02-6	Trans-1,3-Dichloropropene	5 U
79-01-6	Trichloroethene	5 U
124-48-1	Dibromochloromethane	5 U
79-00-5	1,1,2-Trichloroethane	5 U
71-43-2	Benzene	5 U
10061-01-5	cis-1,3-Dichloropropene	5 U
110-75-8	2-Chloroethylvinylether	10 U
75-25-2	Bromoform	5 U
108-10-1	4-Methyl-2-Pentanone	10 U
591-78-6	2-Hexanone	10 U
127-18-4	Tetrachloroethene	5 U
79-34-5	1,1,2,2-Tetrachloroethane	5 U
108-88-3	Toluene	5 U
108-90-7	Chlorobenzene	5 U
100-41-4	Ethylbenzene	5 U
100-42-5	Styrene	5 U
	Total Xylenes	10 U

**Data Reporting Guidelines**

For reporting results to EPA, the following results qualifiers are used. Additional flags or footnotes explaining results are encouraged. However, the definition of each flag must be explicit.

**Value** If the result is a value greater than or equal to the detection limit report the value

**U** Indicates compound was analyzed for but not detected. Report the minimum detection limit for the sample with the U to g 10U based on necessary concentration/dilution action. (This is not necessarily the instrument detection limit.) The footnote should read U. Compound was analyzed for but not detected. The number is the minimum allowable detection limit for the sample.

**J** Indicates an estimated value. This flag is used either when estimating a concentration for tentatively identified compounds where a 1:1 response is assumed or when the mass spectral data indicated the presence of a compound that meets the identification criteria but the result is less than the specified detection limit but greater than zero (e.g., 10U). If limit of detection is 10 ug/l and a concentration of 3 ug/l is calculated, report as 3J.

**E** This flag applies to pesticide parameters where the identification has been confirmed by GC-MS. Single component pesticides ≥ 10 ug/l in the final extract should be confirmed by GC-MS.

**B** This flag is used when the analyte is found in the blank as well as in a sample. It indicates possible probable blank contamination and warns the data user to take appropriate action.

**Other** Other specific flags and footnotes may be required to properly define the results. If used, there must be fully described and such description attached to the data summary report.

**301001**

**Organics Analysis Data Sheet**  
(Page 1)

Sample Number  
**BR-275**  
HEAT# 872

Laboratory Name Hittman Ebasco Assoc. Inc.  
Lab Sample ID No >AC040  
Sample Matrix Water  
Data Release Authorized By [Signature]

Case No 9116  
QC Report No 38  
Contract No 68-01-7280  
Date Sample Received 3/10/88

**Volatile Compounds**

Concentration: Low Medium (Circle One)  
Date Extracted/Prepared 3-11-88  
Date Analyzed: 3-11-88  
Conc/Dil Factor: 1 pH 6.5  
Percent Moisture. (Not Decanted) N/A

CAS Number		ug/l or ug/Kg (Circle One)
74-87-3	Chloromethane	10 U
74-83-9	Bromomethane	10 U
75-01-4	Vinyl Chloride	10 U
75-00-3	Chloroethane	10 U
75-09-2	Methylene Chloride	13 U
67-64-1	Acetone	9 U
75-15-0	Carbon Disulfide	5 U
75-35-4	1, 1-Dichloroethene	5 U
75-34-3	1, 1-Dichloroethane	5 U
156-60-5	Trans-1, 2-Dichloroethene	5 U
67-66-3	Chloroform	5 U
107-06-2	1, 2-Dichloroethane	5 U
78-93-3	2-Butanone R	10 U
71-55-6	1, 1, 1-Trichloroethane	5 U
56-23-5	Carbon Tetrachloride	5 U
108-05-4	Vinyl Acetate	10 U
75-27-4	Bromodichloromethane	5 U

CAS Number		ug/l or ug/Kg (Circle One)
78-87-5	1, 2-Dichloropropane	5 U
10061-02-6	Trans-1, 3-Dichloropropene	5 U
79-01-8	Trichloroethene	5 U
124-48-1	Dibromochloromethane	5 U
79-00-5	1, 1, 2-Trichloroethane	5 U
71-43-2	Benzene	5 U
10061-01-5	cis-1, 3-Dichloropropene	5 U
110-75-8	2-Chloroethylvinylether	10 U
75-25-2	Bromoform	5 U
108-10-1	4-Methyl-2-Pentanone	10 U
591-78-6	2-Hexanone	10 U
127-18-4	Tetrachloroethene	5 U
79-34-5	1, 1, 2, 2-Tetrachloroethane	5 U
108-88-3	Toluene	5 U
108-90-7	Chlorobenzene	5 U
100-41-4	Ethylbenzene	5 U
100-42-5	Styrene	5 U
	Total Xylenes	10 U

**Data Reporting Guidelines**

For reporting results to EPA, the following results qualifiers are used  
Additional flags or footnotes explaining results are encouraged. However, the definition of each flag must be explicit

**Value** If the result is a value greater than or equal to the detection limit report the value

**U** Indicates compound was analyzed for but not detected. Report the minimum detection limit for the sample with the U (e.g. 10U) based on necessary concentration/dilution action. (This is not necessarily the instrument detection limit.) The footnote should read U. Compound was analyzed for but not detected. The number is the minimum attainable detection limit for the sample.

**J** Indicates an estimated value. This flag is used either when estimating a concentration for tentatively identified compounds where a 1:1 response is assumed or when the mass spectral data indicated the presence of a compound that meets the identification criteria but the result is less than the specified detection limit but greater than zero (e.g. 10U). If limit of detection is 10 ug/l and a concentration of 3 ug/l is calculated, report as 3J.

**C** This flag applies to pesticide parameters where the identification has been confirmed by GC-MS. Single component pesticides  $\geq 10$  ug/l in the final extract should be confirmed by GC-MS.

**B** This flag is used when the analyte is found in the blank as well as a sample. It indicates possible probable blank contamination and warns the data user to take appropriate action.

**Other** Other specific flags and footnotes may be required to properly define the results. If used there must be fully described and such description attached to the data summary report.

309001

Laboratory Name Hittman Ebasco Assoc. Inc.

Case No. 9116

# Organics Analysis Data Sheet (Page 2)

Sample Number

BR-268

HEAT # 874

> BC037

## Semivolatile Compounds

Concentration: Low Medium (Circle One)  
Date Extracted/Prepared: 3-14-88  
Date Analyzed: 3-17-88  
Conc./Dil Factor: 1  
Percent Moisture (Decanted) 1190

GPC Cleanup ☐ Yes ☐ No

Separatory Funnel Extraction ☐ Yes

Continuous Liquid - Liquid Extraction ☐ Yes

CAS  
Number

ug/l or ug/Kg  
(Circle One)

108-95-2	Phenol	390 U
111-44-4	bis(2-Chloroethyl)Ether	390 U
95-57-8	2-Chlorophenol	390 U
541-73-1	1,3-Dichlorobenzene	390 U
106-46-7	1,4-Dichlorobenzene	390 U
100-51-6	Benzyl Alcohol	390 U
95-50-1	1,2-Dichlorobenzene	390 U
95-48-7	2-Methylphenol	390 U
39638-32-9	bis(2-chloroisopropyl)Ether	390 U
106-44-5	4-Methylphenol	390 U
621-64-7	N-Nitroso-Di-n-Propylamine	390 U
67-72-1	Hexachloroethane	390 U
98-95-3	Nitrobenzene	390 U
78-59-1	Isophorone	390 U
88-75-5	2,4-Dinitrophenol	390 U
105-67-9	2,4-Dimethylphenol	390 U
65-85-0	Benzoic Acid	92 J
111-91-1	bis(2-Chloroethoxy)Methane	390 U
120-83-2	2,4-Dichlorophenol	390 U
120-82-1	1,2,4-Trichlorobenzene	390 U
91-20-3	Naphthalene	110 J
106-47-8	4-Chloroaniline	390 U
87-68-3	Hexachlorobutadiene	390 U
59-50-7	4-Chloro-3-Methylphenol	390 U
91-57-6	2-Methylnaphthalene	73 J
77-47-4	Hexachlorocyclopentadiene	390 U
88-06-2	2,4,6-Trichlorophenol	390 U
95-95-4	2,4,5-Trichlorophenol	2000 U
91-58-7	2-Chloronaphthalene	390 U
88-74-4	2-Nitroaniline	2000 U
131-11-3	Dimethyl Phthalate	390 U
208-96-8	Acenaphthylene	390 U
99-09-2	3-Nitroaniline	2000 U

CAS  
Number

ug/l or ug/Kg  
(Circle One)

83-32-9	Acenaphthene	180 J
51-28-5	2,4-Dinitrophenol	2000 U
100-02-7	4-Nitrophenol	2000 U
132-64-9	Dibenzofuran	130 J
121-14-2	2,4-Dinitrotoluene	390 U
808-20-2	2,6-Dinitrotoluene	390 U
84-86-2	Diethylphthalate	390 U
7005-72-3	4-Chlorophenyl-phenylether	390 U
86-73-7	Fluorene	240 J
100-01-6	4-Nitroaniline	2000 U
534-52-1	4,6-Dinitro-2-Methylphenol	390 U
86-30-6	N-Nitrosodiphenylamine (1)	390 U
101-55-3	4-Bromophenyl-phenylether	390 U
118-74-1	Hexachlorobenzene	390 U
87-86-5	Pentachlorophenol	2000 U
85-01-8	Phenanthrene	1800
120-12-7	Anthracene	380 J
84-74-2	Di-n-Butylphthalate	390 U
206-44-0	Fluoranthene	790
129-00-0	Pyrene	750 J
85-88-7	Butylbenzylphthalate	390 U
91-94-1	3,3'-Dichlorobenzidine	780 U
56-55-3	Benzo(a)Anthracene	680
117-81-7	bis(2-Ethylhexyl)Phthalate	250 J
218-01-9	Chrysene	820
117-84-0	Di-n-Octyl Phthalate	250 J
205-99-2	Benzo(b)Fluoranthene	1500
207-08-9	Benzo(k)Fluoranthene	390 U
50-32-8	Benzo(a)Pyrene	730
193-39-5	Indeno(1,2,3-cd)Pyrene	780
53-70-3	Dibenz(a,h)Anthracene	130 J
191-24-2	Benzo(g,h,i)Perylene	690

(1) Cannot be separated from diphenylamine 302002

Company Name Hittman Ebasco Assoc. Inc.

No. 9116

**Organics Analysis Data Sheet**  
(Page 2)

Sample Number

BL-269

HEAT# 875

>BD010

**Semivolatile Compounds**

Concentration: Low Medium (Circle One)

Date Extracted/Prepared: 3-14-88

Date Analyzed: 4-4-88

Conc./Dil Factor: 1

Percent Moisture (Decanted) 15%

GPC Cleanup ☐ Yes ☒ No

Separatory Funnel Extraction ☐ Yes

Continuous Liquid - Liquid Extraction ☐ Yes

CAS Number		ug/l or ug/Kg (Circle One)
108-95-2	Phenol	51 J
111-44-4	bis(2-Chloroethyl)Ether	400 U
95-57-8	2-Chlorophenol	400 U
541-73-1	1,3-Dichlorobenzene	400 U
106-46-7	1,4-Dichlorobenzene	400 U
100-51-6	Benzyl Alcohol	400 U
95-50-1	1,2-Dichlorobenzene	400 U
95-48-7	2-Methylphenol	400 U
39638-32-9	bis(2-chloroisopropyl)Ether	400 U
106-44-5	4-Methylphenol	400 U
621-64-7	N-Nitroso-Di-n-Propylamine	400 U
67-72-1	Hexachloroethane	400 U
98-95-3	Nitrobenzene	400 U
78-59-1	Isophorone	400 U
88-75-5	2-Nitrophenol	400 U
105-67-9	2,4-Dimethylphenol	400 U
65-85-0	Benzoic Acid	6000
111-91-1	bis(2-Chloroethoxy)Methane	400 U
120-83-2	2,4-Dichlorophenol	400 U
120-82-1	1,2,4-Trichlorobenzene	400 U
91-20-3	Naphthalene	45 J
106-47-8	4-Chloroaniline	400 U
87-68-3	Hexachlorobutadiene	400 U
59-50-7	4-Chloro-3-Methylphenol	400 U
91-57-6	2-Methylnaphthalene	43 J
77-47-4	Hexachlorocyclopentadiene	400 U
88-06-2	2,4,6-Trichlorophenol	400 U
95-95-4	2,4,5-Trichlorophenol	2000 U
91-58-7	2-Chloronaphthalene	400 U
88-74-4	2-Nitroaniline	2000 U
131-11-3	Dimethyl Phthalate	400 U
208-96-8	Acenaphthylene	28 J
89-09-2	3-Nitroaniline	2000 U

CAS Number		ug/l or ug/Kg (Circle One)
83-32-9	Acenaphthene	67 J
51-28-5	2,4-Dinitrophenol	2000 U
100-02-7	4-Nitrophenol	400 U
132-64-9	Dibenzofuran	47 J
121-14-2	2,4-Dinitrotoluene	400 U
808-20-2	2,6-Dinitrotoluene	520
84-86-2	Diethylphthalate	400 U
7005-72-3	4-Chlorophenyl-phenylether	400 U
86-73-7	Fluorene	140 J
100-01-6	4-Nitroaniline	2000 U
534-52-1	4,6-Dinitro-2-Methylphenol	2000 U
86-30-6	N-Nitrosodiphenylamine (1)	400 U
101-55-3	4-Bromophenyl-phenylether	400 U
118-74-1	Hexachlorobenzene	400 U
87-86-5	Pentachlorophenol	2000 U
85-01-8	Phenanthrene	1800
120-12-7	Anthracene	530
84-74-2	Di-n-Butylphthalate	29 J
208-44-0	Fluoranthene	1600
129-00-0	Pyrene	1200
85-68-7	Butylbenzylphthalate	93 J
91-94-1	3,3'-Dichlorobenzidine	810 U
58-55-3	Benzolanthracene	2000
117-81-7	bis(2-Ethylhexyl)Phthalate	550
218-01-9	Chrysene	2800
117-84-0	Di-n-Octyl Phthalate	330 J
205-99-2	Benzol(b)Fluoranthene	3900
207-08-9	Benzol(k)Fluoranthene	810 U
50-32-8	Benzol(a)Pyrene	2500
193-39-5	Indeno(1,2,3-cd)Pyrene	2000
53-70-3	Dibenz(a,h)Anthracene	360 J
191-24-2	Benzol(g,h,i)Perylene	1730

(1) Cannot be separated from diphenylamine

303002

Name Rittman Ebasco Assoc. Inc.  
 9116  
 do: \_\_\_\_\_

Sample Number  
BR-270  
780038  
WEAS \* 876

Organics Analysis Data Sheet  
 (Page 2)

Semivolatile Compounds

Concentration: (Low) Medium (Circle One)  
 Date Extracted/Prepared 3-14-88  
 Date Analyzed 3-17-88  
 Conc/Dil Factor: 1  
 Percent Moisture (Decanted) 22

GPC Cleanup ☐ Yes ☒ No  
 Separatory Funnel Extraction ☐ Yes  
 Continuous Liquid - Liquid Extraction ☐ Yes

CAS Number		ug/l or ug/Kg (Circle One)
108-95-2	Phenol	430 U
111-44-4	bis(2-Chloroethyl)Ether	430 U
95-57-8	2-Chlorophenol	430 U
541-73-1	1,3-Dichlorobenzene	430 U
106-46-7	1,4-Dichlorobenzene	430 U
100-51-6	Benzyl Alcohol	430 U
95-50-1	1,2-Dichlorobenzene	430 U
95-48-7	2-Methylphenol	430 U
39638-32-9	bis(2-chloroisopropyl)Ether	430 U
106-44-5	4-Methylphenol	430 U
621-64-7	N-Nitroso-Di-n-Propylamine	430 U
67-72-1	Hexachloroethane	430 U
98-95-3	Nitrobenzene	430 U
78-59-1	Isophorone	430 U
88-75-5	2-Nitrophenol	430 U
105-67-9	2,4-Dimethylphenol	430 U
65-85-0	Benzoic Acid	780 J
111-91-1	bis(2-Chloroethoxy)Methane	430 U
120-83-2	2,4-Dichlorophenol	430 U
120-82-1	1,2,4-Trichlorobenzene	430 U
91-20-3	Naphthalene	430 U
106-47-8	4-Chloroaniline	430 U
87-68-3	Hexachlorobutadiene	430 U
59-50-7	4-Chloro-3-Methylphenol	430 U
91-57-6	2-Methylnaphthalene	430 U
77-47-4	Hexachlorocyclopentadiene	430 U
88-06-2	2,4,6-Trichlorophenol	430 U
95-95-4	2,4,5-Trichlorophenol	2200 U
91-58-7	2-Chloronaphthalene	430 U
88-74-4	2-Nitroaniline	2200 U
131-11-3	Dimethyl Phthalate	430 U
208-96-8	Acenaphthylene	430 U
99-09-2	3-Nitroaniline	2200 U

CAS Number		ug/l or ug/Kg (Circle One)
83-32-9	Acenaphthene	430 U
51-28-5	2,4-Dinitrophenol	2200 U
100-02-7	4-Nitrophenol	2200 U
132-64-9	Dibenzofuran	430 U
121-14-2	2,4-Dinitrotoluene	430 U
606-20-2	2,6-Dinitrotoluene	430 U
84-66-2	Diethylphthalate	430 U
7005-72-3	4-Chlorophenyl-phenylether	430 U
86-73-7	Fluorene	430 U
100-01-8	4-Nitroaniline	2200 U
534-52-1	4,6-Dinitro-2-Methylphenol	2200 U
86-30-6	N-Nitrosodiphenylamine (1)	430 U
101-55-3	4-Bromophenyl-phenylether	430 U
118-74-1	Hexachlorobenzene	430 U
87-86-5	Pentachlorophenol	2200 U
85-01-8	Phenanthrene	510
120-12-7	Anthracene	50 J
84-74-2	Di-n-Butylphthalate	430 U
206-44-0	Fluoranthene	440
129-00-0	Pyrene	390 J
85-68-7	Butylbenzylphthalate	88 J
91-94-1	3,3-Dichlorobenzidine	860 U
56-55-3	Benzol(a)Anthracene	350 J
117-81-7	bis(2-Ethylhexyl)Phthalate	540
218-01-9	Chrysene	780
117-84-0	Di-n-Octyl Phthalate	430 U
205-99-2	Benzol(b)Fluoranthene	1600
207-08-8	Benzol(k)Fluoranthene	430 U
50-32-8	Benzol(a)Pyrene	590
193-39-5	Indeno(1,2,3-cd)Pyrene	800
53-70-3	Dibenz(a,h)Anthracene	110 J
191-24-2	Benzol(g,h,i)Perylene	650

(1)-Cannot be separated from diphenylamine

304002

Company Name Hittman Ebasco Assoc. Inc.  
 Case No 9116

# Organics Analysis Data Sheet (Page 2)

Sample Number  
BR-271

282074

## Semivolatile Compounds

Concentration: Low Medium (Circle One)  
 Date Extracted / Prepared 3-14-88  
 Date Analyzed: 3-17-88  
 Conc/Dil Factor: 1  
 Percent Moisture (Decanted) 31

GPC Cleanup ☐ Yes ☒ No  
 Separatory Funnel Extraction ☐ Yes  
 Continuous Liquid - Liquid Extraction ☐ Yes

CAS Number		ug/l or ug/Kg (Circle One)
108-95-2	Phenol	490 U
111-44-4	bis(2-Chloroethyl)Ether	490 U
95-57-8	2-Chlorophenol	490 U
541-73-1	1,3-Dichlorobenzene	490 U
106-46-7	1,4-Dichlorobenzene	490 U
100-51-6	Benzyl Alcohol	490 U
95-50-1	1,2-Dichlorobenzene	490 U
95-48-7	2-Methylphenol	490 U
39638-32-9	bis(2-chloroisopropyl)Ether	490 U
106-44-5	4-Methylphenol	490 U
621-64-7	N-Nitroso-Di-n-Propylamine	490 U
67-72-1	Hexachloroethane	490 U
98-95-3	Nitrobenzene	490 U
78-59-1	Isophorone	490 U
88-75-5	2-Nitrophenol	490 U
105-67-9	2,4-Dimethylphenol	490 U
65-85-0	Benzoic Acid	240 J
111-91-1	bis(2-Chloroethoxy)Methane	490 U
120-83-2	2,4-Dichlorophenol	490 U
120-82-1	1,2,4-Trichlorobenzene	490 U
91-20-3	Naphthalene	490 U
106-47-8	4-Chloroaniline	490 U
87-68-3	Hexachlorobutadiene	490 U
59-50-7	4-Chloro-3-Methylphenol	490 U
91-57-6	2-Methylnaphthalene	490 U
77-47-4	Hexachlorocyclopentadiene	490 U
88-06-2	2,4,6-Trichlorophenol	490 U
95-95-4	2,4,5-Trichlorophenol	240 J
91-58-7	2-Chloronaphthalene	490 U
88-74-4	2-Nitroaniline	240 J
131-11-3	Dimethyl Phthalate	490 U
208-96-8	Acenaphthylene	490 U
99-09-2	3-Nitroaniline	240 J

CAS Number		ug/l or ug/Kg (Circle One)
83-32-9	Acenaphthene	490 U
51-28-5	2,4-Dinitrophenol	240 J
100-02-7	4-Nitrophenol	240 J
132-64-9	Dibenzofuran	490 U
121-14-2	2,4-Dinitrotoluene	490 U
606-20-2	2,6-Dinitrotoluene	490 U
84-66-2	Diethylphthalate	490 U
7005-72-3	4-Chlorophenyl-phenylether	490 U
86-73-7	Fluorene	490 U
100-01-6	4-Nitroaniline	240 J
534-52-1	4,6-Dinitro-2-Methylphenol	240 J
86-30-6	N-Nitrosodiphenylamine (1)	490 U
101-55-3	4-Bromophenyl-phenylether	490 U
118-74-1	Hexachlorobenzene	490 U
87-86-5	Pentachlorophenol	240 J
85-01-8	Phenanthrene	190 J
120-12-7	Anthracene	490 U
84-74-2	Di-n-Butylphthalate	490 U
206-44-0	Fluoranthene	190 J
129-00-0	Pyrene	200 J
85-68-7	Butylbenzylphthalate	490 U
91-94-1	3,3'-Dichlorobenzidine	980 U
56-55-3	Benz(a)Anthracene	200 J
117-81-7	bis(2-Ethylhexyl)Phthalate	240 J
218-01-9	Chrysene	320 J
117-84-0	Di-n-Octyl Phthalate	320 J
205-99-2	Benz(b)Fluoranthene	490 U
207-08-9	Benz(k)Fluoranthene	430 J
50-32-8	Benz(a)Pyrene	310 J
193-39-5	Indeno(1,2,3-cd)Pyrene	290 J
53-70-3	Dibenz(h)Anthracene	140 J
191-24-2	Benz(g,h,i)Perylene	290 J

(1) Cannot be separated from diphenylamine

305002



**Organics Analysis Data Sheet**  
(Page 2)

BK-272  
HEAT # 878

**Semivolatile Compounds**

Concentration: Low Medium (Circle One)  
Date Extracted/Prepared: 3-14-88  
Date Analyzed: 3-24-88  
Conc./Dil Factor: 1  
Percent Moisture (Decanted): 99%

GPC Cleanup ☐ Yes ☒ No  
Separatory Funnel Extraction ☐ Yes  
Continuous Liquid - Liquid Extraction ☐ Yes

CAS Number		ug/l or ug/Kg (Circle One)
108-95-2	Phenol	370 U
111-44-4	bis(2-Chloroethyl)Ether	370 U
95-57-8	2-Chlorophenol	370 U
541-73-1	1,3-Dichlorobenzene	370 U
106-46-7	1,4-Dichlorobenzene	370 U
100-51-6	Benzyl Alcohol	370 U
95-50-1	1,2-Dichlorobenzene	370 U
95-48-7	2-Methylphenol	370 U
39638-32-9	bis(2-chloroisopropyl)Ether	370 U
106-44-5	4-Methylphenol	370 U
621-64-7	N-Nitroso-Di-n-Propylamine	370 U
67-72-1	Hexachloroethane	370 U
98-95-3	Nitrobenzene	370 U
78-59-1	Isophorone	370 U
88-75-5	2,4-Dinitrophenol	370 U
105-67-9	2,4-Dimethylphenol	370 U
65-85-0	Benzoic Acid	53 J
111-91-1	bis(2-Chloroethoxy)Methane	370 U
120-83-2	2,4-Dichlorophenol	370 U
120-82-1	1,2,4-Trichlorobenzene	370 U
91-20-3	Naphthalene	370 U
106-47-8	4-Chloroaniline	370 U
87-68-3	Hexachlorobutadiene	370 U
59-50-7	4-Chloro-3-Methylphenol	370 U
91-57-6	2-Methylnaphthalene	370 U
77-47-4	Hexachlorocyclopentadiene	370 U
59-06-2	2,4,6-Trichlorophenol	370 U
95-95-4	2,4,5-Trichlorophenol	1800 U
91-58-7	2-Chloronaphthalene	370 U
88-74-4	2-Nitroaniline	1800 U
131-11-3	Dimethyl Phthalate	370 U
208-96-8	Acenaphthylene	370 U
99-09-2	3-Nitroaniline	1800 U

CAS Number		ug/l or ug/Kg (Circle One)
83-32-9	Acenaphthene	370 U
51-28-5	2,4-Dinitrophenol	1800 U
100-02-7	4-Nitrophenol	1800 U
132-64-9	Dibenzofuran	370 U
121-14-2	2,4-Dinitrotoluene	370 U
606-20-2	2,6-Dinitrotoluene	370 U
84-66-2	Diethylphthalate	370 U
7005-72-3	4-Chlorophenyl-phenylether	370 U
86-73-7	Fluorene	370 U
100-01-6	4-Nitroaniline	1800 U
534-52-1	4,6-Dinitro-2-Methylphenol	1800 U
86-30-6	N-Nitrosodiphenylamine (1)	370 U
101-55-3	4-Bromophenyl-phenylether	370 U
118-74-1	Hexachlorobenzene	370 U
87-86-5	Pentachlorophenol	1800 U
85-01-8	Phenanthrene	74 J
120-12-7	Anthracene	370 U
84-74-2	Di-n-Butylphthalate	370 U
206-44-0	Fluoranthene	150 J
129-00-0	Pyrene	140 J
85-68-7	Butylbenzylphthalate	370 U
91-94-1	3,3'-Dichlorobenzidine	740 U
56-55-3	Benz(a)Anthracene	86 J
117-81-7	bis(2-Ethylhexyl)Phthalate	200 J
218-01-9	Chrysene	150 J
117-84-0	Di-n-Octyl Phthalate	370 U
205-99-2	Benzo(b)Fluoranthene	370 J
207-08-9	Benzo(k)Fluoranthene	370 U
50-32-8	Benzo(a)Pyrene	140 J
193-39-5	Indeno(1,2,3-cd)Pyrene	140 J
53-70-3	Dibenz(a,h)Anthracene	370 U
191-24-2	Benzo(g,h,i)Perylene	150 J

(1) Cannot be separated from diphenylamine

306002

Organics Analysis Data Sheet  
(Page 2)

Semivolatile Compounds

Concentration: Low Medium (Circle One)

Extracted/Prepared 3-14-88

Analyzed 3-17-88

Conc/Dil Factor: 1

Percent Moisture (Decanted) 10%

GPC Cleanup ☐ Yes ☒ No

Separatory Funnel Extraction ☐ Yes

Continuous Liquid - Liquid Extraction ☐ Yes

CAS Number		ug/l or ug/Kg (Circle One)
08 95-2	Phenol	380 u
1-44-4	bis(2-Chloroethyl)Ether	380 u
5-57-8	2-Chlorophenol	380 u
41-73-1	1,3-Dichlorobenzene	380 u
96-46-7	1,4-Dichlorobenzene	380 u
90-51-6	Benzyl Alcohol	380 u
95-50-1	1,2-Dichlorobenzene	380 u
5-48-7	2-Methylphenol	380 u
9638-32-9	bis(2-chloroisopropyl)Ether	380 u
106-44-5	4-Methylphenol	380 u
21-64-7	N-Nitroso-Di-n-Propylamine	380 u
7-72-1	Hexachloroethane	380 u
98 95-3	Nitrobenzene	380 u
78-59-1	Isophorone	380 u
98-75-5	2-Nitrophenol	380 u
105-67-9	2,4-Dimethylphenol	380 u
55-85-0	Benzoic Acid	50 J
111-91-1	bis(2-Chloroethoxy)Methane	380 u
120-83-2	2,4-Dichlorophenol	380 u
120-82-1	1,2,4-Trichlorobenzene	380 u
91-20-3	Naphthalene	380 u
106-47-8	4-Chloroaniline	380 u
87-68-3	Hexachlorobutadiene	380 u
59-50-7	4-Chloro-3-Methylphenol	380 u
91-57-6	2-Methylnaphthalene	380 u
77-47-4	Hexachlorocyclopentadiene	380 u
88-06-2	2,4,6-Trichlorophenol	380 u
95-95-4	2,4,5-Trichlorophenol	190 J
91-58-7	2-Chloronaphthalene	380 u
88-74-4	2-Nitroaniline	1900 u
131-11-3	Dimethyl Phthalate	380 u
208 96-8	Acenaphthylene	380 u
99-09-2	3-Nitroaniline	1900 u

CAS Number		ug/l or ug/Kg (Circle One)
83-32-9	Acenaphthene	380 u
51-28-5	2,4-Dinitrophenol	1900 u
100-02-7	4-Nitrophenol	1900 u
132-64-9	Dibenzofuran	380 u
121-14-2	2,4-Dinitrotoluene	380 u
606-20-2	2,6-Dinitrotoluene	380 u
84-66-2	Diethylphthalate	380 u
7005-72-3	4-Chlorophenyl-phenylether	380 u
86-73-7	Fluorene	380 u
100-01-6	4-Nitroaniline	1900 u
534-52-1	4,6-Dinitro-2-Methylphenol	1900 u
86-30-6	N-Nitrosodiphenylamine (1)	380 u
101-55-3	4-Bromophenyl-phenylether	380 u
118-74-1	Hexachlorobenzene	380 u
87-86-5	Pentachlorophenol	1900 u
85-01-8	Phenanthrene	110 J
120-12-7	Anthracene	380 u
84-74-2	Di-n-Butylphthalate	380 u
206-44-0	Fluoranthene	140 J
129-00-0	Pyrene	140 J
85-68-7	Butylbenzylphthalate	380 u
91-94-1	3,3-Dichlorobenzidine	760 u
56-55-3	Benzolanthracene	110 J
117-81-7	bis(2-Ethylhexyl)Phthalate	150 J
218-01-9	Chrysene	150 J
117-84-0	Di-n-Octyl Phthalate	280 J
205-99-2	Benzobifluoranthene	280 J
207-08-9	Benzokifluoranthene	380 u
50-32-8	BenzolPyrene	130 J
193-39-5	Indeno[1,2,3-cd]Pyrene	120 J
53-70-3	Dibenz[ah]Anthracene	380 J
191-24-2	Benzol[ghi]Perylene	100 J

(1)-Cannot be separated from diphenylamine

Name Hittman Ebasco Assoc. Inc.  
9116

Sample Number  
BR-274

Organics Analysis Data Sheet  
(Page 2)

HEAT #880  
>BC033

Semivolatile Compounds

Concentration: Low Medium (Circle One)  
Date Extracted/Prepared 3-14-88  
Date Analyzed 3-17-88  
Conc/Dil Factor: 1  
Percent Moisture (Decanted) 1390

GPC Cleanup ☐ Yes ☒ No

Separatory Funnel Extraction ☐ Yes

Continuous Liquid-Liquid Extraction ☐ Yes

CAS Number		ug/l or ug/Kg (Circle One)
108-95-2	Phenol	390 U
111-44-4	bis(2-Chloroethyl)Ether	390 U
95-57-8	2-Chlorophenol	390 U
541-73-1	1,3-Dichlorobenzene	390 U
106-46-7	1,4-Dichlorobenzene	390 U
100-51-6	Benzyl Alcohol	390 U
95-50-1	1,2-Dichlorobenzene	390 U
95-48-7	2-Methylphenol	390 U
39638-32-9	bis(2-chloroisopropyl)Ether	390 U
106-44-5	4-Methylphenol	390 U
621-64-7	N-Nitroso-Di-n-Propylamine	390 U
67-72-1	Hexachloroethane	390 U
98-95-3	Nitrobenzene	390 U
78-59-1	Isophorone	390 U
88-75-5	2-Nitrophenol	390 U
105-67-9	2,4-Dimethylphenol	390 U
65-85-0	Benzoic Acid	1900 U
111-91-1	bis(2-Chloroethoxy)Methane	390 U
120-83-2	2,4-Dichlorophenol	390 U
120-82-1	1,2,4-Trichlorobenzene	390 U
91-20-3	Naphthalene	390 U
106-47-8	4-Chloroaniline	390 U
87-68-3	Hexachlorobutadiene	390 U
59-50-7	4-Chloro-3-Methylphenol	390 U
91-57-6	2-Methylnaphthalene	220 J
77-47-4	Hexachlorocyclopentadiene	390 U
88-06-2	2,4,6-Trichlorophenol	390 U
95-95-4	2,4,5-Trichlorophenol	1900 U
91-58-7	2-Chloronaphthalene	390 U
88-74-4	2-Nitroaniline	1900 U
131-11-3	Dimethyl Phthalate	390 U
208-96-8	Acenaphthylene	390 U
99-09-2	3-Nitroaniline	1900 U

CAS Number		ug/l or ug/Kg (Circle One)
83-32-9	Acenaphthene	390 U
51-28-5	2,4-Dinitrophenol	1900 U
100-02-7	4-Nitrophenol	1900 U
132-64-9	Dibenzofuran	390 U
121-14-2	2,4-Dinitrotoluene	390 U
606-20-2	2,6-Dinitrotoluene	390 U
84-66-2	Diethylphthalate	390 U
7005-72-3	4-Chlorophenyl-phenylether	390 U
86-73-7	Fluorene	390 U
100-01-6	4-Nitroaniline	1900 U
534-52-1	4,6-Dinitro-2-Methylphenol	1900 U
86-30-6	N-Nitrosodiphenylamine (1)	390 U
101-55-3	4-Bromophenyl-phenylether	390 U
118-74-1	Hexachlorobenzene	390 U
87-86-5	Pentachlorophenol	1900 U
85-01-8	Phenanthrene	140 J
120-12-7	Anthracene	390 U
84-74-2	Di-n-Butylphthalate	390 U
206-44-0	Fluoranthene	51 J
129-00-0	Pyrene	43 J
85-68-7	Butylbenzylphthalate	100 J
91-94-1	3,3-Dichlorobenzidine	780 U
56-55-3	Benzo(a)Anthracene	390 U
117-81-7	bis(2-Ethylhexyl)Phthalate	440
218-01-9	Chrysene	390 U
117-84-0	Di-n-Octyl Phthalate	140 J
205-99-2	Benzo(b)Fluoranthene	390 U
207-08-9	Benzo(k)Fluoranthene	390 U
50-32-8	Benzo(a)Pyrene	390 U
193-39-5	Indeno(1,2,3-cd)Pyrene	80 J
53-70-3	Dibenzo(h,i)Anthracene	390 U
191-24-2	Benzo(g,h,i)Perylene	59 J

(1)-Cannot be separated from diphenylamine

308004

9116

Sample Number

BR-277(OL)

NEAT#

760006

Organics Analysis Data Sheet  
(Page 2)

## Semivolatile Compounds

Concentration: Low Medium (Circle One)Date Extracted/Prepared: 3-14-88Date Analyzed: 4-4-88Conc./Dil Factor: 10Percent Moisture (Decanted): 15%GPC Cleanup ☐ Yes ☒ NoSeparatory Funnel Extraction ☐ YesContinuous Liquid - Liquid Extraction ☐ YesCAS  
Numberug/l or ug/Kg  
(Circle One)

108-95-2	Phenol	3900 U
111-44-4	bis(2-Chloroethyl)Ether	3900 U
95-57-8	2-Chlorophenol	3900 U
541-73-1	1,3-Dichlorobenzene	3900 U
106-46-7	1,4-Dichlorobenzene	3900 U
100-51-6	Benzyl Alcohol	3900 U
95-50-1	1,2-Dichlorobenzene	3900 U
95-48-7	2-Methylphenol	3900 U
39638-32-9	bis(2-chloroisopropyl)Ether	3900 U
106-44-5	4-Methylphenol	3900 U
621-64-7	N-Nitroso-Di-n-Propylamine	3900 U
67-72-1	Hexachloroethane	3900 U
98-95-3	Nitrobenzene	3900 U
78-59-1	Isophorone	3900 U
88-75-5	2-Nitrophenol	3900 U
105-67-9	2,4-Dimethylphenol	3900 U
65-85-0	Benzoic Acid	19000 U
111-91-1	bis(2-Chloroethoxy)Methane	3900 U
120-83-2	2,4-Dichlorophenol	3900 U
120-82-1	1,2,4-Trichlorobenzene	3900 U
91-20-3	Naphthalene	1100 J
106-47-8	4-Chloroaniline	3900 U
87-68-3	Hexachlorobutadiene	3900 U
59-50-7	4-Chloro-3-Methylphenol	3900 U
91-57-6	2-Methylnaphthalene	480 J
77-47-4	Hexachlorocyclopentadiene	3900 U
88-06-2	2,4,6-Trichlorophenol	3900 U
95-95-4	2,4,5-Trichlorophenol	19000 U
91-58-7	2-Chloronaphthalene	3900 U
88-74-4	2-Nitroaniline	19000 U
131-11-3	Dimethyl Phthalate	3900 U
208-96-8	Acenaphthylene	3900 U
99-09-2	3-Nitroaniline	19000 U

CAS  
Numberug/l or ug/Kg  
(Circle One)

83-32-9	Acenaphthene	3900 U
51-28-5	2,4-Dinitrophenol	19000 U
100-02-7	4-Nitrophenol	19000 U
132-64-9	Dibenzofuran	3900 U
121-14-2	2,4-Dinitrotoluene	3900 U
806-20-2	2,6-Dinitrotoluene	3900 U
84-66-2	Diethylphthalate	3900 U
7005-72-3	4-Chlorophenyl-phenylether	3900 U
86-73-7	Fluorene	3900 U
100-01-6	4-Nitroaniline	19000 U
534-52-1	4,6-Dinitro-2-Methylphenol	19000 U
86-30-6	N-Nitrosodiphenylamine (1)	3900 U
101-55-3	4-Bromophenyl-phenylether	3900 U
118-74-1	Hexachlorobenzene	3900 U
87-86-5	Pentachlorophenol	19000 U
85-01-8	Phenanthrene	3900 U
120-12-7	Anthracene	3900 U
84-74-2	Di-n-Butylphthalate	3900 U
206-44-0	Fluoranthene	3900 U
129-00-0	Pyrene	3900 U
85-68-7	Butylbenzylphthalate	3900 U
91-84-1	3,3'-Dichlorobenzidine	17800 U
56-55-3	Benzo(a)Anthracene	3900 U
117-81-7	bis(2-Ethylhexyl)Phthalate	470 J
218-01-9	Chrysene	3900 U
117-84-0	Di-n-Octyl Phthalate	790 J
205-99-2	Benzo(b)Fluoranthene	530 J
207-08-9	Benzo(k)Fluoranthene	1010 J
50-32-8	Benzo(a)Pyrene	680 J
193-39-5	Indeno(1,2,3-cd)Pyrene	3900 U
53-70-3	Dibenz(h,i)Anthracene	3900 U
191-24-2	Benzo(g,h,i)Perylene	3900 U

(1) Cannot be separated from diphenylamine

301006

Story Name Hittman Ebasco Assoc. Inc.

Case No 9176

Sample Number  
BR-266  
HEAT 836  
76025

# Organics Analysis Data Sheet (Page 2)

## Semivolatile Compounds

Concentration: Low Medium (Circle One)  
Date Extracted/Prepared 3-11-88  
Date Analyzed 3-11-88  
Conc./Dil Factor: 1  
Percent Moisture (Decanted) NIA

GPC Cleanup ☐ Yes ☒ No  
Separatory Funnel Extraction ☒ Yes  
Continuous Liquid - Liquid Extraction ☐ Yes

CAS Number		ug/l or ug/Kg (Circle One)
106-95-2	Phenol	10 u
111-44-4	bis(2-Chloroethyl)Ether	10 u
95-57-8	2-Chlorophenol	10 u
541-73-1	1,3-Dichlorobenzene	10 u
106-46-7	1,4-Dichlorobenzene	10 u
100-51-6	Benzyl Alcohol	10 u
95-50-1	1,2-Dichlorobenzene	10 u
95-49-7	2-Methylphenol	10 u
39638-32-9	bis(2-chloroisopropyl)Ether	10 u
106-44-5	4-Methylphenol	10 u
621-64-7	N-Nitroso-Di-n-Propylamine	10 u
67-72-1	Hexachloroethane	10 u
98-95-3	Nitrobenzene	10 u
78-59-1	Isophorone	10 u
88-75-5	2-Nitrophenol	10 u
105-67-9	2,4-Dimethylphenol	10 u
65-85-0	Benzoic Acid	50 u
111-91-1	bis(2-Chloroethoxy)Methane	10 u
120-83-2	2,4-Dichlorophenol	10 u
120-82-1	1,2,4-Trichlorobenzene	10 u
91-20-3	Naphthalene	10 u
106-47-8	4-Chloroaniline	10 u
87-68-3	Hexachlorobutadiene	10 u
59-50-7	4-Chloro-3-Methylphenol	10 u
91-57-6	2-Methylnaphthalene	10 u
77-47-4	Hexachlorocyclopentadiene	10 u
88-06-2	2,4,6-Trichlorophenol	10 u
95-95-4	2,4,5-Trichlorophenol	50 u
91-58-7	2-Chloronaphthalene	10 u
88-74-4	2-Nitroaniline	50 u
131-11-3	Dimethyl Phthalate	10 u
208-96-8	Acenaphthylene	10 u
99-09-2	3-Nitroaniline	50 u

CAS Number		ug/l or ug/Kg (Circle One)
83-32-8	Acenaphthene	10 u
51-28-5	2,4-Dinitrophenol	50 u
100-02-7	4-Nitrophenol	50 u
132-64-9	Dibenzofuran	10 u
121-14-2	2,4-Dinitrotoluene	10 u
606-20-2	2,6-Dinitrotoluene	10 u
84-66-2	Diethylphthalate	10 u
7005-72-3	4-Chlorophenyl-phenylether	10 u
86-73-7	Fluorene	10 u
100-01-6	4-Nitroaniline	50 u
534-52-1	4,6-Dinitro-2-Methylphenol	50 u
86-30-8	N-Nitrosodiphenylamine (1)	10 u
101-55-3	4-Bromophenyl-phenylether	10 u
118-74-1	Hexachlorobenzene	10 u
87-86-5	Pentachlorophenol	50 u
85-01-8	Phenanthrene	10 u
120-12-7	Anthracene	10 u
94-74-2	Di-n-Butylphthalate	10 u
206-44-0	Fluoranthene	10 u
128-00-0	Pyrene	10 u
85-68-7	Butylbenzylphthalate	10 u
91-94-1	3,3'-Dichlorobenzidine	20 u
86-55-3	Benzofluoranthene	10 u
117-81-7	bis(2-Ethylhexyl)Phthalate	10 u
218-01-9	Chrysene	10 u
117-84-0	Di-n-Octyl Phthalate	10 u
205-99-2	Benzofluoranthene	10 u
207-08-9	Benzofluoranthene	10 u
30-32-8	Benzofluoranthene	10 u
193-39-5	Indeno(1,2,3-cd)Pyrene	10 u
53-70-3	Dibenzofluoranthene	10 u
191-24-2	Benzofluoranthene	10 u

(1)-Cannot be separated from diphenylamine

Company Name Hittman Ebasco Associates Inc.  
No 9116

Sample Number  
BR268

Organics Analysis Data Sheet  
(Page 3)

Pesticide/PCBs

Concentration Low Medium (Circle One)

GPC Cleanup Yes X No

Date Extracted/Prepared 3/14/88

Separatory Funnel Extraction Yes

Date Analyzed 3/18/88

Continuous Liquid-Liquid Extraction Yes

Conc/Dil Factor 1.00

Percent Moisture (decanted) 11

CAS  
Number

ug/L or ug/Kg  
(Circle One)

319-84-67	Alpha-BHC	8.9 U
319-85-7	Beta-BHC	8.9 U
319-86-8	Delta-BHC	8.9 U
58-89-9	Gamma-BHC(Lindane)	8.9 U
76-44-8	Heptachlor	8.9 U
309-00-2	Aldrin	8.9 U
1024-57-3	Heptachlor Epoxide	8.9 U
959-98-8	Endosulfan I	8.9 U
60-57-1	Dieldrin	18 U
72-55-9	4'-4'-DDE	18 U
72-20-8	Endrin	18 U
33213-65-9	Endosulfan II	18 U
72-54-8	4'-4'-DDD	18 U
1031-07-8	Endosulfan Sulfate	18 U
50-29-3	4'-4'-DDT	150 U
72-43-5	Methoxychlor	89 U
53494-70-5	Endrin Ketone	18 U
57-74-9	Chlordane	89 U
8001-35-2	Toxaphene	180 U
12674-11-2	Aroclor - 1016	89 U
11104-28-2	Aroclor - 1221	89 U
11141-16-5	Aroclor - 1232	89 U
53469-21-9	Aroclor - 1242	89 U
12672-29-6	Aroclor - 1248	89 U
11097-69-1	Aroclor - 1254	180 U
11096-82-5	Aroclor - 1260	180 U

VI = Volume of extract injected (ul)  
Vs = Volume of water extracted (ml)  
Ws = Weight of sample extracted (g)  
Vt = Volume of total extract (ul)

or Ws 30.07 Vt 2000.00 VI 1.00

Form 1

2000

2WS  
302003

Name Hittman Ebasco Associates Inc.  
9116

Sample Number  
BR269

Organics Analysis Data Sheet  
(Page 3)

Concentration Low Medium (Circle One)

Pesticide/PCBs

GPC Cleanup Yes X No

Date Extracted/Prepared 3/14/88

Separatory Funnel Extraction Yes

Date Analyzed 3/18/88

Continuous Liquid-Liquid Extraction Yes

Conc/Dil Factor 1.00

Percent Moisture (decanted) 15

CAS Number		ug/L or ug/Kg (Circle One)
319-84-67	Alpha-BHC	9.2 U
319-85-7	Beta-BHC	9.2 U
319-86-8	Delta-BHC	9.2 U
58-89-9	Gamma-BHC(Lindane)	9.2 U
76-44-8	Heptachlor	9.2 U
309-00-2	Aldrin	9.2 U
1024-57-3	Heptachlor Epoxide	9.2 U
959-98-8	Endosulfan I	9.2 U
60-57-1	Dieldrin	18 U
72-55-9	4'-4'-DDE	18 U
72-20-8	Endrin	18 U
33213-65-9	Endosulfan II	18 U
72-54-8	4'-4'-DDD	18 U
1031-07-8	Endosulfan Sulfate	18 U
50-29-3	4'-4'-DDT	18 U
72-43-5	Methoxychlor	92 U
53494-70-5	Endrin Ketone	18 U
57-74-9	Chlordane	200 A
8001-35-2	Toxaphene	180 U
12674-11-2	Aroclor - 1016	92 U
11104-28-2	Aroclor - 1221	92 U
11141-16-5	Aroclor - 1232	92 U
53469-21-9	Aroclor - 1242	92 U
12672-29-6	Aroclor - 1248	92 U
11097-69-1	Aroclor - 1254	180 U
11096-82-5	Aroclor - 1260	<del>750</del> 1100

A = sum of the  
alpha, gamma  
chlordane

Vi = Volume of extract injected (ul)  
Vs = Volume of water extracted (ml)  
Ws = Weight of sample extracted (g)  
Vt = Volume of total extract (ul)

Vs \_\_\_\_\_ or Ws 30.48 Vt 2000.00 Vi \_\_\_\_\_ 1.00 \_\_\_\_\_

Form 1

303003

duB

Name Hittman Ebasco Associates Inc.  
9116

Sample Number  
BR270

Organics Analysis Data Sheet  
(Page 3)

Pesticide/PCBs

Concentration Low Medium (Circle One)

GPC Cleanup Yes X No

Date Extracted/Prepared 3/14/88

Separatory Funnel Extraction Yes

Date Analyzed 3/18/88

Continuous Liquid-Liquid Extraction Yes

Inc/Dil Factor 1.00

Percent Moisture (decanted) 22

CAS  
Number ug/L or ug/Kg  
(Circle One)

319-84-67	Alpha-BHC	9.8 U
319-85-7	Beta-BHC	9.8 U
319-86-8	Delta-BHC	9.8 U
58-89-9	Gamma-BHC(Lindane)	9.8 U
76-44-8	Heptachlor	9.8 U
309-00-2	Aldrin	9.8 U
1024-57-3	Heptachlor Epoxide	9.8 U
959-98-8	Endosulfan I	9.8 U
60-57-1	Dieldrin	20 U
72-55-9	4'4'-DDE	20 U
72-20-8	Endrin	20 U
33213-65-9	Endosulfan II	20 U
72-54-8	4'4'-DDD	20 U
1031-07-8	Endosulfan Sulfate	20 U
50-29-3	4'4'-DDT	20 U
72-43-5	Methoxychlor	98 U
53494-70-5	Endrin Ketone	20 U
57-74-9	Chlordane	260 <u>A</u>
8001-35-2	Toxaphene	200 U
12674-11-2	Aroclor - 1016	98 U
11104-28-2	Aroclor - 1221	98 U
11141-16-5	Aroclor - 1232	98 U
53469-21-9	Aroclor - 1242	98 U
12672-29-6	Aroclor - 1248	98 U
11097-69-1	Aroclor - 1254	200 U
11096-82-5	Aroclor - 1260	<del>1000</del> <u>1300</u>

Vi = Volume of extract injected (ul)  
Vs = Volume of water extracted (ml)  
Ws = Weight of sample extracted (g)  
Vt = Volume of total extract (ul)

1/s \_\_\_\_\_ or Ws 31.40 Vt 2000.00 Vi \_\_\_\_\_ 1.00 \_\_\_\_\_

Form 1

304003

*hwt*



Company Name Hittman Ebasco Associates Inc.  
9116

Sample Number  
BR271

Organics Analysis Data Sheet  
(Page 3)

Pesticide/PCBs

GPC Cleanup Yes X No

Separatory Funnel Extraction Yes

Continuous Liquid-Liquid Extraction Yes

Concentration Low Medium (Circle One)

Date Extracted/Prepared 3/14/88

Date Analyzed 3/18/88

Conc/Dil Factor 1.00

Percent Moisture (decanted) 31

ug/L or ug/Kg  
(Circle One)

CAS  
Number

319-84-67	Alpha-BHC	11 U
319-85-7	Beta-BHC	11 U
319-86-8	Delta-BHC	11 U
58-89-9	Gamma-BHC(Lindane)	11 U
76-44-8	Heptachlor	11 U
309-00-2	Aldrin	11 U
1024-57-3	Heptachlor Epoxide	11 U
959-98-8	Endosulfan I	23 U
60-57-1	Dieldrin	24
72-55-9	4'4'-DDE	23 U
72-20-8	Endrin	23 U
33213-65-9	Endosulfan II	17 U
72-54-8	4'4'-DDD	23 U
1031-07-8	Endosulfan Sulfate	100
50-29-3	4'4'-DDT	110 U
72-43-5	Methoxychlor	23 U
53494-70-5	Endrin Ketone	110 U
57-74-9	Chlordane	230 U
8001-35-2	Toxaphene	110 U
12674-11-2	Aroclor - 1016	110 U
11104-28-2	Aroclor - 1221	110 U
11141-16-5	Aroclor - 1232	110 U
53469-21-9	Aroclor - 1242	110 U
12672-29-6	Aroclor - 1248	230 U
11097-69-1	Aroclor - 1254	230 U
11096-82-5	Aroclor - 1260	230 U

Vi = Volume of extract injected (ul)  
Vs = Volume of water extracted (ml)  
Ws = Weight of sample extracted (g)  
Vt = Volume of total extract (ul)

Vs \_\_\_\_\_ or Ws 30.73 Vt \_\_\_\_\_ 2000.00 Vi \_\_\_\_\_ 1.00 \_\_\_\_\_

Form 1

305003

AWS

Organics Analysis Data Sheet  
 (Page 3)

ation Low Medium (Circle One)

Pesticide/PCBs

GPC Cleanup \_\_\_\_\_ Yes X No

Extracted/Prepared \_\_\_\_\_ 3/14/88

Separatory Funnel Extraction \_\_\_\_\_ Yes

ate Analyzed \_\_\_\_\_ 3/18/88

Continuous Liquid-Liquid Extraction \_\_\_\_\_ Yes

Conc/Dil Factor \_\_\_\_\_ 1.00

ercent Moisture (decanted) \_\_\_\_\_ 9

CAS  
 Number

ug/L or ug/Kg  
 (Circle One)

319-84-67	Alpha-BHC	8.5 U
319-85-7	Beta-BHC	8.5 U
319-86-8	Delta-BHC	8.5 U
58-89-9	Gamma-BHC(Lindane)	8.5 U
76-44-8	Heptachlor	8.5 U
309-00-2	Aldrin	8.5 U
1024-57-3	Heptachlor Epoxide	8.5 U
959-98-8	Endosulfan I	8.5 U
60-57-1	Dieldrin	17 U
72-55-9	4'4'-DDE	17 U
72-20-8	Endrin	17 U
33213-65-9	Endosulfan II	17 U
72-54-8	4'4'-DDD	17 U
1031-07-8	Endosulfan Sulfate	17 U
50-29-3	4'4'-DDT	<del>20</del> 57
72-43-5	Methoxychlor	85 U
53494-70-5	Endrin Ketone	17 U
57-74-9	Chlordane	85 U
8001-35-2	Toxaphene	170 U
12674-11-2	Aroclor - 1016	85 U
11104-28-2	Aroclor - 1221	85 U
11141-16-5	Aroclor - 1232	85 U
53469-21-9	Aroclor - 1242	85 U
12672-29-6	Aroclor - 1248	85 U
11097-69-1	Aroclor - 1254	210
11096-82-5	Aroclor - 1260	170 U

Vi = Volume of extract injected (ul)  
 Vs = Volume of water extracted (ml)  
 Ws = Weight of sample extracted (g)  
 Vt = Volume of total extract (ul)

or Ws 31.03 Vt 2000.00 Vi 1.00

Form 1

306003

*dwB*

Organics Analysis Data Sheet  
(Page 3)

Pesticide/PCBs

Concentration Low Medium (Circle One)

GPC Cleanup Yes X No

Sample Extracted/Prepared 3/14/88

Separatory Funnel Extraction Yes

Sample Analyzed 3/18/88

Continuous Liquid-Liquid Extraction Yes

Conc/Dil Factor 1.00

Percent Moisture (decanted) 10

CAS Number	ug/L or <u>ug/Kg</u> (Circle One)
319-84-67	Alpha-BHC 8.7 U
319-85-7	Beta-BHC 8.7 U
319-86-8	Delta-BHC 8.7 U
58-89-9	Gamma-BHC(Lindane) 8.7 U
76-44-8	Heptachlor 8.7 U
309-00-2	Aldrin 8.7 U
1024-57-3	Heptachlor Epoxide 8.7 U
959-98-8	Endosulfan I 8.7 U
60-57-1	Dieldrin 17 U
72-55-9	4'4'-DDE 29
72-20-8	Endrin 17 U
33213-65-9	Endosulfan II 17 U
72-54-8	4'4'-DDD 17 U
1031-07-8	Endosulfan Sulfate 17 U
50-29-3	4'4'-DDT 120
72-43-5	Methoxychlor 87 U
53494-70-5	Endrin Ketone 17 U
57-74-9	Chlordane 87 U
8001-35-2	Toxaphene 170 U
12674-11-2	Aroclor - 1016 87 U
11104-28-2	Aroclor - 1221 87 U
11141-16-5	Aroclor - 1232 87 U
53469-21-9	Aroclor - 1242 87 U
12672-29-6	Aroclor - 1248 87 U
11097-69-1	Aroclor - 1254 170 U
11096-82-5	Aroclor - 1260 170 U

Vi = Volume of extract injected (ul)  
Vs = Volume of water extracted (ml)  
Ws = Weight of sample extracted (g)  
Vt = Volume of total extract (ul)

or Ws 30.67 Vt 2000.00 Vi 1.00

Form 1

307003

*hws*

Hittman Ebasco Associates Inc.  
9116

Sample Number  
BR274

Organics Analysis Data Sheet  
(Page 3)

Pesticide/PCBs

Extraction Low Medium (Circle One)

GPC Cleanup        Yes X No

Extracted/Prepared        3/14/88

Separatory Funnel Extraction        Yes

Analyzed        3/18/88

Continuous Liquid-Liquid Extraction        Yes

Oil Factor        10.00

Moisture (decanted)        13

CAS  
Number

ug/L or ug/Kg  
(Circle One)

319-84-67	Alpha-BHC	89 U
319-85-7	Beta-BHC	89 U
319-86-8	Delta-BHC	89 U
58-89-9	Gamma-BHC(Lindane)	89 U
76-44-8	Heptachlor	89 U
309-00-2	Aldrin	89 U
1024-57-3	Heptachlor Epoxide	89 U
959-98-8	Endosulfan I	89 U
60-57-1	Dieldrin	180 U
72-55-9	4'4'-DDE	180 U
72-20-8	Endrin	180 U
33213-65-9	Endosulfan II	180 U
72-54-8	4'4'-DDD	180 U
1031-07-8	Endosulfan Sulfate	180 U
50-29-3	4'4'-DDT	520 <u>ug/Kg</u>
72-43-5	Methoxychlor	890 U
53494-70-5	Endrin Ketone	180 U
57-74-9	Chlordane	890 U
8001-35-2	Toxaphene	1800 U
12674-11-2	Aroclor - 1016	890 U
11104-28-2	Aroclor - 1221	890 U
11141-16-5	Aroclor - 1232	890 U
53469-21-9	Aroclor - 1242	890 U
12672-29-6	Aroclor - 1248	890 U
11097-69-1	Aroclor - 1254	1800 U
11096-82-5	Aroclor - 1260	1800 U

Vi = Volume of extract injected (ul)  
Vs = Volume of water extracted (ml)  
Ws = Weight of sample extracted (g)  
Vt = Volume of total extract (ul)

or Ws        31.14        Vt        2000.00        Vi        1.00       

Form 1

LWS

2080009

Organics Analysis Data Sheet  
(Page 3)

Pesticide/PCBs

Extraction Low Medium (Circle One)

GPC Cleanup Yes X No

Extracted/Prepared 3/14/88

Separatory Funnel Extraction Yes

Analyzed 3/18/88

Continuous Liquid-Liquid Extraction Yes

Oil Factor 10.00

Moisture (decanted) 15

CAS  
Number

ug/L or ug/Kg  
(Circle One)

319-84-67	Alpha-BHC	89 U <u>J</u>
319-85-7	Beta-BHC	89 U
319-86-8	Delta-BHC	89 U
58-89-9	Gamma-BHC(Lindane)	89 U
76-44-8	Heptachlor	89 U
309-00-2	Aldrin	89 U
1024-57-3	Heptachlor Epoxide	89 U
959-98-8	Endosulfan I	89 U
60-57-1	Dieldrin	180 U <u>J</u>
72-55-9	4'-DDT	550 <u>J</u>
72-20-8	Endrin	180 U <u>J</u>
33213-65-9	Endosulfan II	180 U <u>J</u>
72-54-8	4'-DDD	450 <u>J</u>
1031-07-8	Endosulfan Sulfate	180 U <u>J</u>
50-29-3	4'-DDT	1500 <u>J</u>
72-43-5	Methoxychlor	890 U <u>J</u>
53494-70-5	Endrin Ketone	180 U
57-74-9	Chlordane	890 U
8001-35-2	Toxaphene	1800 U
12674-11-2	Aroclor - 1016	890 U
11104-28-2	Aroclor - 1221	890 U
11141-16-5	Aroclor - 1232	890 U
53469-21-9	Aroclor - 1242	890 U
12672-29-6	Aroclor - 1248	890 U
11097-69-1	Aroclor - 1254	1800 U
11096-82-5	Aroclor - 1260	1800 U <u>V</u>

VI = Volume of extract injected (ul)  
Vs = Volume of water extracted (ml)  
Ws = Weight of sample extracted (g)  
Vt = Volume of total extract (ul)

or Ws 31.81 Vt 2000.00 VI 1.00

Form 1

*pub*  
301007

Story Name Hittman Ebasco Associates Inc.  
Case No 9116

Sample Number  
BR266

Organics Analysis Data Sheet  
(Page 3)

Pesticide/PCBs

Concentration Low Medium (Circle One)

GPC Cleanup Yes X No

Date Extracted/Prepared 3/10/88

Separatory Funnel Extraction X Yes

Date Analyzed 3/17/88

Continuous Liquid-Liquid Extraction Yes

Conc/Dil Factor 1.00

Percent Moisture (decanted) \_\_\_\_\_

CAS  
Number

ug/l or ug/Kg  
(Circle One)

319-84-67	Alpha-BHC	0.05 U
319-85-7	Beta-BHC	0.05 U
319-86-8	Delta-BHC	0.05 U
58-89-9	Gamma-BHC(Lindane)	0.05 U
76-44-8	Heptachlor	0.05 U
309-00-2	Aldrin	0.05 U
1024-57-3	Heptachlor Epoxide	0.05 U
959-98-8	Endosulfan I	0.05 U
60-57-1	Dieldrin	0.1 U
72-55-9	4'4'-DDE	0.1 U
72-20-8	Endrin	0.1 U
33213-65-9	Endosulfan II	0.1 U
72-54-8	4'4'-DDD	0.1 U
1031-07-8	Endosulfan Sulfate	0.1 U
50-29-3	4'4'-DDT	0.1 U
72-43-5	Methoxychlor	0.5 U
53494-70-5	Endrin Ketone	0.1 U
57-74-9	Chlordane	0.5 U
8001-35-2	Toxaphene	1.0 U
12674-11-2	Aroclor - 1016	0.5 U
11104-28-2	Aroclor - 1221	0.5 U
11141-16-5	Aroclor - 1232	0.5 U
53469-21-9	Aroclor - 1242	0.5 U
12672-29-6	Aroclor - 1248	0.5 U
11097-69-1	Aroclor - 1254	1.0 U
11096-82-5	Aroclor - 1260	1.0 U

Vf = Volume of extract injected (ul)

Vs = Volume of water extracted (ml)

Ws = Weight of sample extracted (g)

Vt = Volume of total extract (ul)

Vs 1000.00 or Ws 10000.00 Vf 1.00

Title: Evaluation of Metals Data for the  
Contract Laboratory Program  
Appendix A.2: Data Acceptability Narrative

Date: Feb. 1988  
Number: HW-2  
Revision: 7

Unorganics

Case# 9116 Site John Hassell Matrix: Soil 8  
Lab CSMRT Water 1  
Other -

A.2.1 Are all data of acceptable quality? Yes        No ✓

If no, list exceptions with reason(s) for rejection or qualification as estimated value (J).

i) Spike Sample analysis is designed to provide information on the effect of sample matrix on the digestion procedure and instrument performance.

The following analytes were qualified as estimated (labeled with 'J') because spike recoveries are less than 75 %.

Sb, As, Cr → All Soil Samples.

# STANDARD OPERATING PROCEDURE

Page 22 of 27

Title: Evaluation of Metals Data for the  
Contract Laboratory Program  
Appendix A.2: Data Acceptability Narrative

Date: Feb. 1988

Number: HW-2

Revision: 7

A.2.1 (continuation)

### A.2.2 Contract Problems/Non-compliance

**MMB Reviewer:**

**Signature**

**Date:** \_\_\_\_\_

**Contractor Reviewer:**

**Signature**

**Date:**

Verified by: \_\_\_\_\_

**Date:**

Henry Sherth



000002

ANALYTICA INCORPORATED  
CASE NARRATIVE

LGN: 4278  
Case: 916

Page: 1 of 1  
Date: 3-23-88

Comments: WHEN SAMPLES WERE RECEIVED AT LAB, THE COOLER  
CONTAINED NO TANK ICE.  
PER MS DIANE CALTER OF SMD, LAB ANALYZED SAMPLES.

Lab Manager: *PAHatt*

000003

Page 1 of 8

## Form I

U. S. EPA Contract Laboratory Program  
 Sample Management Office  
 P. O. Box 818 - Alexandria, VA 22313  
 703/557-2490 FTS: 8-557-2490

EPA Sample No.

MBP 664

Date 3-28-88

## INORGANIC ANALYSIS DATA SHEET

LAB NAME ANALYTICA INCORPORATEDCASE NO. 9116SOW NO. 785Lab Receipt Date 3-11-88LAB SAMPLE ID. NO. —QC REPORT NO. 4279

## Elements Identified and Measured

Concentration: Low XMedium —Matrix: Water — Soil XSludge — Other —

ug/L or mg/kg dry weight (Circle One)

1. Aluminum	2360	P	13. Magnesium	[881]	P
2. Antimony	134 JN	F	14. Manganese	78	P
3. Arsenic	2.24 JN	F	15. Mercury	0.114	CV
4. Barium	[19]	P	16. Nickel	48	P
5. Beryllium	0.224	P	17. Potassium	[227]	P
6. Cadmium	1.14	P	18. Selenium	1.14	F
7. Calcium	1880	P	19. Silver	4.0	P
8. Chromium	64 JN	P	20. Sodium	4364	P
9. Cobalt	[2.5]	P	21. Thallium	2.24	F
10. Copper	33	P	22. Vanadium	[7.6]	P
11. Iron	5080	P	23. Zinc	167	P
12. Lead	92	S F	Percent Solids (%)	89	

Cyanide 0.564

Footnotes: For reporting results to EPA, standard result qualifiers are used as defined on Cover Page. Additional flags or footnotes explaining results are encouraged. Definition of such flags must be explicit and contained on Cover Page, however.

Comments: SAMPLE DESCRIPTION: SOIL, BROWN, MEDIUMPb DILUTED 20X TO MEET LINEAR RANGE.

Lab Manager



IFB Amend. One

000004

Page 2 of 8

## Form I

U. S. EPA Contract Laboratory Program  
 Sample Management Office  
 P. O. Box 818 - Alexandria, VA 22313  
 703/557-2490 FTS: 8-557-2490

EPA Sample No.

MBP 665

Date 3-28-88

## INORGANIC ANALYSIS DATA SHEET

LAB NAME ANALYTICA INCORPORATEDCASE NO. 9116SOW NO. 785Lab Receipt Date 3-11-88LAB SAMPLE ID. NO. —QC REPORT NO. 4279

## Elements Identified and Measured

Concentration: Low X Medium —Matrix: Water — Soil X Sludge — Other —

ug/L or (mg/kg dry weight) (Circle One)

1. Aluminum	<u>3570</u>	P	13. Magnesium	<u>[855]</u>	P
2. Antimony	<u>14U J N</u>	F	14. Manganese	<u>51</u>	P
3. Arsenic	<u>2.7 J S N</u>	F	15. Mercury	<u>0.12 U</u>	CV
4. Barium	<u>[7.7]</u>	P	16. Nickel	<u>21</u>	P
5. Beryllium	<u>0.24 U</u>	P	17. Potassium	<u>[233]</u>	P
6. Cadmium	<u>1.2 U</u>	P	18. Selenium	<u>1.2 U</u>	F
7. Calcium	<u>[251]</u>	P	19. Silver	<u>2.4 U</u>	P
8. Chromium	<u>151 J N</u>	P	20. Sodium	<u>467 U</u>	P
9. Cobalt	<u>2.4 U</u>	P	21. Thallium	<u>2.4 U</u>	F
10. Copper	<u>25</u>	P	22. Vanadium	<u>28</u>	P
11. Iron	<u>7230</u>	P	23. Zinc	<u>57</u>	P
12. Lead	<u>145</u>	F	Percent Solids (Z)	<u>83</u>	

Cyanide 0.63

Footnotes: For reporting results to EPA, standard result qualifiers are used as defined on Cover Page. Additional flags or footnotes explaining results are encouraged. Definition of such flags must be explicit and contained on Cover Page, however.

Comments: SAMPLE DESCRIPTION: SOIL, BROWN, MEDIUMPb DETERMINED AT 20X DILUTION.

Lab Manager

Steven D. Hart

IFB Amend. One

000005

Page 3 of 8

Form 1

U. S. EPA Contract Laboratory Program  
 Sample Management Office  
 P. O. Box 318 - Alexandria, VA 22313  
 703/557-2490 FTS: 3-557-2490

EPA Sample No.

MBP 666

Date 3-28-88

## INORGANIC ANALYSIS DATA SHEET

LAB NAME ANALYTICA INCORPORATEDCASE NO. 9116SOW NO. 785Lab Receipt Date 3-11-88LAB SAMPLE ID. NO.       QC REPORT NO. 4279

## Elements Identified and Measured

Concentration:

Low XMedium       Matrix: Water       Soil XSludge       Other       

ug/L or (mg/kg dry weight) (Circle One)

1. Aluminum	3930	P	13. Magnesium	[780]	P
2. Antimony	15u JN	F	14. Manganese	51	P
3. Arsenic	2.4u JN	F	15. Mercury	0.12u	CV
4. Barium	[7.6]	P	16. Nickel	20.8 <sup>unc</sup>	P
5. Beryllium	0.24u	P	17. Potassium	[341]	P
6. Cadmium	1.2u	P	18. Selenium	1.2u	F
7. Calcium	[390]	P	19. Silver	2.4u	P
8. Chromium	146 JN	P	20. Sodium	[612]	P
9. Cobalt	[2.4]	P	21. Thallium	24u 2.2 <sup>unc</sup>	F
10. Copper	25	P	22. Vanadium	29	P
11. Iron	6320	P	23. Zinc	59	P
12. Lead	127	F	Percent Solids (%)	82	

Cyanide

0.61u

Footnotes:

For reporting results to EPA, standard result qualifiers are used as defined on Cover Page. Additional flags or footnotes explaining results are encouraged. Definition of such flags must be explicit and contained on Cover Page, however.

Comments: SAMPLE DESCRIPTION: SOIL, BROWN, MEDIUMPb DETERMINED AT 20X DILUTION.

Lab Manager

Steven D. Hart

IFB Amend. One

000006

Page 4 of 8

Form I

U. S. EPA Contract Laboratory Program  
 Sample Management Office  
 P. O. Box 818 - Alexandria, VA 22313  
 703/557-2490 FTS: 8-557-2490

EPA Sample No.

MBP 667

Date 3-28-88

## INORGANIC ANALYSIS DATA SHEET

LAB NAME ANALYTICA INCORPORATEDCASE NO. 9116SOW NO. 785Lab Receipt Date 3-11-88LAB SAMPLE ID. NO.       QC REPORT NO. 4279Elements Identified and Measured

Concentration:

Low

X

Medium

Matrix: Water

Soil

X

Sludge

Other

ug/L or mg/kg dry weight (Circle One)

1. Aluminum	<u>16700</u>	P	13. Magnesium	<u>2160</u>	P
2. Antimony	<u>16 U J N</u>	F	14. Manganese	<u>155</u>	P
3. Arsenic	<u>8.8 J S N</u>	F	15. Mercury	<u>0.13 U</u>	CV
4. Barium	<u>[28]</u>	P	16. Nickel	<u>13</u>	P
5. Beryllium	<u>[0.26]</u>	P	17. Potassium	<u>[892]</u>	P
6. Cadmium	<u>1.3 U</u>	P	18. Selenium	<u>1.3 U</u>	F
7. Calcium	<u>[984]</u>	P	19. Silver	<u>3.2</u>	P
8. Chromium	<u>19 J N</u>	P	20. Sodium	<u>[655]</u>	P
9. Cobalt	<u>[4.7]</u>	P	21. Thallium	<u>2.6 U</u>	F
10. Copper	<u>17</u>	P	22. Vanadium	<u>31</u>	P
11. Iron	<u>16800</u>	P	23. Zinc	<u>58</u>	P
12. Lead	<u>36</u>	F	Percent Solids (%)	<u>76</u>	

Cyanide

0.66 U

Footnotes:

For reporting results to EPA, standard result qualifiers are used as defined on Cover Page. Additional flags or footnotes explaining results are encouraged. Definition of such flags must be explicit and contained on Cover Page, however.

Comments: SAMPLE DESCRIPTION: SOIL, BROWN, MEDIUMPb DETERMINED AT 5X DILUTION.

Lab Manager

Steven D. Hart

IFB Amend. One

000007

Page 5 of 8

Form I

U. S. EPA Contract Laboratory Program  
 Sample Management Office  
 P. O. Box 818 - Alexandria, VA 22313  
 703/557-2490 FTS: 8-557-2490

EPA Sample No.

M6P 668

Date 3-28-88

## INORGANIC ANALYSIS DATA SHEET

LAB NAME ANALYTICA INCORPORATEDCASE NO. 9116SOW NO. 785Lab Receipt Date 3-11-88LAB SAMPLE ID. NO. —QC REPORT NO. 4279

## Elements Identified and Measured

Concentration: Low X Medium         
 Matrix: Water        Soil X Sludge        Other       

ug/L or (mg/kg dry weight) (Circle One)

1. Aluminum	<u>3180</u>	P	13. Magnesium	<u>[818]</u>	P
2. Antimony	<u>134 JN</u>	F	14. Manganese	<u>104</u>	P
3. Arsenic	<u>2.24 JN</u>	F	15. Mercury	<u>0.114</u>	CV
4. Barium	<u>[15]</u>	P	16. Nickel	<u>45</u>	P
5. Beryllium	<u>0.224</u>	P	17. Potassium	<u>[569]</u>	P
6. Cadmium	<u>1.14</u>	P	18. Selenium	<u>1.14</u>	F
7. Calcium	<u>3780</u>	P	19. Silver	<u>2.9</u>	P
8. Chromium	<u>39 JN</u>	P	20. Sodium	<u>4314</u>	P
9. Cobalt	<u>[2.2]</u>	P	21. Thallium	<u>2.24</u>	F
10. Copper	<u>30</u>	P	22. Vanadium	<u>[7.3]</u>	P
11. Iron	<u>4890</u>	P	23. Zinc	<u>75</u>	P
12. Lead	<u>21</u>	F	Percent Solids (%)	<u>90</u>	

Cyanide

0.564

Footnotes:

For reporting results to EPA, standard result qualifiers are used as defined on Cover Page. Additional flags or footnotes explaining results are encouraged. Definition of such flags must be explicit and contained on Cover Page, however.

Comments: SAMPLE DESCRIPTION: SOIL, BROWN, MEDIUMPb DETERMINED AT 2X DILUTION.

Lab Manager

Steven D. Hatt

IFB Amend. One

000008

Page 6 of 8

Form I

U. S. EPA Contract Laboratory Program  
 Sample Management Office  
 P. O. Box 818 - Alexandria, VA 22313  
 703/557-2490 FTS: 9-557-2490

EPA Sample No.

MBP 669

Date 3-28-88

## INORGANIC ANALYSIS DATA SHEET

LAB NAME ANALYTICA INCORPORATEDCASE NO. 9116SOW NO. 785Lab Receipt Date 3-11-88LAB SAMPLE ID. NO. —QC REPORT NO. 4279

## Elements Identified and Measured

Concentration: Low X Medium       Matrix: Water        Soil X Sludge        Other       ug/L or mg/kg dry weight (Circle One)

1. Aluminum	<u>2510</u>	P	13. Magnesium	<u>[640]</u>	P
2. Antimony	<u>13u JN</u>	F	14. Manganese	<u>84</u>	P
3. Arsenic	<u>2.2u JN</u>	F	15. Mercury	<u>0.11u</u>	CV
4. Barium	<u>[11]</u>	P	16. Nickel	<u>20</u>	P
5. Beryllium	<u>0.22u</u>	P	17. Potassium	<u>[491]</u>	P
6. Cadmium	<u>1.1u</u>	P	18. Selenium	<u>1.1u</u>	F
7. Calcium	<u>1340</u>	P	19. Silver	<u>2.2</u>	P
8. Chromium	<u>17 JN</u>	P	20. Sodium	<u>431u</u>	P
9. Cobalt	<u>2.2u</u>	P	21. Thallium	<u>2.2u</u>	F
10. Copper	<u>20</u>	P	22. Vanadium	<u>[7.1]</u>	P
11. Iron	<u>3930</u>	P	23. Zinc	<u>37</u>	P
12. Lead	<u>13</u>	S F	Percent Solids (%)	<u>90</u>	

Cyanide 0.56 u

Footnotes: For reporting results to EPA, standard result qualifiers are used as defined on Cover Page. Additional flags or footnotes explaining results are encouraged. Definition of such flags must be explicit and contained on Cover Page, however.

Comments: SAMPLE DESCRIPTION: SOIL, BROWN, MEDIUMPb DETERMINED AT 2X DILUTION.

Lab Manager

Steven D. Hart

IFB Amend. One

000009

Page 7 of 8

Form I

U. S. EPA Contract Laboratory Program  
 Sample Management Office  
 P. O. Box 818 - Alexandria, VA 22313  
 703/557-2490 FTS: 8-557-2490

EPA Sample No.

MBP 670

Date 3-28-88

## INORGANIC ANALYSIS DATA SHEET

LAB NAME ANALYTICA INCORPORATEDCASE NO. 9116SOW NO. 785Lab Receipt Date 3-11-88LAB SAMPLE ID. NO. —QC REPORT NO. 4279Elements Identified and Measured

Concentration: Low X Medium —  
 Matrix: Water — Soil X Sludge — Other —

ug/L or (mg/kg dry weight) (Circle One)

1. Aluminum	<u>3070</u>	P	13. Magnesium	<u>[640]</u>	P
2. Antimony	<u>14U JN</u>	F	14. Manganese	<u>88</u>	P
3. Arsenic	<u>2.4U JN</u>	F	15. Mercury	<u>0.12U</u>	CV
4. Barium	<u>[9.8]</u>	P	16. Nickel	<u>206</u>	P
5. Beryllium	<u>0.24U</u>	P	17. Potassium	<u>[436]</u>	P
6. Cadmium	<u>1.2</u>	P	18. Selenium	<u>1.2U</u>	F
7. Calcium	<u>[948]</u>	P	19. Silver	<u>2.4U</u>	P
8. Chromium	<u>90 JN</u>	P	20. Sodium	<u>462U</u>	P
9. Cobalt	<u>2.4U</u>	P	21. Thallium	<u>2.4U</u>	F
10. Copper	<u>250</u>	P	22. Vanadium	<u>[8.1]</u>	P
11. Iron	<u>9190</u>	P	23. Zinc	<u>154</u>	P
12. Lead	<u>40</u>	F	Percent Solids (%)	<u>84</u>	

Cyanide 0.60U

Footnotes: For reporting results to EPA, standard result qualifiers are used as defined on Cover Page. Additional flags or footnotes explaining results are encouraged. Definition of such flags must be explicit and contained on Cover Page, however.

Comments: SAMPLE DESCRIPTION: SOIL, BROWN, MEDIUMPb DETERMINED AT 10X DILUTION.

Lab Manager

Steven D. Heath

IFB Amend. One



000010

Page 8 of 8

Form 1

U. S. EPA Contract Laboratory Program  
 Sample Management Office  
 P. O. Box 818 - Alexandria, VA 22313  
 703/557-2490 FTS: 8-357-3490

EPA Sample No.

MBP 672

Date 3-28-88

## INORGANIC ANALYSIS DATA SHEET

LAB NAME ANALYTICA INCORPORATEDCASE NO. 9116SOW NO. 785Lab Receipt Date 3-11-88LAB SAMPLE ID. NO. —QC REPORT NO. 4279

## Elements Identified and Measured

Concentration: Low X Medium —  
 Matrix: Water — Soil X Sludge — Other —

ug/L or (mg/kg dry weight) (Circle One)

1. Aluminum	<u>14800</u>	P	13. Magnesium	<u>1870</u>	P
2. Antimony	<u>14U J N F</u>		14. Manganese	<u>173</u>	P
3. Arsenic	<u>12 J S N F</u>		15. Mercury	<u>0.22</u>	CV
4. Barium	<u>5347</u>	P	16. Nickel	<u>49</u>	P
5. Beryllium	<u>50.247</u>	P	17. Potassium	<u>59837</u>	P
6. Cadmium	<u>1.4</u>	P	18. Selenium	<u>1.2U</u>	F
7. Calcium	<u>4940</u>	P	19. Silver	<u>2.4U</u>	P
8. Chromium	<u>51 J N P</u>		20. Sodium	<u>467U</u>	P
9. Cobalt	<u>55.57</u>	P	21. Thallium	<u>2.4U</u>	F
10. Copper	<u>64</u>	P	22. Vanadium	<u>28</u>	P
11. Iron	<u>15200</u>	P	23. Zinc	<u>78</u>	P
12. Lead	<u>43</u>	F	Percent Solids (%)	<u>83</u>	

Cyanide 0.60U

Footnotes: For reporting results to EPA, standard result qualifiers are used as defined on Cover Page. Additional flags or footnotes explaining results are encouraged. Definition of such flags must be explicit and contained on Cover Page, however.

Comments: SAMPLE DESCRIPTION: SOIL, BROWN, MEDIUMPb DETERMINED AT 10X DILUTION

Lab Manager



IFB Amend. One

000004

Page 1 of 1

## Form I

U. S. EPA Contract Laboratory Program  
 Sample Management Office  
 P. O. Box 818 - Alexandria, VA 22313  
 703/557-2490 FTS: 8-557-2490

EPA Sample No.

MBP 671

Date 3-23-88

## INORGANIC ANALYSIS DATA SHEET

LAB NAME ANALYTICA INCORPORATEDCASE NO. 9116SOW NO. 785Lab Receipt Date 42<sup>nd</sup> 3-11-88LAB SAMPLE ID. NO. —QC REPORT NO. 4278

## Elements Identified and Measured

Concentration: Low X Medium —Matrix: Water X Soil — Sludge — Other —

(ug/L or mg/kg dry weight (Circle One))

1. Aluminum	<u>51277</u>	P	13. Magnesium	<u>51147</u>	P
2. Antimony	<u>160U</u>	F	14. Manganese	<u>3U</u>	P
3. Arsenic	<u>10U</u>	F	15. Mercury	<u>0.2U</u>	CV
4. Barium	<u>9U</u>	P	16. Nickel	<u>9U</u>	P
5. Beryllium	<u>7U</u>	P	17. Potassium	<u>797U</u>	P
6. Cadmium	<u>5U</u>	P	18. Selenium	<u>5U</u>	F
7. Calcium	<u>296U</u>	P	19. Silver	<u>10U</u>	P
8. Chromium	<u>10U</u>	P	20. Sodium	<u>1940U</u>	P
9. Cobalt	<u>10U</u>	P	21. Thallium	<u>10U</u>	F
10. Copper	<u>13U</u>	P	22. Vanadium	<u>8U</u>	P
11. Iron	<u>5267</u>	P	23. Zinc	<u>5197</u>	P
12. Lead	<u>5U</u>	F	Percent Solids (%)	<u>NR</u>	

Cyanide 10U

Footnotes: For reporting results to EPA, standard result qualifiers are used as defined on Cover Page. Additional flags or footnotes explaining results are encouraged. Definition of such flags must be explicit and contained on Cover Page, however.

Comments: SAMPLE DESCRIPTION: WATER, CLEAR & COLORLESSRINSTATE BLANKLab Manager 

IFB Amend. One

**REFERENCE NO. 26**

## NUS CORPORATION AND SUBSIDIARIES

TELECON NOTE

CONTROL NO:

DATE:

2/1/89

TIME:

1350 HRS

DISTRIBUTION:

JOHN HASSALL TEL

-DD # 02-8901-25

BETWEEN:

J. SCHERTER

OF: NASSAU CO.

HEALTH DEPT.

PHONE:

(516) 535-2406

AND:

E. LEONARD (NUS CORP.)

DISCUSSION:

RE: DECEMBER 1987 SPILL

o MARCH 21, 1988 VISUAL INSPECTION  
TO VERIFY SPILL.

o AUGUST 11, 1988 SAMPLING

- OLD SOIL ~5 FEET FROM TANK B ~6 INCHES  
DEEP. NON-DETECT ON VOLATILES

- NEW SOIL ~6 INCHES DEEP. NON-DETECT  
ON VOLATILES. SEVERAL UNIDENTIFIED  
PEAKS

- DURING SAMPLING OUTFLOW OF TANK NO. 11,  
IT WAS OILY WATER.

ACTION ITEMS:

o ALL UNDERGROUND TANKS (CONCRETE) FROM  
WASTE WATER TREATMENT SYSTEM WERE  
LEAK TESTED IN 1988. TEST WERE  
INCONCLUSIVE, AND TANK ASSUMED TO BE  
UNSOUND.

NUS CORPORATION AND SUBSIDIARIES

TELECON NOTE

CONTROL NO:

DATE:

2/1/89

TIME:

1350 HRS

DISTRIBUTION:

JOHN NASSAU

CO # 028901-25

BETWEEN:

J. SCHOLTER

OF: NASSAU CO.

MOBILE DEPT

PHONE:

(516) 535-2406

AND:

E. LEONARD (NUS CORP.)

DISCUSSION:

RE: DECEMBER 1987 SPILL

• APPROXIMATELY FOUR TANKS ARE PRESENTLY OUT OF SERVICE. THE REMAINING TANKS ARE STILL BEING TESTED. IF THEY ARE DETERMINED TO BE LEAKING, FURTHER INVESTIGATIONS WILL BE PERFORMED (SOIL BORINGS).


• ALL TANK EVENTUALLY TO BE CERTIFIED AS NOT LEAKING, OR REPLACED WITH DOUBLE WALLED TANKS.


E. Leonard 2/1/89


ACTION ITEMS:

**REFERENCE NO. 27**





	TITLE: THREE MILE VICINITY MAP	
	SITE : JOHN HASSAL INC. WESTBURY, N.Y.	
DATE : 2/22/88	TDD : 02-8802-07	
QUAD : HICKSVILLE, N.Y.	FIGURE NUMBER:	SCALE: 1"=2000'



CONTOUR INTERVAL 5 FEET  
NATIONAL GEODETIC VERTICAL DATUM OF 1929  
DEPTH CURVES AND SOUNDINGS IN FEET—DATUM IS MEAN LOW WATER  
THE RELATIONSHIP BETWEEN THE TWO DATUMS IS VARIABLE  
SHORELINE SHOWN REPRESENTS THE APPROXIMATE LINE OF MEAN HIGH WATER  
THE MEAN RANGE OF TIDE IS APPROXIMATELY 2.7 FEET